T1 (FALSE ACACIA) CROWN LIFT TO 5m. T2 (ROWAN) CROWN LIFT TO 5m. T3 (ASH) SAPLIN TO FELL. G1 (ELDER + HAWTHORNE) CROWN LIFT ON INSIDE OF BOUNDARY. FELL SECOND ELDER. T4 (CONIFER) TO FELL AND REPLACE WITH CHESNUT OR BIRCH. T5 (SYCAMORE) TO FELL. T6 T7 T8 (OAK) REMOVE STUBS + STUB ENDS BACK TO DECENT GROWTH + DEADWOOD. W1 CROWN CLEAN WHERE NESSESARY + FELL DEAD OAKS G2 FELL (CONIFERS) REPLACE WITH HAWTHORNE T9 (PISSARD)PLUM) REDUCE BRANCHES BACK AWAY FROM WINDOWS OF HOUSE.