

Proposed Drainage Strategy

PERSEVERANCE STREET, BARNSELEY

CAIRNWELL DEVELOPMENTS LTD

Rev.B – September 2024



PROPOSED DRAINAGE STRATEGY

PERSEVERANCE STREET, BARNSELY

FOR

CAIRNWELL DEVELOPMENTS LIMITED

48063-ECE-XX-XX-RP-C-0005

Rev.B - September 2024

Eastwood Consulting Engineers is a trading name of Eastwood and Partners (Consulting Engineers) Limited
Registered Office: St Andrew's House, 23 Kingfield Road, Sheffield, S11 9AS, Company No: 1835021, VAT Registration No: 738 2114 44

Directors: S R Ellis BEng CEng MStructE MICE I S J English BEng CEng MStructE I C A Topliss BSc CEnv CSci CGeol SiLC FICE FGS
A R Priest BEng I A G Marshall BEng CEng MStructE

Technical Directors: A Allison BEng I M P Chappell BEng CEng MStructE I K Edwards MSci CGeol FGS
C Hodge EngTech MICE I A J Kerslake BEng FGS

Senior Associates: C A Wood BSc CEng MStructE MICE

Associates/Principals: A M Cross MEng CEng MICE I A Lavelle MEng CEng MICE I R A Noble BSc FGS I C L Capes BSc FGS I R Wall BSc CGeol FGS
W T Chidawanyika BSc CEng MIEI MICE I A J Cartlidge MEng I C J Burgoyne BSc IEng MICE I G C Burgin BSc MSc FGS

Consultants: P Richardson BSc CEng MICE FStructE I S D Preston BEng CEng FICE FStructE I K R Pursall BEng CEng MStructE

PROPOSED DRAINAGE STRATEGY
PERSEVERANCE STREET, BARNSELEY
FOR
CAIRNWELL DEVELOPMENTS LIMITED

Introduction

The proposals involve the construction of a care home facility on a 0.26 Ha site. The proposed site layout is shown on Watson Batty Architects Drg. No 90100 P3 (Appendix 1).

Existing Site

The site is a disused car park which is thought to have been constructed in the mid 2000's and is accessed from Perseverance Street to the east, as shown on the appended Survey Solutions Drg. No. 48285NGLS-01 (Appendix 2). The site is almost entirely hard paved with small overgrown landscaped areas around the perimeter and within islands at the ends of the parking bays. Several bushes have also now become established within the site, predominantly rooted within drainage gullies.

Existing Surface Water Drainage

The appended Yorkshire Water record plan (Appendix 3) shows there to be combined sewers within the site as well as surface water and combined sewers within Perseverance Street to the east and Springfield Street to the south. The sewers within the site are a 375 dia. combined running west to east and two combined sewers entering from the south and discharging to the 375 dia. combined sewer.

Two separate CCTV drainage surveys have been undertaken. The first survey was undertaken by Survey Solutions (Appendix 4) and established that the manholes identified by the topographical survey are associated with the former car park use.

The later survey was carried out by Drain Doctor (Appendix 5) and established the presence of the combined sewers within the site. The two combined sewers running south to north within the site were both found to be 150 dia.

Reading the Survey Solutions report (Appendix 4) alongside surveys undertaken as part of a previous site appraisal for an unrelated development proposal, it has been established that the on-site gullies are connected to a below ground drainage system which conveys run-off through a petrol interceptor and into a 1.4m dia. proprietary galvanised steel pipe with access shafts at both ends. At the northern end is a flow control device and an outfall pipe believed to discharge to a culverted watercourse running west to east within the site close to the northern boundary. The rate at which the discharge from the site is currently restricted is not known. The purpose of the large diameter pipe is to provide storage for the volumes of water held back by the flow control device.

Existing Foul Drainage

There is currently no foul discharge from the site. As discussed previously, there are combined sewers within and around the site.

Proposed Sewer Abandonment

The existing 375 dia. combined sewer and culverted watercourse which both cross the site will be unaffected by the development, with the building positioned at least 6m from the sewer.

The Drain Doctor CCTV survey (Appendix 5) and subsequent monitoring of the two 150 dia. on-site combined sewers has confirmed that they both discharge into the 375 dia combined sewer. The eastern of the two sewers has been found to serve two residential properties at the junction of Perseverance Street and Springfield Street. The western sewer does not appear to have any live connections, as no flow has been observed over a period of time, and it is assumed that the served the former terraced housing which occupied the that part of the site.

Due to site constraints, diversion of the eastern live sewer has been discounted, with discussions ongoing with Yorkshire Water to enter into a Build Over Agreement. It is proposed that the western redundant sewer is to be abandoned, with an application to Yorkshire Water to be made in due course.

Proposed Surface Water Drainage

In accordance with National Policy, consideration should initially be given to the discharge of surface water to ground via soakaways or other infiltration methods.

A Phase 2 site investigation report on the site states that varying depths of made ground up to 3.8m deep was encountered, along with backfilled basements associated with former terraced housing. The underlying natural ground was found to be typically a clay material. The solid geology beneath the site is expected to comprise the Pennine Middle Coal Measures (i.e interbedded mudstone, siltstone and sandstone with coal seams). Given the depth of the made ground and underlying cohesive natural strata, the report concludes that disposal of surface water via soakaways is not considered viable on the site.

Therefore, it is proposed that surface water from the site is discharged to the existing culverted watercourse which runs west to east within the site, close to the northern boundary. This maintains the existing drainage arrangement.

As shown on sheet SW1 (Appendix 6), the existing impermeable area which is positively drained to the watercourse is taken to be 2,320 m². Assuming a rainfall intensity of 50 mm/hour, the unrestricted discharge rate from the site would be approximately 32 litres/second.

The parameters which were used when the existing flow control device and attenuation storage were originally designed are not known, i.e return period rainfall event, maximum discharge rate, design head etc. The volume of storage available within the large pipe is calculated to be approximately 45 m³ (1.4m dia. x 29m long).

As a sense check, calculations have been produced showing the estimated maximum flow rate which would need to be imposed in order to completely fill the storage during two likely design return periods, see Sheets SW2A & SW3A (Appendix 7). For the 1 in 30 year return period this is 5 litres/second, increasing to 11 litres/second for the 1 in 100 year return period.

The lower rate is typical of the “minimum practical” rate for flow control devices which was widely taken at the time of installation. It is therefore proposed that the rate at which surface water from the development be discharged is restricted to **5 litres/second**.

It is proposed that the existing flow control device is replaced with a new device with a known design rate and with a design head appropriate for the proposed site levels.

Sheet SW4B (Appendix 8) shows that the proposed impermeable area positively drained is 1,840 m². It is proposed that attenuated volumes of run-off are retained on site for all rainfall events up to and including the 1 in 100 year return period plus an allowance of 40% for climate change. The appended calculation sheet SW5B (Appendix 9) shows that 95 m³ of storage is required in order to prevent flooding from the site with the above design criteria.

It is proposed that the existing large diameter storage pipe is retained, with additional storage provided within proprietary below ground voided storage units located to the west of the care home building. As the existing pipe provides 45 m³ of storage, an additional 50 m³ of new storage is therefore required.

All run-off from external parking areas is to be passed through a new suitably sized Class 1 by-pass separator with vent pipe and high-level alarm. Roof water will not pass through the separator.

Proposed Foul Drainage

All foul discharge from the proposed development is to be collected within a traditional gravity system and conveyed to both the 375 dia. combined sewer to the north of the proposed care home and to the retained 150 dia. combined sewer at the south of the building.

Proposed Drainage Strategy Plan

An external drainage layout Drg. No. 48063-ECE-XX-XX-DR-C-0061-P04 is appended (Appendix 10), showing the proposals for foul and surface water disposal based upon the strategies described above.

Flood Routing

External surfacing levels are set to fall away from the building locally. Should rainfall events exceed the design condition or should there be a blockage within the flow control device, then flooding will occur from the lowest point of the system, which will be a gully/gullies located within the turning head at the north west corner of the site. Ponding will then occur at this location before overtopping the perimeter kerbing and flowing from the site into the open watercourse to the west, maintaining the existing flood routing. The maximum flood water area will be more than 2m below the proposed care home floor level.



Proposed Maintenance

The existing adopted combined sewers within and around the site will continue to be maintained by Yorkshire Water. The new foul and surface water drainage systems are to remain private and will be maintained by the Care Home Management in accordance with the appended Maintenance Schedule (Appendix 11).

APPENDICES

1. Watson Batty Architects	Proposed Site Plan 90100 P3
2. Survey Solutions	Topographical Survey 48285NGLS-01
3. Yorkshire Water	Sewer Record
4. Survey Solutions	CCTV drainage survey
5. Drain Doctor	CCTV drainage survey
6. Eastwood Consulting Engineers	Existing Impermeable Areas Plan SW1
7. Eastwood Consulting Engineers	Existing flow rate calculations SW2A & SW3A
8. Eastwood Consulting Engineers	Proposed Impermeable Areas Plan SW4B
9. Eastwood Consulting Engineers	Proposed storage volume calculation SW5B
10. Eastwood Consulting Engineers	External Drainage Layout
11. Eastwood Consulting Engineers	External Drainage Maintenance Schedule

APPENDIX 1



KEY

Red Line Site Boundary

TREES



Proposed Trees, please refer to Amenity Tree's 'Proposed Landscaping Planting Plans' Drawing

BOUNDARY CONDITION

Proposed 2100mm High Close Boarded Timber Fence

Proposed 1800mm High Close Boarded Timber Fence



Approximate Location of Existing Fire Hydrant on Perseverance Street

FOR ALL LANDSCAPING DETAILS REFER TO AMENITY TREE'S LANDSCAPING PLANTING & HARDWORKS DRAWING'S.

FOR EXACT LOCATION OF EXISTING SEWER & CULVERT SHOWN PLEASE REFER TO 1st HORIZON SURVEYING AND ENGINEERING Ltd SURVEY REFERENCE: 'SPRINGFIELD STREET, TOPOGRAPHIC SURVEY

FOR ALL PROPOSED EXTERNAL SITE LEVELS DETAILS PLEASE REFER TO EASTWOODS STRUCTURAL & CIVIL CONSULTANT'S DRAWING'S.

FOR ALL EXISTING SHRUBS, REFER TO REPORT: 'TREE SURVEY AND CONSTRAINTS REPORT' BY AMENITY TREE

FOR ALL WORKS TO TREES, ECOLOGY & LANDSCAPING REFER TO AMENITY TREE'S APPROVED REPORTS REF: 'TREE SURVEY AND CONSTRAINTS' REPORT, 'BIODIVERSITY ENHANCEMENT MEASURES' REPORT, 'ASSESSMENT OF BIODIVERSITY' REPORT, 'PRELIMINARY ECOLOGICAL APPRAISAL' REPORT, 'A.I.A' REPORT AND 'EXTENDED PHASE ONE HABITAT SURVEY'

DECOMMISSIONING (AND ASSOCIATED WWORKS) OF ALL EXISTING ELECTRICAL ITEMS ON THE SITE - LAMPOSTS, LIGHTING UNITS ETC TO BE UNDERTAKEN BY THE CONTRACTOR

SITE PLAN LAYOUT SUBJECT TO PLANNING APPROVAL, BUILDING CONTROL AND OTHER STATUTORY APPROVALS.

Revision: P3 Date: 16/05/2024 Drawn: NM Checked: GB

Site layout updated as per Planning Application Layout

Revision: P2 Date: 13/03/2024 Drawn: CB Checked: NM

Tender Issue

Revision: P1 Date: July 2023 Drawn: NM Checked: GB

Position of Secure Line Fence to east side of Site moved. Garden Shed location updated. Secure Line to Western side of site moved north.

Suitability:

D2

Tender

Residential Care Home

Proposed Site Plan

Location:
Perseverance Street
BARNLEY

Client:
Exemplar Healthcare

UPRN Originator Zone Level Type Role Number Revision

PERSE WBA SI ZZ DR A 90100 P3


Date: 13/07/23 Drawn: NM Checked: GB Scale: 1:200@A1 Int. Job No: 4009_022

CAD REF:

WATSON BATTY
ARCHITECTS

Shires House, Shires Road
Guiseley, Leeds LS20 8EU
Leeds | Loughborough

T: 01943 876 665
E: enquiries@watsonbatty.com
W: www.watsonbatty.com




FUTURE BUILT

Note: Do not Scale from this drawing. All dimensions to be checked on site.

APPENDIX 2



APPENDIX 3



Public Waste Water Network 24/03/2023 14:14:25 OS Grid Coordinates: 433627 : 406304 Map Name : SE3306SE svcGISSafeMovePD

APPENDIX 4

Q-LEVEL	DESCRIPTION	ACC.	Q-LEVEL	DESCRIPTION
QL-D	Service positions taken from records	3 or greater	QL-B2	Perforated & vertical location using only one physical technique
QL-C	Visual evidence of service entrance but not identified by geographic technology	3 or greater	QL-B1	Perforated & vertical location using multiple physical techniques
QL-B4	Undetectable service proven shown as an assumed entry point	3 or greater	QL-A	Perforated & vertical location verification by spin excavation, triangulation and/or inspection chamber
QL-B3	Perforance location by one geophysical technique but with no or poor depth information	3 or greater		

DRAINAGE SURVEY

All accessible Manholes and Inspection chambers have had their respective covers lifted with pipe sizes, inverts, chamber sizes/types and service data recorded from ground level. All connections from DP's, Gullies, Drains, VP's, RE's and lampholes have been proven wherever possible using audible connections (AC) and/or sonde instrumentation where applicable. Where these methods have proved unsuccessful then assumed (AR) straight line connections will be shown.

All accessible Manholes and Inspection chambers have had their respective covers lifted with pipe sizes, inverts, chamber sizes/type and service data recorded from ground level. Pipework has been traced, accessed and collected for post processing. Drainage layout, including manhole covers not located by topographical survey, may be taken from CCTV chainage and will be shown as indicative only.

Elec cables will have been predominantly located using EML methodology with electronically derived depths shown. GPR techniques will be employed to achieve greater quality levels as required.

BT cables will have been predominantly located using EML methodology with electronically derived depths shown. GPR techniques will be employed to achieve greater quality levels as required. Due to current laws and legislation protecting all BT apparatus, cabling can only be located remotely. We therefore compare all our telecom findings against record information to produce the final service layout. In some instances, where high amount of cable ducts are present, we may only be able to identify a linear centre peak signal rather than identifying all the individual duct positions. For further information regarding Telecoms apparatus, please contact Openreach directly.

CTV and/or Com cables will have been predominantly located using EML methodology with electronically derived depths shown. GPR techniques will be employed to achieve greater quality levels as required.

FO cables will have been predominantly located using GPR methodology. This is due to the materials used within fibre optic cabling. In some rare instances, tracer cabling or conductive non fibre optic cabling will be present within some or all ducting. When this is the case, both EML and GPR methodology will be combined to identify service network and achieve greater quality levels.

LC, TS and/or Sec cables will have been predominantly located using EML methodology with electronically derived depths shown. GPR techniques will be employed to achieve greater quality levels as required.

GM/GS and/or WM/WS pipe work will have been attempted and located using both EML & GPR methodology with electronically derived depths shown for the former and depths to crown levels shown for the latter.

When the Gas/Water pipe work is constructed using conductible materials, then we are able to employ multiple geophysical techniques to identify service network and achieve greater quality levels. When a non conductible material is used, GPR methodology will be employed to locate and plot the final service layout.

GPR methodology used to identify and locate all non metallic, non conductive piping and cabling. We also employ GPR to obtain a greater accuracy levels on EML located services. The GPR has a greater success rate on pipe or service diameter upward of Ø63mm, C63mm, as size increments increase, so does the chance of detection. The GPR can produces varying results and as such, wouldn't be used as an independent utility surveying instrument.

All UITS will have been predominantly located using EML methodology with electronically derived depths shown. GPR techniques will be employed to achieve greater quality levels as required. Every effort has been made to identify the service but in this instance, is not achievable. We recommend excavation work to determine identity and depth where applicable.


Scarring has been identified on site with a potential of an undetectable service present.

Assumed routes (AR) are shown if there is evidence that a service exists but we are unable to trace it whilst on site. The surveyor will attempt to locate various risers/ics/valves/meters (service evidence) etc. around site area to successfully determine an assumed route between these points. If there is little evidence on site but they believe a service is still present, then a common sense approach to an assumed route shall be employed.

Taken from records (TFR) are service routes that are taken from STAT record plans or previous survey information and overlaid onto our drawings.


We recommend full statutory record information be obtained to confirm site findings and to position undetectable which may be present.

Due to the geophysical nature of subsurface technology, we always recommend excavation works to be carried out within critical areas for verification and to eliminate the possibility of undetectable services present.



ABBREVIATIONS & SYMBOLS

PS	1 Duct & Cables	DC	Depth To Crown	RRC	Rectangular Brick Chamber
PS	2 Duct & Cables	DCI	Depth To Invert	RCC	Rectangular Brick Chamber
AC	Access Connection	DS	Depth To SR	RE	Rodding Eye
AG	Above Ground	DTB	Depth To Base	SA	Surface Abandoned
AR	Asbestos Road	DTW	Depth To Water	SL	SL Level
BL	Base Level	DTS	Depth To Surface	SUL	Surface Level
CB	Circular Benching	EBO	End External Bore	TRR	Transfer From Records
CC	Circular Brick Chamber	EOT	End of Trade →	UTC	Unable To CCTV
CC	Circular Chamber	ES	End of Service	UTOD	Unable To Determine O.D.
CL	Cover Level	IL	Invert Level	UTL	Unable To Lift
CP	Circ. Plastic Chamber	OH	Overhead	UTS	Unable To Survey
CL	Cover Level	PR	Poor Depth Response	UTL	Unable To Trace
CL	Covers Under Way	RB	Red Bent	WL	Water Level
				CMC	Circular Metal Chamber
		BT (CABLE)			
GET		OVERHEAD (CABLE)			
COM		COMMUNICATION (CABLE)			
CTV		CABLE TV (CABLE)			
EM		EMPTY (CABLE)			
E		ELECTRIC (CABLE)			
OE		OVERHEAD (ELECTRIC CABLE)			
FB		FIBRE OPTIC (CABLE)			
FUEL		FUEL PIPES			
GAS		GAS MAIN			
GS		GAS SERVICE			
GR		GROUND PENETRATING RADAR (GPR) TRACE			
HW		HOT WATER PIPE			
LI		LIGHTING (CIRCUIT)			
LI		LIGHTING (PIPE)			
SCAM		VISIBLE SCANNING			
TR		TRAFFIC LIGHTING			
TE		TELECOM CABLES			
TR		TRAFFIC LIGHTS			
UN		UNIDENTIFIED SERVICE			
UT		UNKNOWN TRACE			
WA		WATER MAIN			
WA		WATER SERVICE			
COMB		COMBINED WATER			
EFF		EFFLUENT			
FL		FALL SEWER			
FL		FALL WATER RISING MAIN			
FL		RISING MAIN			
FL		SURFACE WATER SEWER			
FL		SURFACE WATER RISING MAIN			
FL		INVESTIGATION EXTENTS			



DRAWING NOTES

All below ground details shown have been identified from above ground without excavation. Survey Solution use electro-magnetic and/or ground penetrating radar (GPR) methods to investigate for underground utilities, services and features. Results using these methods are not infallible and we recommend trial excavations are carried out to confirm any identifications, positions and depths.

Any areas on the drawing where services or features have not been shown are not necessarily clear of services or features but are an indication that no items have been identified during our investigations. All reasonable care and normal good practice should still be employed during design and construction processes.

Certain types of services such as plastic or concrete pipes, some conduit and ducting where direct access can not be achieved for tracing may not be shown and alternative locating methods should be used.

Survey Solutions has used all reasonable care to research available service records, but the completeness or use of the service records supplied to or by Survey Solutions cannot be guaranteed. Therefore Survey Solutions cannot be held responsible for any features annotated as 'taken from records' (TFR).

Depths obtained using electro-magnetic or GPR are effected by ground conditions and should be treated as indicative only. Electro-magnetic depths to utilities and services are generally taken to the centre of a feature, GPR depths to the top of a feature and drainage depth shown to inverts, unless otherwise indicated.

Drainage pipe sizes will be obtained without entering the chamber and therefore should be treated as approximate. Pipe dimensions which have not been obtained visually will be taken from records when available.

All services, drainage and utilities routes are assumed straight between access points, unless otherwise stated. The numbers of cables in runs will not be shown unless specifically requested. All services are below ground unless indicated.

Services, utilities and features may not have been surveyed if obstructed or not reasonably visible or accessible at the time of survey.

Survey Solutions accept no responsibility for the completeness or accuracy of either the topographical survey or base mapping on this project.

All critical dimensions and measurements should be checked and verified with any errors or discrepancies notified to Survey Solutions immediately. The accuracy of the digital data is the same as the plotting scale implies. All dimensions are in metres unless otherwise stated.

The contractor must check and verify all site and building dimensions, levels, utilities and drainage details and connections prior to commencing work.

© Land Survey Solutions Limited hold the copyright to all the information contained within this document and their written consent must be obtained before copying or using the data other than for the purpose it was originally supplied.

Do not scale from this drawing

This survey has been carried out in accordance with PAS 128: 2014 & our version of the Royal Institution of Chartered Surveyors (RICS) specification for Measured Surveys of Land, Buildings and Utilities. Our survey extents have been agreed and confirmed with formal acceptance of 63949 from Exemplar Health Services Ltd. If you have any queries regarding the final services layout, please may we ask you to carefully read all the information within this title block in its entirety before continuing to do so.

TOPOGRAPHICAL/DWG DRAWING INFORMATION		
TOPOGRAPHICAL SURVEY DATE 02/02/2013		
SURVEY TYPE	DESCRIPTION	EFFECT ON SURVEY RESULTS
TOPO	Survey Solutions	
OUTDATED		
CS		
NTS		

GENERAL SITE CONDITIONS	
AVERAGE	
ADDITIONAL INFORMATION	EFFECT ON SURVEY RESULTS

DESKTOP UTILITY RECORDS (PAS 128: 2014 SURVEY TYPE D)		
PREREQUISITE FOR PAS 128: 2014 SURVEY TYPE B		
COMMISSIONED: YES		
UTILITY	AVAILABILITY	UTILITY COMPANY PROVIDER
SEWER	NO	N/A
WATER MAIN	NO	N/A
GAS MAIN	PUBLIC	CADENT GAS
TELECOM	PUBLIC	BRITISH TELECOMS
CABLE TV	NO	N/A
ELECTRICITY	NO	N/A
OIL PIPES	NO	N/A
OTHER	NO	N/A

A	ADDITIONAL SURVEY INFORMATION ADDED.	RDN	JTM	JTM	22/03/2023
REV	DESCRIPTION	DRAWN	CHECKED	APPR	SURVEY DATE



PROJECT TITLE LAND OFF PERSEVERANCE STREET, BARNSELEY, S70 6HH.				
DRAWING DETAIL UTILITIES AND CCTV DRAINAGE SURVEY. SHEET 1 OF 1				
CLIENT EXEMPLAR HEALTHCARE SERVICES LTD				SCALE 1:200
OWNER/JR SMD/JR	SURVEY DATE 01/03/2023	CHECKED BY RDN	APPROVED BY JTM	DWG STATUS FINAL
DRAWING NUMBER 48285NGUG-01			REVISION A	ISSUE DATE 17/03/2023



CCTV Report



Project

Land off Perseverance street,
Barnsley, S70 6HH.

Survey Date

01/03/2023

Client

Exemplar Healthcare Services Ltd

Checked by

RDN

Surveyor

DJR

Revision - Issue Date

Job Number

48285CCTV-01

Issue Date

17/03/2023

LAND SURVEYING
BUILDING SURVEYING
UNDERGROUND SURVEYING
SITE ENGINEERING
MONITORING

IPSWICH

BRENTWOOD

COVENTRY

GLASGOW





Project-information

Project name:
SPST Barnsley

Contract number:
48285

Contact:
Gregg Harris

Date:
13/03/2023

Client **Exemplar Healthcare Services Limited**
 Contact: **Gregg Harris**
 Position:
 Road **Kimberworth Road**
 Town **Rotherham**
 County **South Yorkshire**
 Telephone:
 Fax:
 Mobile: **07398508876**
 E-Mail: **gharris@exemplarhc.com**

Site **ST Barnsley**
 Contact: **Gregg Harris**
 Position:
 Road **Springfield Street S70 6HH**
 Town **Barnsley**
 County **South Yorkshire**
 Telephone:
 Fax:
 Mobile:
 E-Mail:

Contractor **Survey Solutions**
 Contact: **Daniel Richardson**
 Position: **Surveyor**
 Road **6 Farringdon Way**
 Town **Eastwood, NG16 3BF**
 County **Nottinghamshire**
 Telephone:
 Fax:
 Mobile:
 E-Mail: **Nottingham.office@survey-solutions.co.uk**



Defect Grade Description

Project name:
SPST Barnsley

Contract number:
48285

Contact:
Gregg Harris

Date:
13/03/2023

1:

Brick: No Structural Defects
 Pipe: No Structural Defects

Acceptable Structural Condition

2:

Brick: Minor cracking, Surface mortar loss, Spalling slight, wear slight
 Pipe: Circumfrential crack, Moderate joint defects, Spalling slight, Wear slight

Minor collapse risk in short term but potential for further deterioration

3:

Brick: Total mortarloss without other defects, single brick displaced, Deformation up to 5%, Spalling medium, Wear medium
 Pipe: Fractures with deformation up tp 5%, Longitudinal cracking or mulitple cracking, Minor loss of level, More severe joint defects, Spalling medium, Wear medium

! Collapse unlikely in near future but future deterioration likely !

4:

Brick: Total mortarloss with deformation greater than 10%, Deformation up to 10% and fractured, Displaced/hanging brickwork, Small number of missing bricks
 Pipe: Broken, Deformation up to 10% and broken,, Fractured with deformation 5 - 10%, Multiple fractures, Serious loss of level, spalling large, wear large

!! Collapse likely in foreseeable future !!

5:

Brick: Already Collapsed, Missing invert, Deformation over 10% and fractured, Displaced/hanging brickwork and deformation over 10%, Extensive missing bricks
 Pipe: Already collapsed, Deformation over 10% and broken, Extensive areas of fabric missing, Fractured with deformation over 10%

!!! Collapsed or collapse imminent !!!



Survey Solutions
 Eastwood, NG16 3BF
 Nottinghamshire
 Tel: , Fax:

Inspection report

Date: 13/03/2023	Job N°:	Weather: Showers	Operator:	section number: 1	PLR: ? X
Present:	Vehicle:	Camera: SOLO PRO	Preset:	Cleaned: No	Grade:

Road: Springfield Street	Division:	start MH: MH1 A
Place: St, Barnsley	District:	end MH:
Location:	Tape No.:	Total length: 12 m

Purpose: Asset condition	Shape/Size: dia 150 mm
Use: Surface water	Material: Polypropylene Pipe length:
Catchment:	Lining:
	Category:

Comment:

Location details:

1:100	position	code	observation	counter	photo	grade
	0.00	MH	Manhole Remark: MH1 A	00:00:00		(Constr) 0
	0.00	ST	Start of Survey	00:00:00		(Misc) 0
	0.00	WL	Water level, 0 % height/diameter	00:00:00		(Serv) 0
	0.70	LR	Line of Sewer deviates right	00:00:00		(Serv) 0
	5.00	GP	General Condition photograph	00:00:00	5_5a	(Misc) 0
	10.00	GP	General Condition photograph	00:00:00	6_6a	(Misc) 0
	11.20	LR	Line of Sewer deviates right	00:00:00		(Serv) 0
	12.00	FH	Finish Survey, Remark: Gully reached.	00:00:00		(Misc) 0

Structural Defects

Constructional Features

Service Defects

Miscellaneous Features

Inspection photosPlace:
St, BarnsleyRoad:
Springfield StreetDate:
13/03/2023section number:
1PLR:
? X

Photo: 5_5a, 00:00:00
5m, General Condition photograph



Photo: 6_6a, 00:00:00
10m, General Condition photograph



Survey Solutions
Eastwood, NG16 3BF
Nottinghamshire
Tel: , Fax:

Inspection report

Date: 13/03/2023	Job N°:	Weather: Showers	Operator:	section number: 2	PLR: MH1 X X
Present:	Vehicle:	Camera: SOLO PRO	Preset:	Cleaned: No	Grade:

Road: Springfield Street	Division:	start MH: MH1 X
Place: St, Barnsley	District:	end MH: MH4
Location:	Tape No.:	Total length: 20 m

Purpose: Asset condition	Shape/Size: dia 225 mm
Use: Surface water	Material: Polypropylene Pipe length:
Catchment:	Lining:
	Category:

Comment:
Location details:

1:150	position	code	observation	counter	photo	grade
	0.00	MH	Manhole Remark: MH1 X	00:00:00		(Constr) 0
	0.00	ST	Start of Survey	00:00:00		(Misc) 0
	0.00	WL	Water level, 0 % height/diameter	00:00:00		(Serv) 0
	3.40	JN	Junction at 02 o'clock, dia 100 mm	00:00:00	12_4a	(Constr) 0
	8.00	GP	General Condition photograph	00:00:00	13_5a	(Misc) 0
	9.70	JN	Junction at 03 o'clock, dia 100 mm	00:00:00	14_6a	(Constr) 0
	9.90	JN	Junction at 10 o'clock, dia 100 mm	00:00:00	15_7a	(Constr) 0
	14.10	JN	Junction at 03 o'clock, dia 100 mm	00:00:00	16_8a	(Constr) 0
	19.00	JN	Junction at 09 o'clock, dia 100 mm	00:00:00	17_9a	(Constr) 0
	20.00	FH	Finish Survey, Remark: MH4 Reached.	00:00:00		(Misc) 0

Structural Defects	Constructional Features
Service Defects	Miscellaneous Features

Inspection photos

 Place:
St, Barnsley

 Road:
Springfield Street

 Date:
13/03/2023

 section number:
2

 PLR:
MH1 X X


Photo: 12_4a, 00:00:00
 3.4m, Junction at 02 o'clock, dia 100 mm



Photo: 13_5a, 00:00:00
 8m, General Condition photograph



Photo: 14_6a, 00:00:00
 9.7m, Junction at 03 o'clock, dia 100 mm




Photo: 15_7a, 00:00:00
 9.9m, Junction at 10 o'clock, dia 100 mm

Inspection photosPlace:
St, BarnsleyRoad:
Springfield StreetDate:
13/03/2023section number:
2PLR:
MH1 X X

Photo: 16_8a, 00:00:00
14.1m, Junction at 03 o'clock, dia 100 mm



Photo: 17_9a, 00:00:00
19m, Junction at 09 o'clock, dia 100 mm



Survey Solutions
 Eastwood, NG16 3BF
 Nottinghamshire
 Tel: , Fax:

Inspection report

Date: 13/03/2023	Job N°:	Weather: Showers	Operator:	section number: 3	PLR: ? X
Present:	Vehicle:	Camera: SOLO PRO	Preset:	Cleaned: No	Grade:

Road: Springfield Street	Division:	start MH: MH3 A
Place: St, Barnsley	District:	end MH:
Location:	Tape No.:	Total length: 7.5 m

Purpose: Asset condition	Shape/Size: dia 225 mm
Use: Surface water	Material: Polypropylene Pipe length:
Catchment:	Lining:
	Category:

Comment:

Location details:

1:75	position	code	observation	counter	photo	grade
	0.00	MH	Manhole Remark: MH3 A	00:00:00		(Constr) 0
	0.00	ST	Start of Survey	00:00:00		(Misc) 0
	0.00	WL	Water level, 15 % height/diameter	00:00:00		(Serv) 0
	2.50	GP	General Condition photograph	00:00:00	24_4a	(Misc) 0
	5.00	GP	General Condition photograph	00:00:00	3_5a	(Misc) 0
	7.50	OB	Obstruction, 80 % height/diameter loss	00:00:00	3_6a	(Serv) 2
	7.50	SA	Survey abandoned, Remark: Unable to survey beyond blockage.	00:00:00		(Misc) 0

Structural Defects

Constructional Features

Service Defects

Miscellaneous Features

Inspection photos

 Place:
St, Barnsley

 Road:
Springfield Street

 Date:
13/03/2023

 section number:
3

 PLR:
? X


Photo: 24_4a, 00:00:00
2.5m, General Condition photograph



Photo: 3_5a, 00:00:00
5m, General Condition photograph



Photo: 3_6a, 00:00:00
7.5m, Obstruction, 80 % height/diameter loss



Survey Solutions
Eastwood, NG16 3BF
Nottinghamshire
Tel: , Fax:

Inspection report

Date: 13/03/2023	Job N°:	Weather: Showers	Operator:	section number: 4	PLR: ? X
Present:	Vehicle:	Camera: SOLO PRO	Preset:	Cleaned: No	Grade:

Road: Springfield Street	Division:	start MH: MH4 A
Place: St, Barnsley	District:	end MH:
Location:	Tape No.:	Total length: 19.1 m

Purpose: Asset condition	Shape/Size: dia 150 mm
Use: Surface water	Material: Polypropylene Pipe length:
Catchment:	Lining:
	Category:

Comment:
Location details:

1:150	position	code	observation	counter	photo	grade
	0.00	MH	Manhole Remark: MH4 A	00:00:00		(Constr) 0
	0.00	ST	Start of Survey	00:00:00		(Misc) 0
	0.00	WL	Water level, 0 % height/diameter	00:00:00		(Serv) 0
	2.50	JN	Junction at 12 o'clock, dia 100 mm	00:00:00	31_4a	(Constr) 0
	5.00	GP	General Condition photograph	00:00:00	32_5a	(Misc) 0
	5.85	JN	Junction at 09 o'clock, dia 100 mm	00:00:00	33_6a	(Constr) 0
	10.00	GP	General Condition photograph	00:00:00	34_7a	(Misc) 0
	12.50	JN	Junction at 09 o'clock, dia 100 mm	00:00:00	35_8a	(Constr) 0
	15.00	GP	General Condition photograph	00:00:00	36_9a	(Misc) 0
	17.00	LU	Line of Sewer deviates up	00:00:00		(Serv) 0
	19.10	FH	Finish Survey, Remark: Gully reached.	00:00:00		(Misc) 0

Structural Defects	Constructional Features
Service Defects	Miscellaneous Features

Inspection photos

 Place:
St, Barnsley

 Road:
Springfield Street

 Date:
13/03/2023

 section number:
4

 PLR:
? X


Photo: 31_4a, 00:00:00
2.5m, Junction at 12 o'clock, dia 100 mm



Photo: 32_5a, 00:00:00
5m, General Condition photograph



Photo: 33_6a, 00:00:00
5.85m, Junction at 09 o'clock, dia 100 mm



Photo: 34_7a, 00:00:00
10m, General Condition photograph

Inspection photosPlace:
St, BarnsleyRoad:
Springfield StreetDate:
13/03/2023section number:
4PLR:
? X

Photo: 35_8a, 00:00:00
12.5m, Junction at 09 o'clock, dia 100 mm



Photo: 36_9a, 00:00:00
15m, General Condition photograph



Survey Solutions
Eastwood, NG16 3BF
Nottinghamshire
Tel: , Fax:

Inspection report

Date: 13/03/2023	Job N°:	Weather: Showers	Operator:	section number: 5	PLR: ? X
Present:	Vehicle:	Camera: SOLO PRO	Preset:	Cleaned: No	Grade:


Road: Springfield Street	Division:	start MH: MH4 X
Place: St, Barnsley	District:	end MH:
Location:	Tape No.:	Total length: 2.05 m
Purpose: Asset condition	Shape/Size: dia 225 mm	
Use: Surface water	Material: Polypropylene	Pipe length:
Catchment:	Lining:	
	Category:	
Comment:		
Location details:		

1:25	position	code	observation	counter	photo	grade
	0.00	MH	Manhole Remark: MH4 X	00:00:00		(Constr) 0
	0.00	ST	Start of Survey	00:00:00		(Misc) 0
	0.00	WL	Water level, 0 % height/diameter	00:00:00		(Serv) 0
	1.90	JDM	Joint displaced. Medium	00:00:00	42_4a	(Struct) 1
	2.05	FH	Finish Survey, Remark: Attenuation tank reached.	00:00:00		(Misc) 0
Structural Defects			Constructional Features			
Service Defects			Miscellaneous Features			

Inspection photosPlace:
St, BarnsleyRoad:
Springfield StreetDate:
13/03/2023section number:
5PLR:
? X

Photo: 42_4a, 00:00:00
1.9m, Joint displaced. Medium

APPENDIX 5




Project

Project Name: 2024-06-30133 Walter Thompson Perseverance Street Barnsley S70 6HD

Project Date: 12/08/2024

Inspection Standard: MSCC5 Sewers & Drainage GB (SRM5 Scoring)



WALTER THOMPSON

Table of Contents

Project Name	Project Number	Project Date
2024-06-30133 Walter Thompson Perseverance Street Barnsley S70		12/08/2024

Project Information	P-1
Section Item 1: MH1 > MH2 (MH1X)	1
Section Item 2: MH2 > MH3 (MH2X)	3
Section Item 3: Exc Pipe1 > Downstream (Exc Pipe1X)	9
Section Item 4: Upstream > Exc Pipe1 (UpstreamX)	11
Section Item 5: Exc Pipe2 > Downstream (Exc Pipe2X)	13
Section Item 6: Upstream > MH4 (UpstreamX)	15
Section Item 7: Upstream B > MH4 (Upstream BX)	18
Section Item 8: MH4 > Downstream (MH4X)	20
Section Item 9: Upstream > mh5 (UpstreamX)	22
Section Item 10: MH5 > MH6 (MH5X)	23
Section Item 11: MH9 > Downstream (MH9X)	24

Project Information

Project Name	Project Number	Project Date
2024-06-30133 Walter Thompson Perseverance Street Barnsley S70		12/08/2024

Client

Company: Walter Thompson (Contractors) Ltd
Department: Construction House
Town or City: North Allerton
County: North Yorkshire
Post Code: DL7 8ED

**Site**

Company: Walter Thompson
Street: Perseverance Street
Town or City: Barnsley
Post Code: S70 6HD

Contractor

Company: DRAIN DOCTOR NW
Phone: 08000 266623




Section Inspection - 06/08/2024 - MH1X

Item No. 1	Insp. No. 1	Date: 06/08/24	Time: 9:43	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR MH1X
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Downstream	Upstream Node:	MH1
Road:	Perseverance Street	Inspected Length:	39.60 m	Upstream Pipe Depth:	
Location:		Total Length:	39.60 m	Downstream Node:	MH2
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	375 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:
Recommendations:

Scale:	1:343	Position [m]	Code	Observation	MPEG	Photo	Grade																																													
Depth: m MH1  0.00 0.00 6.19 10.40 12.12 36.26 37.10 38.71 39.60 Depth: m MH2 <table><tr><td>MH</td><td>Start node, manhole, reference: MH1</td><td>00:00:00</td><td></td><td></td></tr><tr><td>WL</td><td>Water level, 25% of the vertical dimension: fast flowing</td><td>00:00:01</td><td></td><td></td></tr><tr><td>FM</td><td>Fractures, multiple from 12 o'clock to 12 o'clock</td><td>00:00:50</td><td>MH1X_57 331753-29 01-490a-b</td><td>4 / 2</td></tr><tr><td>JN</td><td>Junction at 12 o'clock, 150mm dia</td><td>00:01:05</td><td></td><td></td></tr><tr><td>CN</td><td>Connection other than junction at 01 o'clock, 100mm dia</td><td>00:01:13</td><td>MH1X_c03 737ab-b56 c-44e3-8d</td><td></td></tr><tr><td>CN</td><td>Connection other than junction at 12 o'clock, 100mm dia</td><td>00:02:41</td><td>MH1X_0d 9a47b8-c1 79-421c-9</td><td></td></tr><tr><td>S01</td><td>Crack, longitudinal at 12 o'clock, start</td><td>00:02:44</td><td>MH1X_caf ab7d0-50e 5-4003-96</td><td></td></tr><tr><td>F01</td><td>Crack, longitudinal at 12 o'clock, finish</td><td>00:03:09</td><td></td><td>2 / 2</td></tr><tr><td>MHF</td><td>Finish node, manhole, reference: MH2: UTL</td><td>00:03:13</td><td></td><td></td></tr></table>								MH	Start node, manhole, reference: MH1	00:00:00			WL	Water level, 25% of the vertical dimension: fast flowing	00:00:01			FM	Fractures, multiple from 12 o'clock to 12 o'clock	00:00:50	MH1X_57 331753-29 01-490a-b	4 / 2	JN	Junction at 12 o'clock, 150mm dia	00:01:05			CN	Connection other than junction at 01 o'clock, 100mm dia	00:01:13	MH1X_c03 737ab-b56 c-44e3-8d		CN	Connection other than junction at 12 o'clock, 100mm dia	00:02:41	MH1X_0d 9a47b8-c1 79-421c-9		S01	Crack, longitudinal at 12 o'clock, start	00:02:44	MH1X_caf ab7d0-50e 5-4003-96		F01	Crack, longitudinal at 12 o'clock, finish	00:03:09		2 / 2	MHF	Finish node, manhole, reference: MH2: UTL	00:03:13		
MH	Start node, manhole, reference: MH1	00:00:00																																																		
WL	Water level, 25% of the vertical dimension: fast flowing	00:00:01																																																		
FM	Fractures, multiple from 12 o'clock to 12 o'clock	00:00:50	MH1X_57 331753-29 01-490a-b	4 / 2																																																
JN	Junction at 12 o'clock, 150mm dia	00:01:05																																																		
CN	Connection other than junction at 01 o'clock, 100mm dia	00:01:13	MH1X_c03 737ab-b56 c-44e3-8d																																																	
CN	Connection other than junction at 12 o'clock, 100mm dia	00:02:41	MH1X_0d 9a47b8-c1 79-421c-9																																																	
S01	Crack, longitudinal at 12 o'clock, start	00:02:44	MH1X_caf ab7d0-50e 5-4003-96																																																	
F01	Crack, longitudinal at 12 o'clock, finish	00:03:09		2 / 2																																																
MHF	Finish node, manhole, reference: MH2: UTL	00:03:13																																																		

Construction Features
Miscellaneous Features
Structural Defects
Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
2	80.0	2.5	100.0	4.0	2	1.0	0.1	3.0	2.0

Section Pictures - 06/08/2024 - MH1X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
1	Downstream	MH1X		



MH1X_57331753-2901-490a-b26d-40df08841c2e_20240812_111305_771.jpg, 00:00:50, 6.19 m
 Fractures, multiple from 12 o'clock to 12 o'clock



MH1X_c03737ab-b56c-44e3-8d3f-9695d96e3ca8_20240812_111333_891.jpg, 00:01:13, 12.12 m
 Connection other than junction at 01 o'clock, 100mm dia



MH1X_0d9a47b8-c179-421c-9966-5658da730b5a_20240812_111402_502.jpg, 00:02:41, 36.26 m
 Connection other than junction at 12 o'clock, 100mm dia




MH1X_cafab7d0-50e5-4003-9632-e5a048611cf2_20240812_111451_058.jpg, 00:02:44, 37.10 m
 Crack, longitudinal at 12 o'clock, start

Section Inspection - 06/08/2024 - MH2X

Item No. 2	Insp. No. 1	Date: 06/08/24	Time: 10:07	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR MH2X
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Downstream	Upstream Node:	MH2
Road:	Perseverance Street	Inspected Length:	91.64 m	Upstream Pipe Depth:	
Location:		Total Length:	91.64 m	Downstream Node:	MH3
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	375 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:
Recommendations:

Scale: 1:441	Position [m]	Code	Observation	MPEG	Photo	Grade
	Depth: m MH2 0.00	MH	Start node, manhole, reference: MH2: UTL	00:00:00		
	0.00	WL	Water level, 10% of the vertical dimension: fast flowing	00:00:18		
	3.58	CM	Cracks, multiple from 10 o'clock to 03 o'clock	00:00:30	MH2X_34 3fe477-d1 13-4899-a	3 / 2
	5.22	S01	Crack, longitudinal at 11 o'clock, start	00:00:35	MH2X_6d b244d5-3ff 5-431f-bfe	
	6.96	F01	Crack, longitudinal at 11 o'clock, finish	00:00:41		2 / 2
	9.27	CN	Connection other than junction at 03 o'clock, 150mm dia	00:00:48	MH2X_cc2 52805-bd3 a-4993-b6	
	9.93	CL	Crack, longitudinal at 02 o'clock	00:01:13	MH2X_8b 485754-31 ee-4d55-9	2 / 2
	15.05	JN	Junction at 01 o'clock, 100mm dia	00:01:35	MH2X_a3 8a3649-f4 5a-43d8-9	
	20.08	JN	Junction at 02 o'clock, 100mm dia	00:02:00		
	31.35	JN	Junction at 01 o'clock, 100mm dia	00:02:47		
	31.74	JDM	Joint displaced, medium	00:02:55	MH2X_d2c 1b144-da1 8-423f-8fe	1 / 3
	35.61	DEEJ	Attached deposits, encrustation at joint from 07 o'clock to 04 o'clock, 10% cross-sectional area loss	00:03:09	MH2X_ad 42cbe7-0a 16-4016-9	3
	35.73	CL	Crack, longitudinal at 12 o'clock	00:03:10	MH2X_de e560cd-5f 12-4c64-9	2 / 2
	37.91	ID	Infiltration, dripping at 12 o'clock	00:03:23	MH2X_c37 2f123-ab2 7-44c4-afb	
	44.47	MCBR	Pipe material changes to brick at this point	00:03:40	MH2X_ab 00335a-4f e4-4e54-8	

Section Pictures - 06/08/2024 - MH2X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
2	Downstream	MH2X		



MH2X_343fe477-d113-4899-a973-9e4abd930d52_20240812_111631_725.jpg, 00:00:30, 3.58 m
 Cracks, multiple from 10 o'clock to 03 o'clock



MH2X_6db244d5-3ff5-431f-bfec-cfd338009be2_20240812_111652_207.jpg, 00:00:35, 5.22 m
 Crack, longitudinal at 11 o'clock, start



MH2X_cc252805-bd3a-4993-b611-59dcfd49c579_20240812_111721_045.jpg, 00:00:48, 9.27 m
 Connection other than junction at 03 o'clock, 150mm dia



MH2X_8b485754-31ee-4d55-9e34-2c7c51316338_20240812_111744_612.jpg, 00:01:13, 9.93 m
 Crack, longitudinal at 02 o'clock

Section Pictures - 06/08/2024 - MH2X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
2	Downstream	MH2X		



MH2X_a38a3649-f45a-43d8-9154-86ef85ffa054_20240812_111802_344.jpg, 00:01:35, 15.05 m
 Junction at 01 o'clock, 100mm dia



MH2X_d2c1b144-da18-423f-8fe2-9c940f5444cc_20240812_111859_743.jpg, 00:02:55, 31.74 m
 Joint displaced, medium



MH2X_ad42cbe7-0a16-4016-9956-fc94c6be4d1a_20240812_111922_830.jpg, 00:03:09, 35.61 m
 Attached deposits, encrustation at joint from 07 o'clock to 04 o'clock, 10% cross-sectional area loss



MH2X_dee560cd-5f12-4c64-963a-88c51db298de_20240812_111948_233.jpg, 00:03:10, 35.73 m
 Crack, longitudinal at 12 o'clock

Section Pictures - 06/08/2024 - MH2X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
2	Downstream	MH2X		



MH2X_c372f123-ab27-44c4-afbf-3fa92f379988_20240812_112019_377.jpg, 00:03:23, 37.91 m
 Infiltration, dripping at 12 o'clock



MH2X_ab00335a-4fe4-4e54-8d0e-c2fd4113e1cd_20240812_112037_954.jpg, 00:03:40, 44.47 m
 Pipe material changes to brick at this point



MH2X_5635edc3-1272-4f0a-9816-837d2ba72dcf_20240812_112134_435.jpg, 00:05:16, 57.37 m
 Infiltration, dripping from 10 o'clock to 02 o'clock, start



MH2X_17d61786-185a-4e1b-82ea-5b547061bb71_20240812_112324_575.jpg, 00:06:47, 68.98 m
 Connection other than junction at 12 o'clock, 150mm dia

Section Pictures - 06/08/2024 - MH2X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
2	Downstream	MH2X		




MH2X_edaa8fb6-ba10-4e5d-a599-d9046361bffa_20240812_1
 12411_142.jpg, 00:07:38, 76.75 m
 Connection other than junction at 12 o'clock, 150mm dia

Section Inspection - 06/08/2024 - Exc Pipe1X

Item No. 3	Insp. No. 1	Date: 06/08/24	Time: 11:52	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR EXC PIPE1X
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Downstream	Upstream Node:	EXC PIPE1
Road:	Perseverance Street	Inspected Length:	32.23 m	Upstream Pipe Depth:	
Location:		Total Length:	32.23 m	Downstream Node:	DOWNSTREAM
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	225 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:
Recommendations:

Scale: 1:280	Position [m]	Code	Observation	MPEG	Photo	Grade
Depth: m Exc Pipe1						
						
	0.00	OC	Start node, other special chamber, reference: Exc Pipe1: Excavation	00:00:00		
	0.00	WL	Water level, 0% of the vertical dimension	00:00:11		
	5.80	JN	Junction at 01 o'clock, 150mm dia	00:00:56		
	8.34	JN	Junction at 01 o'clock, 150mm dia	00:01:05		
	9.84	JDM	Joint displaced, medium	00:01:10	Exc Pipe1X_04 1e4a96-96	1 / 3
	11.33	JDM	Joint displaced, medium	00:01:14	Exc Pipe1X_10 5ee651-11	1 / 3
	14.61	JN	Junction at 01 o'clock, 150mm dia	00:01:24		
	16.55	JN	Junction at 01 o'clock, 150mm dia	00:01:30		
	23.29	JN	Junction at 02 o'clock, 150mm dia	00:01:54		
	25.20	JN	Junction at 01 o'clock, 150mm dia	00:02:01		
	32.23	OCF	Finish node, other special chamber, reference: Downstream: Reached drop to main	00:03:19	Exc Pipe1X_69 96a05f-2b	
Downstream Depth: m						

Construction Features
Miscellaneous Features
Structural Defects
Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
2	1.0	0.1	2.0	1.0	2	2.0	0.1	4.0	3.0

Section Pictures - 06/08/2024 - Exc Pipe1X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
3	Downstream	EXC PIPE1X		



Exc
 Pipe1X_041e4a96-962b-4fe0-88a0-0faee3dbe9b0_20240812_113726_191.jpg, 00:01:10, 9.84 m
 Joint displaced, medium



Exc
 Pipe1X_105ee651-1135-472e-ba40-8f5d479d03a8_20240812_113739_703.jpg, 00:01:14, 11.33 m
 Joint displaced, medium



Exc
 Pipe1X_6996a05f-2b40-46db-a197-b5ac073126dd_20240812_113859_811.jpg, 00:03:19, 32.23 m
 Finish node, other special chamber, reference: Downstream,
 Reached drop to main


Section Inspection - 06/08/2024 - UpstreamX

Item No. 4	Insp. No. 1	Date: 06/08/24	Time: 12:09	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR UPSTREAMX
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Upstream	Upstream Node:	UPSTREAM
Road:	Perseverance Street	Inspected Length:	8.04 m	Upstream Pipe Depth:	
Location:		Total Length:	8.04 m	Downstream Node:	EXC PIPE1
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	150 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:

Recommendations:

Scale:	1:70	Position [m]	Code	Observation	MPEG	Photo	Grade																																																						
Depth: m Exc Pipe1  Upstream Depth: m <table><tr><th>Position [m]</th><th>Code</th><th>Observation</th><th>MPEG</th><th>Photo</th><th>Grade</th></tr><tr><td>0.00</td><td>OC</td><td>Start node, other special chamber, reference: Exc Pipe1: excavation</td><td>00:00:00</td><td></td><td></td></tr><tr><td>0.00</td><td>WL</td><td>Water level, 0% of the vertical dimension</td><td>00:00:00</td><td></td><td></td></tr><tr><td>0.10</td><td>REM</td><td>General remark: had to use push road as tractor would pass through pipe</td><td>00:00:00</td><td></td><td></td></tr><tr><td>0.47</td><td>RMJ</td><td>Roots, mass at joint, 20% cross-sectional area loss</td><td>00:00:11</td><td></td><td>5</td></tr><tr><td>1.18</td><td>RMJ</td><td>Roots, mass at joint, 25% cross-sectional area loss</td><td>00:00:15</td><td>Upstream X_b0335336-3924-4</td><td>5</td></tr><tr><td>3.31</td><td>H</td><td>Hole in drain or sewer from 01 o'clock to 05 o'clock</td><td>00:00:26</td><td>Upstream X_0cc2a8b9-c6fe-4d</td><td>5</td></tr><tr><td>4.96</td><td>CUW</td><td>Loss of vision, camera under water</td><td>00:00:36</td><td></td><td></td></tr><tr><td>8.04</td><td>MHF</td><td>Finish node, manhole, reference: Upstream: Rear of No 2</td><td>00:00:59</td><td>Upstream X_c5ad771a-2698-4</td><td></td></tr></table>								Position [m]	Code	Observation	MPEG	Photo	Grade	0.00	OC	Start node, other special chamber, reference: Exc Pipe1: excavation	00:00:00			0.00	WL	Water level, 0% of the vertical dimension	00:00:00			0.10	REM	General remark: had to use push road as tractor would pass through pipe	00:00:00			0.47	RMJ	Roots, mass at joint, 20% cross-sectional area loss	00:00:11		5	1.18	RMJ	Roots, mass at joint, 25% cross-sectional area loss	00:00:15	Upstream X_b0335336-3924-4	5	3.31	H	Hole in drain or sewer from 01 o'clock to 05 o'clock	00:00:26	Upstream X_0cc2a8b9-c6fe-4d	5	4.96	CUW	Loss of vision, camera under water	00:00:36			8.04	MHF	Finish node, manhole, reference: Upstream: Rear of No 2	00:00:59	Upstream X_c5ad771a-2698-4	
Position [m]	Code	Observation	MPEG	Photo	Grade																																																								
0.00	OC	Start node, other special chamber, reference: Exc Pipe1: excavation	00:00:00																																																										
0.00	WL	Water level, 0% of the vertical dimension	00:00:00																																																										
0.10	REM	General remark: had to use push road as tractor would pass through pipe	00:00:00																																																										
0.47	RMJ	Roots, mass at joint, 20% cross-sectional area loss	00:00:11		5																																																								
1.18	RMJ	Roots, mass at joint, 25% cross-sectional area loss	00:00:15	Upstream X_b0335336-3924-4	5																																																								
3.31	H	Hole in drain or sewer from 01 o'clock to 05 o'clock	00:00:26	Upstream X_0cc2a8b9-c6fe-4d	5																																																								
4.96	CUW	Loss of vision, camera under water	00:00:36																																																										
8.04	MHF	Finish node, manhole, reference: Upstream: Rear of No 2	00:00:59	Upstream X_c5ad771a-2698-4																																																									

Construction Features

Miscellaneous Features

Structural Defects

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
1	165.0	20.5	165.0	5.0	2	10.0	2.5	20.0	5.0

Section Pictures - 06/08/2024 - UpstreamX


Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
4	Upstream	UPSTREAMX		



UpstreamX_b0335336-3924-4b33-a2be-40099bb87b09_20240812_114204_616.jpg, 00:00:15, 1.18 m
 Roots, mass at joint, 25% cross-sectional area loss



UpstreamX_0cc2a8b9-c6fe-4dc4-8f75-75a0937ea0fd_20240812_114226_042.jpg, 00:00:26, 3.31 m
 Hole in drain or sewer from 01 o'clock to 05 o'clock




UpstreamX_c5ad771a-2698-45da-a478-a83aa63faf62_20240812_114305_010.jpg, 00:00:59, 8.04 m
 Finish node, manhole, reference: Upstream, Rear of No 2

Section Inspection - 06/08/2024 - Exc Pipe2X

Item No. 5	Insp. No. 1	Date: 06/08/24	Time: 12:16	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR EXC PIPE2X
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Downstream	Upstream Node:	EXC PIPE2
Road:	Perseverance Street	Inspected Length:	12.77 m	Upstream Pipe Depth:	
Location:		Total Length:	12.77 m	Downstream Node:	DOWNSTREAM
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	150 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:
Recommendations:

Scale: 1:111	Position [m]	Code	Observation	MPEG	Photo	Grade
Depth: m Exc Pipe2 						
	0.00	OC	Start node, other special chamber, reference: Exc Pipe2: Excavation 2	00:00:00		
	0.00	WL	Water level, 0% of the vertical dimension	00:00:02		
	1.18	JN	Junction at 11 o'clock, 150mm dia	00:00:17		
	3.66	DES	Settled deposits, fine, 20% cross-sectional area loss	00:00:26		4
	8.04	JN	Junction at 09 o'clock, 150mm dia	00:00:43		
	12.77	OCF	Finish node, other special chamber, reference: Downstream: Redundant	00:01:10		Exc Pipe2X_e1 2c6a32-3e
Downstream Depth: m						

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	1	5.0	0.4	5.0	4.0

Section Pictures - 06/08/2024 - Exc Pipe2X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
5	Downstream	EXC PIPE2X		



Exc

Pipe2X_e12c6a32-3e1b-46a8-8dfa-0d2038e524fa_20240812_114535_382.jpg, 00:01:10, 12.77 m


Finish node, other special chamber, reference: Downstream, Redundant

Section Inspection - 06/08/2024 - UpstreamX

Item No. 6	Insp. No. 1	Date: 06/08/24	Time: 12:58	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR UPSTREAMX
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Upstream	Upstream Node:	UPSTREAM
Road:	Perseverance Street	Inspected Length:	14.78 m	Upstream Pipe Depth:	
Location:		Total Length:	14.78 m	Downstream Node:	MH4
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	150 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	Polyester		

Comments:
Recommendations:

Scale: 1:128	Position [m]	Code	Observation	MPEG	Photo	Grade
Depth: m MH4 						
	0.00	MH	Start node, manhole, reference: MH4	00:00:00		
	0.00	WL	Water level, 0% of the vertical dimension	00:00:28		
	1.06	CL	Crack, longitudinal at 12 o'clock	00:00:34	Upstream X_2073ff9 d-1059-4b	2 / 2
	1.41	FC	Fracture, circumferential from 12 o'clock to 12 o'clock	00:00:37	Upstream X_139ac1 7c-f647-45	3 / 2
	1.89	CC	Crack, circumferential from 12 o'clock to 12 o'clock	00:00:40	Upstream X_56508c 19-a7f9-41	2 / 2
	2.60	CM	Cracks, multiple from 12 o'clock to 12 o'clock	00:00:42	Upstream X_342c90 7d-01b5-4	3 / 2
	4.73	GP	General photograph taken at this point: buried manhole	00:01:34	Upstream X_305cf42 b-dc3d-48	
	11.25	JN	Junction at 09 o'clock, 150mm dia	00:02:04		
	13.83	LL	Line deviates left	00:02:21		
	14.78	SA	Survey abandoned: unable to push camera around bend	00:03:00		

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
4	50.0	6.8	100.0	3.0	4	2.0	0.3	4.0	3.0

Section Pictures - 06/08/2024 - UpstreamX

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
6	Upstream	UPSTREAMX		



UpstreamX_2073ff9d-1059-4bdf-8054-2b143b36b8bf_20240812_114833_120.jpg, 00:00:34, 1.06 m
Crack, longitudinal at 12 o'clock



UpstreamX_139ac17c-f647-4501-9898-87e944ac7036_20240812_114850_286.jpg, 00:00:37, 1.41 m
Fracture, circumferential from 12 o'clock to 12 o'clock



UpstreamX_56508c19-a7f9-4108-8dab-9e6aa03b9b98_20240812_114906_832.jpg, 00:00:40, 1.89 m
Crack, circumferential from 12 o'clock to 12 o'clock



UpstreamX_342c907d-01b5-48cb-a028-132170947893_20240812_114927_787.jpg, 00:00:42, 2.60 m
Cracks, multiple from 12 o'clock to 12 o'clock

Section Pictures - 06/08/2024 - UpstreamX

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
6	Upstream	UPSTREAMX		




UpstreamX_305cf42b-dc3d-4801-b555-6358f9682f41_20240812_115001_507.jpg, 00:01:34, 4.73 m
 General photograph taken at this point, buried manhole

Section Inspection - 06/08/2024 - Upstream BX

Item No. 7	Insp. No. 1	Date: 06/08/24	Time: 13:03	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR UPSTREAM BX
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Upstream	Upstream Node:	UPSTREAM B
Road:	Perseverance Street	Inspected Length:	1.42 m	Upstream Pipe Depth:	
Location:		Total Length:	1.42 m	Downstream Node:	MH4
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	100 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:
Recommendations:

Scale:	1:50	Position [m]	Code	Observation	MPEG	Photo	Grade																														
Depth: m MH4  <table><tr><td>0.00</td><td>MH</td><td>Start node, manhole, reference: MH4</td><td>00:00:00</td><td></td><td></td></tr><tr><td>0.00</td><td>WL</td><td>Water level, 0% of the vertical dimension</td><td>00:00:10</td><td></td><td></td></tr><tr><td>0.35</td><td>JDL</td><td>Joint displaced, large</td><td>00:00:10</td><td>Upstream BX_9bcc79f6-955a-4</td><td>1 / 4</td></tr><tr><td>1.41</td><td>DER</td><td>Settled deposits, coarse, 50% cross-sectional area loss</td><td>00:00:26</td><td></td><td>4</td></tr><tr><td>1.42</td><td>SA</td><td>Survey abandoned: REDUNDANT</td><td>00:00:32</td><td></td><td></td></tr></table>								0.00	MH	Start node, manhole, reference: MH4	00:00:00			0.00	WL	Water level, 0% of the vertical dimension	00:00:10			0.35	JDL	Joint displaced, large	00:00:10	Upstream BX_9bcc79f6-955a-4	1 / 4	1.41	DER	Settled deposits, coarse, 50% cross-sectional area loss	00:00:26		4	1.42	SA	Survey abandoned: REDUNDANT	00:00:32		
0.00	MH	Start node, manhole, reference: MH4	00:00:00																																		
0.00	WL	Water level, 0% of the vertical dimension	00:00:10																																		
0.35	JDL	Joint displaced, large	00:00:10	Upstream BX_9bcc79f6-955a-4	1 / 4																																
1.41	DER	Settled deposits, coarse, 50% cross-sectional area loss	00:00:26		4																																
1.42	SA	Survey abandoned: REDUNDANT	00:00:32																																		

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
1	2.0	1.4	2.0	1.0	2	8.0	9.2	13.0	5.0

Section Pictures - 06/08/2024 - Upstream BX

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
7	Upstream	UPSTREAM BX		



Upstream


BX_9bcc79f6-955a-474c-bba5-4111b563cb96_20240812_120
 226_386.jpg, 00:00:10, 0.35 m
 Joint displaced, large

Section Inspection - 06/08/2024 - MH4X

Item No. 8	Insp. No. 1	Date: 06/08/24	Time: 13:21	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR MH4X
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Downstream	Upstream Node:	MH4
Road:	Perseverance Street	Inspected Length:	12.77 m	Upstream Pipe Depth:	
Location:		Total Length:	12.77 m	Downstream Node:	DOWNSTREAM
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	150 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:
Recommendations:

Scale: 1:111	Position [m]	Code	Observation	MPEG	Photo	Grade
Depth: m MH4 						
	0.00	MH	Start node, manhole, reference: MH4	00:00:00		
	0.00	WL	Water level, 0% of the vertical dimension	00:00:08		
	4.73	CM	Cracks, multiple from 12 o'clock to 12 o'clock	00:00:28	MH4X_6b b3e22b-fa 39-4978-a	3 / 2
	7.21	JN	Junction at 03 o'clock, 150mm dia	00:00:40		
	8.98	DES	Settled deposits, fine, 30% cross-sectional area loss	00:00:51	MH4X_7d 501f97-82 de-4354-9	4
	12.65	DER	Settled deposits, coarse, 95% cross-sectional area loss	00:01:10	MH4X_dce 3b7e3-68c e-42c4-94	5
	12.77	SA	Survey abandoned: UNABLE TO PASS	00:01:42		

Construction Features
Structural Defects
Miscellaneous Features
Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
1	40.0	3.2	40.0	3.0	3	10.0	1.3	16.0	5.0

Section Pictures - 06/08/2024 - MH4X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
8	Downstream	MH4X		



MH4X_6bb3e22b-fa39-4978-ac21-88070a5b0208_20240812_120351_013.jpg, 00:00:28, 4.73 m
 Cracks, multiple from 12 o'clock to 12 o'clock



MH4X_7d501f97-82de-4354-9a49-4944b60663d8_20240812_120423_882.jpg, 00:00:51, 8.98 m
 Settled deposits, fine, 30% cross-sectional area loss



MH4X_dce3b7e3-68ce-42c4-944b-711f0315f6dd_20240812_120454_527.jpg, 00:01:10, 12.65 m
 Settled deposits, coarse, 95% cross-sectional area loss


Section Inspection - 06/08/2024 - UpstreamX

Item No. 9	Insp. No. 1	Date: 06/08/24	Time: 13:54	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR UPSTREAMX
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Upstream	Upstream Node:	UPSTREAM
Road:	Perseverance Street	Inspected Length:	0.78 m	Upstream Pipe Depth:	
Location:		Total Length:	0.78 m	Downstream Node:	MH5
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	150 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:

Recommendations:

Scale:	1:50	Position [m]	Code	Observation	MPEG	Photo	Grade
							
		0.00	MH	Start node, manhole, reference: mh5	00:00:00		
		0.00	WL	Water level, 0% of the vertical dimension	00:00:00		
		0.50	LR	Line deviates right	00:00:33		
		0.78	SA	Survey abandoned: UNABLE TO PASS BEND	00:00:33		

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0


Section Inspection - 06/08/2024 - MH5X

Item No. 10	Insp. No. 1	Date: 06/08/24	Time: 13:51	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR MH5X
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Downstream	Upstream Node:	MH5
Road:	Perseverance Street	Inspected Length:	22.49 m	Upstream Pipe Depth:	
Location:		Total Length:	22.49 m	Downstream Node:	MH6
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	150 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:

Recommendations:

Scale:	1:195	Position [m]	Code	Observation	MPEG	Photo	Grade																																
Depth: m MH5  MH6 Depth: m <table><tr><td>0.00</td><td>MH</td><td>Start node, manhole, reference: MH5</td><td>00:00:00</td></tr><tr><td>0.00</td><td>WL</td><td>Water level, 0% of the vertical dimension</td><td>00:00:14</td></tr><tr><td>3.74</td><td>JN</td><td>Junction at 02 o'clock, 100mm dia</td><td>00:00:25</td></tr><tr><td>10.48</td><td>JN</td><td>Junction at 02 o'clock, 100mm dia</td><td>00:00:46</td></tr><tr><td>10.90</td><td>JN</td><td>Junction at 10 o'clock, 100mm dia</td><td>00:00:48</td></tr><tr><td>15.58</td><td>JN</td><td>Junction at 02 o'clock, 100mm dia</td><td>00:01:03</td></tr><tr><td>19.54</td><td>JN</td><td>Junction at 10 o'clock, 100mm dia</td><td>00:01:16</td></tr><tr><td>22.49</td><td>MHF</td><td>Finish node, manhole, reference: MH6: BURIED</td><td>00:01:30</td></tr></table>								0.00	MH	Start node, manhole, reference: MH5	00:00:00	0.00	WL	Water level, 0% of the vertical dimension	00:00:14	3.74	JN	Junction at 02 o'clock, 100mm dia	00:00:25	10.48	JN	Junction at 02 o'clock, 100mm dia	00:00:46	10.90	JN	Junction at 10 o'clock, 100mm dia	00:00:48	15.58	JN	Junction at 02 o'clock, 100mm dia	00:01:03	19.54	JN	Junction at 10 o'clock, 100mm dia	00:01:16	22.49	MHF	Finish node, manhole, reference: MH6: BURIED	00:01:30
0.00	MH	Start node, manhole, reference: MH5	00:00:00																																				
0.00	WL	Water level, 0% of the vertical dimension	00:00:14																																				
3.74	JN	Junction at 02 o'clock, 100mm dia	00:00:25																																				
10.48	JN	Junction at 02 o'clock, 100mm dia	00:00:46																																				
10.90	JN	Junction at 10 o'clock, 100mm dia	00:00:48																																				
15.58	JN	Junction at 02 o'clock, 100mm dia	00:01:03																																				
19.54	JN	Junction at 10 o'clock, 100mm dia	00:01:16																																				
22.49	MHF	Finish node, manhole, reference: MH6: BURIED	00:01:30																																				

Construction Features

Miscellaneous Features

Structural Defects

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0


Section Inspection - 06/08/2024 - MH9X

Item No. 11	Insp. No. 1	Date: 06/08/24	Time: 14:42	Client's Job Ref Not Specified	Weather Not Specified	Pre Cleaned No	PLR MH9X
Operator Not Specified		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID Not Specified

Town or Village:	Barnsley	Inspection Direction:	Downstream	Upstream Node:	MH9
Road:	Perseverance Street	Inspected Length:	28.39 m	Upstream Pipe Depth:	
Location:		Total Length:	28.39 m	Downstream Node:	DOWNSTREAM
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	150 mm		
Flow Control:	No flow control	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:

Recommendations:

Scale:	1:246	Position [m]	Code	Observation	MPEG	Photo	Grade																																				
Depth: m MH9  <table><tr><td>0.00</td><td>MH</td><td>Start node, manhole, reference: MH9</td><td>00:00:00</td><td></td><td></td></tr><tr><td>0.00</td><td>WL</td><td>Water level, 5% of the vertical dimension</td><td>00:00:12</td><td></td><td></td></tr><tr><td>0.11</td><td>DEF</td><td>Attached deposits, fouling from 04 o'clock to 08 o'clock, 30% cross-sectional area loss</td><td>00:00:10</td><td>MH9X_b6 1292d1-0c 30-4b2b-b</td><td>4</td></tr><tr><td>3.43</td><td>DEF</td><td>Attached deposits, fouling from 04 o'clock to 07 o'clock, 15% cross-sectional area loss</td><td>00:00:24</td><td>MH9X_54 9ea207-83 ad-44cc-b</td><td>3</td></tr><tr><td>11.11</td><td>LL</td><td>Line deviates left: INTO JUNCTION</td><td>00:01:04</td><td>MH9X_b4 188a44-f5 5b-49ee-b</td><td></td></tr><tr><td>28.39</td><td>SA</td><td>Survey abandoned: UNABLE TO PUSH CAMERA FURTHER</td><td>00:02:37</td><td></td><td></td></tr></table>								0.00	MH	Start node, manhole, reference: MH9	00:00:00			0.00	WL	Water level, 5% of the vertical dimension	00:00:12			0.11	DEF	Attached deposits, fouling from 04 o'clock to 08 o'clock, 30% cross-sectional area loss	00:00:10	MH9X_b6 1292d1-0c 30-4b2b-b	4	3.43	DEF	Attached deposits, fouling from 04 o'clock to 07 o'clock, 15% cross-sectional area loss	00:00:24	MH9X_54 9ea207-83 ad-44cc-b	3	11.11	LL	Line deviates left: INTO JUNCTION	00:01:04	MH9X_b4 188a44-f5 5b-49ee-b		28.39	SA	Survey abandoned: UNABLE TO PUSH CAMERA FURTHER	00:02:37		
0.00	MH	Start node, manhole, reference: MH9	00:00:00																																								
0.00	WL	Water level, 5% of the vertical dimension	00:00:12																																								
0.11	DEF	Attached deposits, fouling from 04 o'clock to 08 o'clock, 30% cross-sectional area loss	00:00:10	MH9X_b6 1292d1-0c 30-4b2b-b	4																																						
3.43	DEF	Attached deposits, fouling from 04 o'clock to 07 o'clock, 15% cross-sectional area loss	00:00:24	MH9X_54 9ea207-83 ad-44cc-b	3																																						
11.11	LL	Line deviates left: INTO JUNCTION	00:01:04	MH9X_b4 188a44-f5 5b-49ee-b																																							
28.39	SA	Survey abandoned: UNABLE TO PUSH CAMERA FURTHER	00:02:37																																								

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	2	5.0	0.2	7.0	4.0

Section Pictures - 06/08/2024 - MH9X

Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
11	Downstream	MH9X		



MH9X_b61292d1-0c30-4b2b-b659-c26eacf2a2cb_20240812_121118_358.jpg, 00:00:10, 0.11 m
 Attached deposits, fouling from 04 o'clock to 08 o'clock, 30% cross-sectional area loss




MH9X_549ea207-83ad-44cc-b032-0152d315ed48_20240812_121140_525.jpg, 00:00:24, 3.43 m
 Attached deposits, fouling from 04 o'clock to 07 o'clock, 15% cross-sectional area loss



MH9X_b4188a44-f55b-49ee-b505-0b5ae8c3b84a_20240812_121212_354.jpg, 00:01:04, 11.11 m
 Line deviates left, INTO JUNCTION

APPENDIX 6



SHEET SW1

SCALE @ A3 = 1:300

APPENDIX 7

EASTWOOD & PARTNERS (Consulting Engineers) Ltd.

Project: Exemplar, Barnsley	Sheet	SW2A
	Job No.	48063
	Date	Sep-24
Subject: Existing Surface Water Storage 1 in 30	Designed	MW
	Checked	
	Revision	

Site Details :
Information From Wallingford Maps :

Location :	Barnsley	M5-60	19.0 mm
Grid Ref :		r	0.37
		SAAR	750 mm
Total Site Area	0.265 ha	UCWI	80 (Fig. 9.7)
		Soil Type	4
		SOIL	0.45 (Section 7.4)
Roof	ha		
Paved	ha		
Other	ha		
Total Impermeable	0.232 ha		
PIMP	87.5%		
PR	69.3	Equation 7.3	
Cv	0.79	Equation 7.21	
Default Cv	0.84	Designer to insert to override calculated Cv	

Design Return Period	30	Years	Max. Branch Length	50
			Approx. Time of Flow	0.8 mins

Percentage Increase For Climate Change: **0%**

Details of Restricted Discharge :

Maximum Permitted Rate of Flow from the System	Litres/sec/ha
	5.0 Litres/sec
Assumed Average Flow as a Proportion (Estimate)	75 %
Average Rate of Flow	3.8 Litres/sec

Calculation of Critical Duration and Storage Volume Required :

Trial Durations (mins)	15	30	60	120	240	360	480
Average Point Intensity (mm/hr)	70.1	46.3	29.2	17.9	10.8	7.9	6.4
Volume of Run-off for the period = Area x Cv x i x D (m3)	34.2	45.1	57.0	69.9	83.9	92.6	99.3
With climate change	34.2	45.1	57.0	69.9	83.9	92.6	99.3
Volume of Out-flow for the period = Ave. flow x (D+Tf)(m3)	3.6	6.9	13.7	27.2	54.2	81.2	108.2
Storage Volume for this Duration (m3)	30.6	38.2	43.3	42.7	29.7	11.4	-8.9

Storage Volume Required for

30 Year Return Period = 43.3 m3

EASTWOOD & PARTNERS (Consulting Engineers) Ltd.

Project: Exemplar, Barnsley	Sheet	SW3A
	Job No.	48063
	Date	Sep-24
Subject: Existing Surface Water Storage 1 in 100	Designed	MW
	Checked	
	Revision	

Site Details :

Information From Wallingford Maps :

Location :	Barnsley	M5-60	19.0 mm
Grid Ref :		r	0.37
		SAAR	750 mm
Total Site Area	0.265 ha	UCWI	80 (Fig. 9.7)
		Soil Type	4
		SOIL	0.45 (Section 7.4)
Roof	ha		
Paved	ha		
Other	ha		
Total Impermeable	0.232 ha		
PIMP	87.5%		
PR	69.3	Equation 7.3	
Cv	0.79	Equation 7.21	
Default Cv	0.84	Designer to insert to override calculated Cv	

Design Return Period	100	Years	Max. Branch Length	50
			Approx. Time of Flow	0.8 mins

Percentage Increase For Climate Change: **0%**

Details of Restricted Discharge :

Maximum Permitted Rate of Flow from the System	Litres/sec/ha
	11.0 Litres/sec
Assumed Average Flow as a Proportion (Estimate)	75 %
Average Rate of Flow	8.3 Litres/sec


Calculation of Critical Duration and Storage Volume Required :

Trial Durations (mins)	15	30	60	120	240	360	480
Average Point Intensity (mm/hr)	90.8	60.5	38.4	23.6	14.1	10.3	8.2
Volume of Run-off for the period = Area x Cv x i x D (m3)	44.2	58.9	74.9	91.9	109.6	120.2	128.3
With climate change	44.2	58.9	74.9	91.9	109.6	120.2	128.3
Volume of Out-flow for the period = Ave. flow x (D+Tf)(m3)	7.8	15.3	30.1	59.8	119.2	178.6	238.0
Storage Volume for this Duration (m3)	36.4	43.6	44.7	32.1	-9.6	-58.4	-109.7


Storage Volume Required for

100 Year Return Period = 44.7 m3

APPENDIX 8



PROPOSED IMPERMEABLE
AREA POSITIVELY DRAINED
1840 m²



APPENDIX 9

EASTWOOD & PARTNERS (Consulting Engineers) Ltd.

Project: Exemplar, Barnsley	Sheet	SW5B
	Job No.	48063
	Date	Sep-24
Subject: Surface Water Storage	Designed	MW
	Checked	
	Revision	

Site Details :

Information From Wallingford Maps :

Location :	Barnsley	M5-60	19.0 mm
Grid Ref :		r	0.37
		SAAR	750 mm
Total Site Area	0.265 ha	UCWI	80 (Fig. 9.7)
		Soil Type	4
		SOIL	0.45 (Section 7.4)
Roof	ha		
Paved	ha		
Other	ha		
Total Impermeable	0.184 ha		
PIMP	69.4%		
PR	54.3	Equation 7.3	
Cv	0.78	Equation 7.21	
Default Cv	1.00	Designer to insert to override calculated Cv	

Design Return Period	100	Years	Max. Branch Length	50
			Approx. Time of Flow	0.8 mins

Percentage Increase For Climate Change: **40%**

Details of Restricted Discharge :

Maximum Permitted Rate of Flow from the System	Litres/sec/ha
	5.0 Litres/sec
Assumed Average Flow as a Proportion (Estimate)	75 %
Average Rate of Flow	3.8 Litres/sec

Calculation of Critical Duration and Storage Volume Required :

Trial Durations (mins)	15	30	60	120	240	360	480
Average Point Intensity (mm/hr)	90.8	60.5	38.4	23.6	14.1	10.3	8.2
Volume of Run-off for the period = Area x Cv x i x D (m3)	41.8	55.6	70.7	86.8	103.5	113.5	121.2
With climate change	58.5	77.9	99.0	121.5	144.9	158.9	169.7
Volume of Out-flow for the period = Ave. flow x (D+Tf)(m3)	3.6	6.9	13.7	27.2	54.2	81.2	108.2
Storage Volume for this Duration (m3)	54.9	70.9	85.3	94.4	90.7	77.7	61.5

Storage Volume Required for

100 Year Return Period = 94.4 m3

APPENDIX 10



APPENDIX 11

EXEMPLAR HEALTH CARE LTD.

PERSEVERANCE STREET, BARNSELY

EXTERNAL DRAINAGE MAINTENANCE SCHEDULE

<u>CATEGORY</u>	<u>ACTION</u>	<u>FREQUENCY</u>
REGULAR	General removal of litter and debris from external paving and landscaping areas.	Monthly (or more frequently if required)
	Cleaning of gullies, drainage channels and drainage channel sump units to remove debris and silt.	6 monthly, after autumn leaf fall (or more frequently if necessary)
	Cleaning of manholes to remove debris and silt.	Annually, after autumn leaf fall (or more frequently if necessary)
	Inspection of all chambers, manholes and proprietary storage units to identify and make good any defects as necessary, including CCTV survey and jetting/cleaning of pipework if necessary.	Annually or after any exceptional rainfall events.
	Removal of trapped oil and silt from proprietary Class 1 surface water separator.	Annually (or more frequently if notified by alarm)
CORRECTIVE	Clear blockages in gully outlets, drainage channel sump units and branch connections.	As required
	Clear blockages in proprietary storage units.	As required

Eastwood

CONSULTING ENGINEERS

