NOTES

- Recommended Plotting Size: A1
- Map recreated from Google Earth building layout and is not to scale. Do not scale from Drawing. Drawing is for representative purposes only.
- The fields of view provided are scaled based on the Google Earth layout of the location and may not accurately represent the camera views. All shown fields of view are indicative.
- All locations to be confirmed on site.




- Camera 15 Location
- Existing mounting point on wall (Camera shown).
- Purpose - Detection within Entrance Gate area.
- Existing location to be reused, Camera to be replaced.




- Camera 12 Location
- Existing mounting point on wall (Camera shown).
- Purpose - Detection at Entrance into Powerhouse Square.
- Existing location to be reused, Camera to be replaced.

- Camera 10 Location
- Location of mounting is proposed.
- Purpose - Detection of Powerhouse Square and Pedestrian Entrance.
- New Camera to be installed.



- Camera 18 Location
- Existing mounting point on wall (Camera Shown).
- Purpose - Identification of Gate within Darwin Yard.
- Existing location to be reused, Camera to be replaced.



- Camera 16 Location
- Location of mounting is proposed.
- Purpose - Observation within open public area towards pantry.
- New Camera to be installed.

LEGEND

- Existing Camera - Remove
- Dome Camera - Existing - Replace
- Dome Camera - Additional
- Dome Camera - Remove
- FoV - Detection
- FoV - Observation
- FoV - Recognition
- FoV - Identification
- FoV - Partial Blindspot
- Building/Obstruction
- Obstructive Foliage
- Gate
- Site Boundary

3	Camera 16 updated.
2	Cameras and Views updated.

Consultive Solutions Limited

Hedworths 2
Bowes Offices
Lambton Park
Chester le Street
Co Durham
DH3 4AN

www.consultivesolutions.co.uk

Consultive Solutions

BARNSLEY Metropolitan Borough Council

Project	CCTV Consultancy
Title	Elsecar Heritage Centre Proposed CCTV Indicative Type B Coverage (1)
Type	LAYOUT
Purpose	FOR ISSUE

SCALE	NTS @A1		REV
DRAWN	28.01.25	PA	3
UPDATED	14.01.26	PA	ISSUE
CHECKED	14.01.26	RG	1

Drawing Number
CSL-BMC-2025-933.1-01004