Key	NATIVE HEDGE	When/How To plant	% MIX	No.
	Shrubs and climbers	**Whips**	**94%**	
	Crataegus monogyna (Hawthorn)		36	157
	Corylus avellana (Hazel)		36	157
	Prunus spinosa (Blackthorn)		8	35
	Sambucus nigra (Elder)		7	30
	Viburnum opulus (Guelder rose)		4	18
	Lonicera periclymenum (Honeysuckle)		3	13
NH015	**Trees**	To be planted at 6 l/m. Staggered row.	**6%**	
	Quercus robur (Pedunculate oak)		1	4
	Quercus petraea (Sessile oak)		1	4
	Ulmus glabra (Wych elm)		1	4
	Betula pendula (Silver birch)		1	4
	Ilex aquifolium (Holly)		1	4
	Sorbus aucuparia (Mountain ash)		1	4

Key	NATIVE HEDGE	When/How To plant	% MIX	No.
	Shrubs and climbers	**Whips**	**94%**	
	Crataegus monogyna (Hawthorn)		36	24
	Corylus avellana (Hazel)		36	24
	Prunus spinosa (Blackthorn)		8	5
	Sambucus nigra (Elder)		7	5
	Viburnum opulus (Guelder rose)		4	3
	Lonicera periclymenum (Honeysuckle)		3	2
NH018	**Trees**	To be planted at 6 l/m. Staggered row.	**6%**	
	Quercus robur (Pedunculate oak)		1	2
	Quercus petraea (Sessile oak)		1	2
	Ulmus glabra (Wych elm)		1	2
	Betula pendula (Silver birch)		1	2
	Ilex aquifolium (Holly)		1	2
	Sorbus aucuparia (Mountain ash)		1	2

Key	NATIVE HEDGE	When/How To plant	% MIX	No.
	Shrubs and climbers	**Whips**	**94%**	
	Crataegus monogyna (Hawthorn)		36	17
	Corylus avellana (Hazel)		36	17
	Prunus spinosa (Blackthorn)		8	4
	Sambucus nigra (Elder)		7	3
	Viburnum opulus (Guelder rose)		4	2
	Lonicera periclymenum (Honeysuckle)		3	1
NH019	**Trees**	To be planted at 6 l/m. Staggered row.	**6%**	
	Quercus robur (Pedunculate oak)		1	1
	Quercus petraea (Sessile oak)		1	1
	Ulmus glabra (Wych elm)		1	1
	Betula pendula (Silver birch)		1	1
	Ilex aquifolium (Holly)		1	1
	Sorbus aucuparia (Mountain ash)		1	1

Key	NATIVE HEDGE	When/How To plant	% MIX	No.
	Shrubs and climbers	**Whips**	**94%**	
	Crataegus monogyna (Hawthorn)		36	152
	Corylus avellana (Hazel)		36	152
	Prunus spinosa (Blackthorn)		8	34
	Sambucus nigra (Elder)		7	30
	Viburnum opulus (Guelder rose)		4	17
	Lonicera periclymenum (Honeysuckle)		3	13
NH020	**Trees**	To be planted at 6 l/m. Staggered row.	**6%**	
	Quercus robur (Pedunculate oak)		1	5
	Quercus petraea (Sessile oak)		1	5
	Ulmus glabra (Wych elm)		1	5
	Betula pendula (Silver birch)		1	5
	Ilex aquifolium (Holly)		1	5
	Sorbus aucuparia (Mountain ash)		1	5

Bulb Planting

No.	Name	Min Size Container	Density	Qty
ALL	(1) Hyacinthoides non-scripta	(1) Grade 6/7	(1)10	(1)365
	(2)Crocus speciosus	(2)Grade 5/6	(2)10	(2)365
	(3)narcissus february gold	(3)Grade 8/10	(3)10	(3)365

Seeding Mixes		Sowing Rate	Area
Wildflower Grass - EM5F Mix	Emorsgate Seeds	1.5g/m²	10618
Wildflower Grass - EL1F Mix	Emorsgate Seeds	1.5g/m²	8282
Amenity Grass - A22	Germinal Seeds	50.00g/m²	6019

robinson

Robinson Landscape Design
The Studio, Hedgeley, North Bank
Haydon Bridge, Hexham, NE47 6LY
Tel: 01434 684 100
info@robinsonlandscapedesign.co.uk

Project
Wilthorpe, Barnsley
Drawing Name
Planting Schedule 4 of 4

Drawing No: 5685-93-017
Scale at A1: 1:200

Drawn: CJT
Checked: TR
Date: 13-02-2015

Rev.	Drawn: Checked: / Date:	
H	Drawn: FW Checked: CJT / Date: 20-02-2017	Plan updated with new housing layout
G	Drawn: ERF Checked: CJT / Date: 08-12-2016	Plan updated with new housing layout
F	Drawn: ERF Checked: CJT / Date: 28-11-2016	Plan updated with new housing layout
E	Drawn: FW Checked: CJT / Date: 26-02-2016	W1 Mix amended, root barrier added
C	Drawn: FW Checked: CJT / Date: 08-01-2016	Amended in line with the new layout