

PLANT SCHEDULE									
TREES									
QTY	CODE	PLANT NAME	STOCK	FORM	GIRTH/HEIGHT	SPECIFICATION			
5No.	BET JAC ms3	Betula utilis "Jaquemontii"	RB	MSTEM3	200-250cm	3x; multi stem; bushy; 3 stems			
14No.	BET PEN xhs	Betula pendula	RB	STD	14-16cm	3x; extra heavy standard;clear stem minimum 175-200, 425-600cm ht			
9No.	CAR FRA xhs14 F	Carpinus betulus "Frans Fontaine"	RB	FTH	14-16cm	3x; Large Feathered; 7 breaks			
4No.	FAG SYL ehs	Fagus sylvatica	RB	EHS	16-18cm	3x; extra heavy standard; clear stem minimum 200, 400-450cm ht			
2No.	PRU PAD xhs14	Prunus padus	RB	STD	14-16cm	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks			
5No.	QUE ROB xhs16	Quercus robur	RB	EHS	16-18cm	3x; extra heavy standard;clear stem minimum 200cm, 400-450cm ht			
5No.	SOR MAJ xhs14	Sorbus aria "Majestica"	RB	STD	14-16cm	3x; extra heavy standard;clear stem minimum 175-200, 425-600cm ht			
12No.	Sor She xhs14	Sorbus aucuparia "Sheerwater Seedling"	RB	STD	14-16cm	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; 400-450cm ht			
11No.	TIL COR xhs16	Tilia cordata	RB	EHS	16-18cm	3x; extra heavy standard;clear stem minimum 200, 400-450cm ht			
HEDGES									
QTY	CODE	PLANT NAME	STOCK	SIZE	SPECIFICATION				
14m	Hornbeam Hedge	60-80cm Carpinus betulus	B Trans						
84No.	Plants spaced @ 6/m	in a Double Staggered Row							
159m	Osm bur Hedge	5L Osmanthus burkwoodii	C 5L	40-60cm	Bushy; 5 breaks				
795No.	Plants spaced @ 5/m	in a Double Staggered Row							
170m	Ski KG 5L Hedge	Skimmia x confusa "Kew Green"	C 5L	30-40cm					
680No.	Plants spaced @ 4/m	in a Single Row							
SHRUBS									
QTY	CODE	PLANT NAME	STOCK	SIZE	SPACING	SPECIFICATION			
1No.	Ara ela 10L	Aralia elata	C 10L	80-100cm	1/m2	Single leader; 2 breaks			
26No.	Ber AN 5L	Berberis thunbergii "Atropurpurea Nana"	C 5L	25-30cm	3/m2	Branched; 5 breaks			
89No.	Bra Sun 5-7.5L	Brachyglottis "Sunshine"	C 5-7.5L	40-60cm	3/m2	Branched; 6 breaks			
34No.	Car HB	Caryopteris x clandonensis "Heavenly Blue"	C 2L	20-30cm	3/m2	Branched; 5 breaks			
1No.	Cor MF 10L	Cornus sanguinea "Midwinter Fire"	C 10L	80-100cm	1/m2	Branched; 5 breaks			
9No.	Cotl RP 10L	Cotinus coggygria "Royal Purple"	C 10L	100-125cm	1/m2	Bushy; 9 breaks			
29No.	Euo Gol 5-7.5L	Euonymus fortunei "Emerald n Gold"	C 5-7.5L	25-30cm	4/m2				
12No.	For Lyn	Forsythia x intermedia "Lynwood"	C 10L	80-100cm	1/m2	Bushy; 5 breaks			
17No.	F Mrs	Fuchsia "Mrs Poppie"	C 3L	20-30cm	4/m2	Bushy; 3 breaks			
40No.	Heb GO 3L 3/m2	Hebe "Great Orme"	C 3L	30-40cm	3/m2	Bushy; 7 breaks			
27No.	Heb Red 5-7.5L	Hebe "Red Edge"	C 5-7.5L	30-40cm	4/m2	Branched; 7 breaks			
7No.	Hyd Lan 10L	Hydrangea macrophylla "Lanarth White"	C 10L	60-80cm	1/m2	Branched; 5 breaks			
12No.	Hyd que 10L	Hydrangea quercifolia	C 10L	60-80cm	2/m2	Bushy; 11 breaks			
6No.	Lav ang 15L	Lavandula angustifolia	C 15L	30-40cm	1/m2	Bushy; 7 breaks			
120No.	Lav Hid 5L	Lavandula angustifolia "Hidcote"	C 5L	20-30cm	5/m2	Bushy; 8 breaks			
42No.	Lon May 4/m2	Lonicera nitida "Maygreen"	C 3L	30-40cm	4/m2	Branched; 3 breaks			
5No.	Mah Apo 5-7.5L	Mahonia aquifolium "Apollo"	C 5-7.5L	40-60cm	3/m2	Several shoots; 6 breaks			
14No.	Pac ter var 2L	Pachysandra terminalis "Variegata"	C 2L	15-20cm	4/m2	Bushy; 5 breaks			
29No.	Per Spi 5L	Perovskia atriplicifolia "Blue Spire"	C 5L	40-60cm	4/m2	Branched; 7 breaks			
7No.	Phi BE 10L	Philadelphus "Belle Etoile"	C 10L	40-60cm	1/m2	Bushy; 5 breaks			
43No.	Pru Ott	Prunus laurocerasus "Otto Luyken"	C 3L	30-40cm	3/m2	Branched; 4 breaks			
50No.	Ros MJU 5L 3/m2	Rosmarinus officinalis "Miss Jessopp's Upright"	C 5L	40-60cm	3/m2	Bushy; 7 breaks			
7No.	Sam BL 10L	Sambucus nigra "Black Lace"	C 10L	60-80cm	3/m2	Bushy; 6 breaks			
42No.	San vir	Santolina virens	C 3L	15-20cm	3/m2	Bushy; 5 breaks			
24No.	Sar Dig	Sarcococca hookeriana "Digyna"	C 3L	20-30cm	4/m2	Bushy; 4 breaks			
5No.	Ski Rub 10L	Skimmia japonica "Rubella"	C 10L	40-60cm	1/m2	Bushy; 6 break			
28No.	Ski KG 5L	Skimmia x confusa "Kew Green"	C 5L	30-40cm	3/m2	Branched; 9 breaks			
18No.	Spi AW	Spiraea japonica "Anthony Waterer"	C 3L	30-40cm	4/m2	Bushy; 7 breaks			
5No.	Spi AW 10L	Spiraea japonica "Anthony Waterer"	C 10L	40-60cm	1/m2	Several shoots; 3 breaks			
40No.	Spi Fir 5-7.5L	Spiraea japonica "Firelight"	C 5-7.5L	30-40cm	2/m2				
7No.	Vib Pri 10L	Viburnum tinus "Eve Price"	C 10L	40-60cm	2/m2				
66No.	Vin Ger	Vinca minor "Gertrude Jekyll"	C 2L	20-30cm	5/m2				
HERBACEOUS PLANTS									
QTY	CODE	PLANT NAME	STOCK	SPACING	SPECIFICATION				
18No.	Ast Hya 3L	Astilbe 'Hyazinth'	C 3L	4/m2	Full pot				
12No.	Ast Had	Astrantia major 'Hadspen Blood'	C 3L	4/m2	Full pot				
44No.	Cal KF 10L	Calamagrostis x acutiflora "Karl Foerster"	C 10L	1/m2	Full pot				
8No.	Ech pur	Echinacea purpurea	C 2L	3/m2	Full pot				
5No.	Eup rob 5L	Euphorbia amygdaloides robbiae	C 5L	3/m2	Full pot				
19No.	Hak aur 3L	Hakonechloa macro 'Aureola'	C 3L	3/m2	Full pot				
6No.	Hel ori 5-7.5L	Helleborus orientalis	C 5-7.5L	3/m2	Full pot				
9No.	Heu KLP 5L	Heuchera "Key Lime Pie"	C 5L	5/m2	Full pot				
11No.	Sti gig 10L	Stipa gigantea	C 10L	1/m2	Full pot				
25No.	Sti Pon 5-7.5L	Stipa tenuissima "Pony Tails"	C 5-7.5L	4/m2	Full pot				
CLIMBERS									
QTY	CODE	PLANT NAME	STOCK	HEIGHT	HABIT	SPECIFICATION			
12No.	Cle mon E 10L	Clematis montana 'Elizabeth'	C 10L	100-150cm	Twiner	Caned; sev. shoots; 5 brks			
1No.	Hyd pet 10L	Hydrangea anomala petiolaris	C 10L	100-150cm	Self-clinger				
6No.	Lon jap 'Halls' 10L	Lonicera japonica 'Hall's Prolific'	C 10L	100-150cm	Twiner	Caned x 3; several shoots; 5 breaks			
PLANT MIXES									
PERCENT	QTY	PLANT NAME	STOCK	SIZE	SPECIFICATION				
116m2	GROUNDCOVER MIX 7 planted @ 4/m2								
50%	232No.	Geranium macrorrhizum "Album"	C 2L	20-30cm	Full pot				
50%	232No.	Hypericum x moserianum	C 2L	20-30cm	Bushy; 5 breaks				
Individual varieties to be planted in groups of between 5 and 7.									
48m2	GROUNDCOVER MIX 11 planted @ 4/m2								
25%	48No.	Hypericum x moserianum	C 3L	30-40cm	Bushy; 7 breaks				
25%	48No.	Leucanthemum vulgare	C 1L	-	Full Pot				
25%	48No.	Stipa tenuissima	C 3L	20-30cm	Full Pot				
25%	48No.	Vinca minor "Gertrude Jekyll"	C 3L	20-30cm	Several shoots; 3 breaks				
Individual varieties to be planted in groups of between 3 and 5.									
64m2	GROUNDCOVER MIX 16 planted @ 4/m2								
25%	64No.	Bergenia cordifolia "Purpurea"	C 2L	20-30cm	Full pot				
25%	64No.	Geranium macrorrhizum "Album"	C 2L	20-30cm	Full pot				
20%	51No.	Heuchera micrantha "Palace Purple"	C 2L	20-30cm	Full pot				
15%	38No.	Liriope muscari	C 2L	20-30cm	Full pot				
15%	38No.	Polystichum setiferum	C 2L	20-30cm	Full pot				
Individual varieties to be planted in groups of between 3 and 5.									
47m2	GROUNDCOVER MIX 28 planted @ 3/m2								
34%	48No.	Euonymus fortunei "Emerald Gaiety"	C 2L	15-20cm					
34%	48No.	Lonicera pileata	C 2L	20-30cm					
33%	47No.	Vinca minor "Gertrude Jekyll"	C 2L	20-30cm	3 breaks				
Individual varieties to be planted in groups of 3, 5 and 7.									
68m2	GROUNDCOVER MIX 33 planted @ 4/m2								
15%	41No.	Bergenia cordifolia	C 2L	20-30cm	Full pot				
15%	41No.	Ajuga reptans 'Atropurpurea'	C 2L	20-30cm	Full pot				
25%	68No.	Rubus 'Betty Ashburner'	C 2L	30-40cm	Branched; 3 breaks				
25%	68No.	Euonymus fortunei 'Emerald 'n' Gold'	C 2L	20-30cm	Bushy; 5 breaks				
15%	41No.	Brunnera macrophylla 'Hadspen Cream'	C 2L	20-30cm	Full pot				
5%	14No.	Hedera helix 'Green Ripple'	2L	40-60cm	Several shoots; 3 breaks				
Individual varieties to be planted in groups of between 3 and 5									
278m2 GROUNDCOVER MIX 35 planted @ 3/m2									
20%	167No.	Rosa "Grouse"	C 2L	20-30cm					
20%	167No.	Rosa "Max Graff"	C 3L	40-60cm	Cutting; bush; 3 breaks				
10%	83No.	Geranium x cantabrigiense 'Biokovo'	C 3L	-	Full pot				
5%	42No.	Stipa tenuissima	C 3L	20-30cm	Full Pot				
20%	167No.	Astilbe 'Deutschland'	C 3L	-	Full pot				
20%	167No.	Lonicera nitida 'Maigrün'	C 3L	30-40D	Bushy; 6 breaks				
5%	42No.	Vinca minor 'Gertrude Jekyll'	C 3L	20-30D	Several shoots; 3 breaks				
Individual varieties to be planted in groups of between 3 and 5									
614m2 SEMI-NATIVE SHRUB MIX 1 planted @ 1m centres									
5%	31No.	Acer campestre	B	200-300cm	2x; Feathered; 5 breaks				
20%	123No.	Cornus 'Sibirica'	B	60-80cm	Branched; 3 breaks				
10%	61No.	Corylus avellana	B Trans	60-80cm	1+2; Branched; 3 break				
5%	31No.	Crataegus monogyna	B Trans	80-100cm	1+2				
10%	61No.	Ilex aquifolium	C 3L	30-40cm	Leader with laterals				
5%	31No.	Prunus avium 'Plena'	B	200-300cm	2x; Feathered; 5 breaks				
20%	123No.	Prunus laurocerasus	C 10L	80-100cm	Bushy; 6 breaks				
10%	61No.	Sambucus nigra Black Lace	C 10L	60-80cm	Branched; 4 breaks				
5%	31No.	Sorbus aucuparia	B	200-300cm	2x; Feathered; 5 breaks				
10%	61No.	Viburnum plicatum 'Mariesii'	C 10L	60-80cm	Branched; 5 breaks				
Individual varieties to be planted in groups of between 5 and 11.									
46m2 MEDIUM SHRUB MIX 3 planted @ 3/m2									
20%	28No.	Choisya 'Aztec Pearl'	2L	20-30cm	Bushy; 5 breaks				
10%	14No.	Hydrangea macrophylla 'Lanarth White'	3L	40-60cm	Branched; 3 breaks				
20%	28No.	Sarcococca hookeriana digyna	3L	20-30cm	Bushy; 6 breaks				
20%	28No.	Skimmia 'Kew Green'	3L	30-40cm	Bushy; 3 breaks				
10%	14No.	Pachysandra terminalis	2L	15-20cm	Several shoots; 7 breaks				
10%	14No.	Philadelphus 'Belle Etoile'	2L	20-30cm	Branched; 3 breaks				
10%	14No.	Polystichum setiferum	1.5-2L	-	Full pot				
Individual varieties to be planted in groups of 3, 5 and 7									
208m2 ORNAMENTAL MIX 15 planted @ 4/m2									
10%	83No.	Euphorbia amygdaloides robbiae	C 2L	-	Full pot				
10%	83No.	Nepeta 'Six Hills Giant'	C 3L	-	Full pot				
10%	83No.	Hakonechloa macro 'Aureola'	C 3L	-	Full pot				
10%	83No.	Lonicera nitida 'Maigrün'	C 3L	30-40cm	Bushy; 6 breaks				
10%	83No.	Viburnum tinus 'Eve Price'	C 5L	30-40cm	Bushy; 5 breaks				
15%	125No.	Sarcococca humilis	C 3L	20-25cm	Bushy; 6 breaks				
10%	83No.	Escallonia laevis 'Gold Ellen'	C 5L	40-60cm	Bushy; 5 breaks				
15%	125No.	Skimmia x confusa 'Kew Green'	C 5L	30-40cm	Bushy; 4 breaks				
10%	83No.	Vinca minor "Gertrude Jekyll"	C 3L	20-30cm	Several shoots; 3 breaks				
Individual varieties to be planted in single species groups of 3, 5, 7 or 9no.									
Viburnum, Escallonia and Skimmia to be planted to the back of the border, or in the centre of bed if located away from a boundary feature, either singly or in groups of 3no.									
56m2 ORNAMENTAL MIX 17 planted @ 3/m2									
20%	34No.	Cornus stolonifera 'Flaviramea'	C 2L	40-60cm	Branched; 4 breaks				
20%	34No.	Corylus avellana	C 2L	40-60cm	Branched; 2 breaks				
15%	25No.	Ilex aquifolium 'Alaska'	C 3L	40-60cm	Leader with laterals				
20%	34No.	Sarcococca hookeriana digyna	C 3L	20-30cm	Bushy; 6 breaks				
17%	17No.	Viburnum davidii	C 5L	30-40cm	Bushy; 4 breaks				
15%	25No.	Viburnum plicatum 'Mariesii'	C 3L	40-60cm	Leader with laterals				
Individual varieties to be planted in single species groups of 3-9no.									
28m2 SHADE MIX 9 planted @ 3/m2									
30%	25No.	Euonymus fortunei 'Emerald Gaiety'	C5L	25-30cm	Bushy; 9 breaks				
25%	21No.	Pittosporum tenuifolium 'Tom Thumb'	C5L	30-40cm	Bushy; 5 breaks				
25%	21No.	Viburnum davidii	C5L	30-40cm	Bushy; 4 breaks				
20%	17No.	Pachysandra terminalis 'Variegata'	C2L	15-20cm	Several shoots; 6 breaks				
Individual varieties to be planted in groups of 1, 3 and 5.									
32m2 SHADY MIX 16 planted @ 3/m2									
25%	24No.	Bergenia cordifolia	C 2L	20-30cm	Full pot				
25%	24No.	Euonymus fortunei 'Emerald Gaiety'	C 3L	20-30cm	Bushy; 5 Breaks				
25%	24No.	Geranium macrorrhizum "Johnsons Blue"	C 2L	20-30cm	-				
25%	24No.	Lonicera pileata	C 2L	20-30cm	-				
Individual varieties to be planted in groups of 1, 3 and 5.									
40m2 SHADY MIX 17 planted @ 3/m2									
25%	30No.	Hakonechloa macro 'Aureola'	C3L	-	Full pot				
25%	30No.	Heuchera micrantha 'Palace Purple'	C3L	-	Full Pot				
25%	30No.	Pachysandra terminalis	C3L	20-30cm	Several shoots; 9 breaks				
25%	30No.	Pittosporum tenuifolium 'Tom Thumb'	C3L	20-30cm	Bushy; 3 breaks				
Individual varieties to be planted in groups of 1, 3 and 5.									
53m2 SHADY MIX 18 planted @ 3/m2									
25%	40No.	Asplenium scolopendrium	C3L	-	Full Pot				
25%	40No.	Euphorbia amygdaloides robbiae	C5L	-	Full pot				
25%	40No.	Vinca minor "Atropurpurea"	C2L	20-30cm	Several shoots; 3 breaks				
25%	40No.	Skimmia japonica "Rubella"	C3L	30-40cm	Bushy; 3 break				
Individual varieties to be planted in groups of 1, 3 and 5.									
Skimmia to be planted at minimum 500mm from path edge.									
88m2 SUNNY MIX 10 planted @ 3/m2									
20%	53No.	Hebe 'Red Edge'	C5L	30-40cm	Bushy; 7 breaks				
20%	53No.	Choisya ternata "Aztec Pearl"	C3L	30-40cm	Bushy; 5 breaks				
20%	53No.	Sedum 'Autumn Joy'	C3L	-	Full Pot				
20%	53No.	Spiraea japonica 'Gold Mound'	C3L	30-40cm	Bushy; 6brks				
20%	53No.	Vinca minor "Gertrude Jekyll"	C2L	20-30cm	3 breaks				
Individual									
66m2 SUNNY MIX 12 planted @ 3/m2									
25%	50No.	Carex elata 'Aurea'	C3L	-	Full pot				
25%	50No.	Rosmarinus officinalis "Miss Jessopp's Upright"	C3L	30-40cm	Bushy; 4 breaks				
25%	50No.	Santolina virens	C3L	20-30cm	Bushy; 7 breaks				
25%	50No.	Spiraea japonica 'Firelight'	C5L	40-60cm	Bushy; 6brks				
Individual varieties to be planted in groups of 1, 3 and 5.									
37m2 SUNNY MIX 13 planted @ 3/m2									
25%	28No.	Deschampsia cespitosa 'Goldtau'	C2L	-	Full pot				
25%	28No.	Euonymus fortunei "Silver Queen"	C3L	20-30cm	Bushy; 5 breaks				
25%	28No.	Lavandula angustifolia 'Hidcote'	C5L	20-30cm	Bushy; 7 breaks				
25%	28No.	Vinca minor "Gertrude Jekyll"	C2L	20-30cm	3 breaks				
Individual varieties to be planted in groups of 1, 3 and 5.									
37m2 BULB PLANTING 2 planted @ 15/m2									
50%	278No.	Galanthus nivalis		Grade 5/6					
50%	278No.	Narcissus pseudonarcissus		10-12cm					
34m2 BULB PLANTING 6 shade planted @ 20/m2									
35%	238No.	Hyacinthoides non-scripta		Grade 8/9					
35%	238No.	Cyclamen coum		Grade 10/13					
30%	204No.	Anemone nemorosa		Size 1					
Individual varieties to be planted in groups of approximately 7-11.									
66m2 BULB PLANTING 7 planted @ 20/m2									
50%	660No.	Hyacinthoides non-scripta		Grade 8/9					
50%	660No.	Galanthus nivalis		Grade 5/6					
Individual varieties to be planted in groups of approximately 7-11.									
NOTES AND ABBREVIATIONS:									
B = Bare root (bagged).									
C = Container (or pot) grown, followed by size of the container (or pot).									
FORM = Shape of tree as supplied by the nursery.									
Fth = Feather.									
HABIT = Juvenile habit or plant shape as supplied by the nursery.									
QTY = Quantity									
RB = Rootballed (balled and wrapped).									
SIZE = Height or Spread of juvenile plant.									
Std = (clear stem) Standard.									
STOCK = Root condition/protection method eg Bare root.									
Trans = Transplant (or undercut seedling).									
Twiner = Twining climber attached to trellis/frame, refer to specification.									
- Refer to specification for further information.</									