



### Product Information

Ibstock Code:	2426
Type:	Wirecut
Facing Description:	Rolled
Dry Brick Weight (kg):	2kg
Pack Quantity:	475
Packaging (standard):	Banded (plastic) & Shrinkwrapped
Factory:	Dorket Head

### Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T2 R1
Configuration:	Vertically Perforated
Voids (%):	20-25
Compressive Strength (N/mm <sup>2</sup> ):	40
Active Soluble Salts:	S2
Water Absorption (% weight):	16
Durability:	F2
Gross Dry Density (Sound Insulation) (Kg/m <sup>3</sup> ):	1390
Equivalent Thermal Conductivity "K" value 5% Exposed:	Refer to Ibstock
Initial Rate of Absorption (Suction Rate) (Kg/m <sup>2</sup> /min):	Refer to Ibstock
EAN:	5036335013977