



SPECIFICATION

- ① Black plastic trim, fixed to aluminium carcass using small pan head screws with heads painted black
- ② 2mm thick aluminium carcass finished white inside and satin black RAL9005 externally
- ③ Tridonic P560 crystal white LED, 38 off modules required. One off Tridonic Talex LCU 060/12 D010 120/240v converter required
- ④ 3mm thick 050 Opal perspex face with face applied translucent vinyl 3M scotchcal vinyl Holly Green 3630-76