



MATERIALS. ALL MATERIALS USED WITHIN ESCAPE ROUTES MUST BE OF CLASS AS DEFINED IN BS 476 PART 7, 1987 (FLOOR COVERINGS) TO ESCAPE ROUTES TO BE TESTED IN ACCORDANCE WITH BS 7924 NEW COVERINGS THAT CONFORM TO THIS STANDARD ARE LABELLED AS BS870.

HEAT DETECTORS. HEAT DETECTORS TO COMMON ROOM AND KITCHEN.

SMOKE DETECTORS. TO ALL HABITABLE ROOMS AND STAINWELL AT EACH LEVEL.

ALARM SOUNDERS. TO BE FITTED IN EACH BEDROOM.

EMERGENCY BREAK GLASS CALL POINTS. TO BE FITTED TO FIRST FLOOR LANDING, KITCHEN AREA, AND BY ROOM DOOR IN COMMON ROOM.

CONTROL PANEL.

FIRE CONTROL. PANEL AND INDICATING EQUIPMENT MUST COMPLY WITH BS 5838 PART 4, 1996. THE CONTROL PANEL SHOULD BE READILY VISIBLE UPON ENTERING THE PREMISES.

EMERGENCY LIGHTING SYSTEMS.

EMERGENCY LIGHTING SYSTEMS. MUST COMPLY WITH BS 5266, PART 1, 1998. ALL STAIRWAYS, LANDINGS AND PASSAGES FORMING THE EMERGENCY ESCAPE ROUTE MUST BE ILLUMINATED BY A LUMINAIRE MUST BE POSITIONED AT EACH LANDING.

MATERIALS.

ALL MATERIALS USED WITHIN ESCAPE ROUTES MUST BE OF CLASS AS DEFINED IN BS 476 PART 7, 1987 (FLOOR COVERINGS) TO ESCAPE ROUTES TO BE TESTED IN ACCORDANCE WITH BS 7924 NEW COVERINGS THAT CONFORM TO THIS STANDARD ARE LABELLED AS BS870.

ELECTRICAL SAFETY.

THE SYSTEMS SYSTEM (INCLUDING ELECTRICAL APPLIANCES) SHOULD BE CHECKED BY AN **IMCER** REGISTERED COMPETITOR AND A **PERIODIC** INSPECTION CERTIFICATE SUPPLIED.

CONFINING THAT THE ENTIRE INSTALLATION HAS BEEN COMPLETED BY THE **IMCER** INSTITUTE OF ELECTRICAL ENGINEERS (IEE) (WHEN REGULATIONS 16TH EDITION).

FIRE EQUIPMENT KEY

[NI] FIRE DOOR, KEEP LOCKED SHUT NOTICE
FIRE DOOR, KEEP CLOSED NOTICE TO BOTH SIDES OF DOOR

[NO] FIRE PROCEDURE NOTICE
FLOOR, HALL OR STAIRS FIRE DOOR WITH SMOKE SEAL

[EL] EMERGENCY LUMINAIRE
SMOKE DETECTOR

[A] BREAK GLASS ALARM POINT
MULTI RISK EXTINGUISHER (FOAM, WATER, CARBON DIOXIDE, EXTINGUISHER ELECTRICAL)

[A CO2] FIRE ALARM UNIT
FIRE ALARM SOUNDER (LINKED TO GENERAL SYSTEM)

The figure is a detailed architectural site plan of a residential area. The central focus is the intersection of Stanhope Street and Farbar Street. A red rectangle highlights a specific lot at this intersection, labeled with the number 35. Adjacent lots are labeled 32, 29, and 14. The plan shows the layout of buildings, streets, and surrounding features like 'Askins Court' and 'Groves'. A north arrow is located in the upper right corner of the plan.

LAYOUT AS PROPOSED

LAYOUT AS EXISTING

architecturaldrawings Ltd
DESIGN | DEVELOPMENT | BUILDING

DESIGN | DEVELOPMENT | BUILDING

www.architecturaldrawingsltd.co.uk

REVISIONS
Ms. 1944v

No.	Date
-----	------

**MR TRUEMAN
25 FARRAH STREET
BARNLEY S70 6BT**

**PROPOSED DORMER
WINDOWS
EXISTING & PROPOSED**

DRAWING STATUS

GENERAL ARRANGMENT

SCALE 1:100 @ A1

DATE **MAY 2015**

JOB NO.	DRAW
---------	------

687 | 01

101
1067