



## PAP-POLO LED HOOP LUMINAIRE

PAP-POLO is a decorative pendant hoop luminaire available in a range of sizes and outputs.

Available as Direct or Direct/Indirect with an efficacy of up to 118 lumens/W and a service lifetime in excess of 75,000 hours.





### SPECIFICATION

- Fabricated steel housing
- Opal PETG diffuser
- Suspension mount
- White powder-coated finish (other colours available upon request)
- Direct or Direct/Indirect light distribution
- 75,000 hours L70/B10
- Options:
  - Emergency EM3
  - DALI, DSI, 1-10V, Swt Dim
  - Colour Temp: 3K/4K/6K
  - Bespoke variants upon request



Suitable for a variety of architectural and commercial lighting applications.



Product	PAP-POLO-500 Direct	PAP-POLO-700 Direct	PAP-POLO-900 Direct	Product	PAP-POLO-500 D/I	PAP-POLO-700 D/I	PAP-POLO-900 D/I
LxWxH	500x500x80	700x700x80	900x900x80	LxWxH	500x500x80	700x700x80	900x900x80
Wattage CW	30	41	60	Wattage CW	40	53	73
Luminaire Lumens	2900	3900	5480	Luminaire Lumens	4730	5460	7645
LL/CW	97	95	91	LL/CW	118	103	105
Colour Temp (k)	4000	4000	4000	Colour Temp (k)	4000	4000	4000
Ra	>80	>80	>80	Ra	>80	>80	>80
Colour Consistency SDCM	2	2	2	Colour Consistency SDCM	2	2	2
L70/B10	>75k	>75k	>75k	L70/B10	>75k	>75k	>75k