



SUGGESTED ACTION
INSURE ALL EXCAVATIONS HAVE ADEQUATE TRECHS SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS. BE CORRECT LIFTING EQUIPMENT AND ENSURE OPERATIVES WEAR THE CORRECT PERSONAL PROTECTIVE EQUIPMENT. BE GAS DETECTION/SERBATHING EQUIPMENT AND ENSURE OPERATIVES WEAR THE CORRECT PERSONAL PROTECTIVE EQUIPMENT. OPERATIVES TO WEAR THE CORRECT EAR PROTECTION. UTILITY MANS TO BE INSPECTED AND APPARATUS LOCATED USING APPROPRIATE EQUIPMENT PRIOR TO EXCAVATION. INSURE ALL EXCAVATIONS HAVE ADEQUATE TRECHS SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS. INSURE THE CORRECT SIGNAGE/TRAFFIC CONTROL IS USED.

- [illegible]

kerb faces and service margins.

refer to Figure 2, page 33 in Sewers for Adoption 6th Edition for instructions on tree planting adjacent to sewers).

Sewers to be laid in Class "S" bedding (150mm granular bed & surround), the depth of cover to the top of the sewer is less than 1.2m in Highway verges (or less than 900mm in non vehicular areas) then a concrete should be provided above the granular bed and the movements of the bedding and backfill material to conform to the movements of the surrounding ground.

Preliminary

Rev	Details	Date	Dwn.	Chk.
B	Changes to Layout.	24-20	AST	
A	Changes to Layout.	15-1-20	AST	

Avant Homes

Lidgett Lane/Pilley Green
Pilley, Barnsley

Section 38/278 Layout

Dwg No.: STE/19/28/13 B

Date : 8-1-20

Scale : 1:500