



# Street Lighting Arrangement

 New 10M Ral 9006 steel column with Philips City soul Gen 2 lantern complete with electronic PECU Model BPP531 T35 DW GRN185 740 post mount RAL9006 with 7 pin NEMA and 14 metres cable

 Disconnect old column and remove to Council tip, return lantern to council stores

All materials to comply fully with current BMBC Street Lighting Specification.

The street lighting columns and lanterns and their maintenance remain the responsibility of the developer until completion of the adoption process.

All lighting columns are to be provided with an unmetered single phase electricity supply via the REC cable network. It is expected that the developer will coordinate with the REC regarding the installation of any cable ducts they may require.



Rev	By	Revision Details	Date

 **BARNESLEY**  
Metropolitan Borough Council

Project: **Midland Street Street Lighting Works**

Title: **Street lighting and Electrical Proposals**

Scale	Drawn	Checked	Date
1:300	SGA		23/8/21

Drawing No.		Rev
A1	SL20-66/1300/Midland/01	