

SUBJECT TO THE
APPROVAL OF
ALL RELEVANT
AUTHORITIES

FOR CONTINUATION SEE BELOW

N O T E S

ATTENTION IS DRAWN TO THE REQUIREMENTS OF
THE CONSTRUCTION DESIGN AND MANAGEMENT
REGULATIONS 2015 AND THE DUTIES AND
RESPONSIBILITIES CONTAINED THEREIN

KEY

- Gully
- Storm water manhole
- Foul water manhole
- Storm water sewer
- Foul water sewer
- Combined sewer
- Channel Drain (min B125 grade cover)
- Yard gully

COLOUR KEY

- Footways and footpath (including cycle routes)
- 600mm wide hard margins laid in stretcher
bond (block paving)
- Flexible surfaced carriageways
- Sett paved carriageways
- Ramps and rumble strips (block paving)
- YW S104 Easement
- Service margins
- Highway drainage
- Street Lighting
- S278 Boundary

- Refer to typical section Drawing No 0425/87/04.01, 0425/87/04.02 & 0425/87/04.03 for typical highway details.
- Dropped kerbs and tactile pavings are required at the junctions to facilitate the movement of wheelchairs etc. The dropped kerbs to be laid with a 0-6mm upstand.
- Adaptable sewers are not to be constructed under or within 1.0 metres of any footpath/kerb line / service strip.
- Off-site drainage already built must have invert levels checked prior to connection of the site drainage.
- Gully positions shown are subject to adjustment on site to ensure full drainage and the absence of ponding.
- No walls are to be constructed 1m of the highway drains located in gardens or verge.
- No water should be allowed to discharge from any private drives onto the adoptable highway.
- All highway works are to be the subject of a Section 38 Agreement of the highways Act 1980.
- All public sewers to comply with the requirements of the Water Authorities publication "Code for Adoption" together with any additional specific requirements of the drainage authority.
- All public sewers are to be the subject of a Section 104 Agreement of the Water Industry Act 1991.
- Any coated base material in carriageway left exposed for more than seven days to be sealed using bituminous sealing grit.
- Highway boundary to be indicated by back edgings laid flush or change of material on Private drives.
- All vertical faces of joints involving flexible materials shall be treated with "Oxy-bit" or other approved joint sealant. This includes ironwork, and precast products. Overbanding will not be accepted with Barnsley Council.

E	BHB	08.02.23	S278 boundary & Gullies amended	RJ	MI
D	RJ	23.12.22	Revised to new planning layout 11.10.22	RJ	MI
C	JMG	18.08.22	Updated to client comments, Forward visibility added	RJ	MI
B	JMG	20.07.22	S278 information added	RJ	MI
A	DJG	28.06.22	Revised to suit new layout		
/	DJG	27.05.22	Issued for approval	MI	MI
Rev	By	Date	Revision	Chk	Apvd

ARP ARP ASSOCIATES
Chartered Consulting Engineers

Northwest House • 5 & 6 Northwest Business Park • Servia Hill, Leeds • LS6 2QH
0113 245 8498 0113 244 3864 leeds@arpassociates.co.uk www.arpassociates.co.uk
ARP Associates is a trading division of ARP Geotechnical Ltd, a company registered in England and Wales with company number 3773831, whose registered office is at 5/6 Northwest Business Park, Servia Hill, Leeds LS6 2QH

TITLE

SECTION 38 LAYOUT
SHEET 1 OF 2

PROJECT

GYPSY LANE,
WOMBWELL

CLIENT

MILLER HOMES
(YORKSHIRE) LTD

DRAWING STATUS

PRELIMINARY

Scale

1:500 @ A1

Date

MAY 22

Drawn

DJG

Chk.

MI

Drg. No.

0425/87/02.01

Rev

E



GYPSY LANE FORWARD VISIBILITY (1:500)

FOR CONTINUATION SEE ABOVE