DO NOT SCALE: CONTRACTOR TO CHECK ALL DIMENSIONS AND REPORT ANY OMISSIONS OR ERRORS

N

OLD MILL

OLD TANNERY ROAD

River Dearne

ANTIFREEZE BOILER HOUSE TO BE REMOVED

CONCRETE FOOTBRIDGE TO REMAIN

EMBANKMENT

2.3m HIGH PALISADE FENCE

1.1m HIGH WALL

0.4m HIGH WALL

CONCRETE

CONCRETE FOOTBRIDGE

0.8m HIGH PALISADE FENCE

ALL ABOVE-GROUND PIPEWORK, VALVES AND SUPPORTS TO BE REMOVED. HOLES IN EXISTING PALISADE FENCE TO BE MADE GOOD ONCE PIPEWORK HAS BEEN REMOVED

CUBICLE TO BE REMOVED

GRAVEL

GRASS

LIGHTING COLUMN TO BE REMOVED

STAIRS TO BE REMOVED

SIPHON PITS TO BE PUMPED OUT, CLEARED AND BACKFILLED IN ACCORDANCE WITH THE SPECIFICATION

2.3m HIGH PALISADE FENCE

EXISTING 500mm HIGH CONCRETE UPSTAND AROUND GASHOLDER BASE TO BE RETAINED. ON COMPLETION OF GASHOLDER REMOVAL THE REMAINING SHALLOW TANK IS TO BE BACKFILLED TO TOP OF UPSTAND IN ACCORDANCE WITH THE SPECIFICATION

CONCRETE

CONC UPSTAND

GRASS

EMBANKMENT

GASHOLDER No.4 TO BE REMOVED.

ABOVE GROUND GASHOLDER DEMOLITION WORKS INCLUDE DEWATERING, DESLUDGING, REMOVAL OF STEELWORK AND REMOVAL OF REDUNDANT PIPEWORK

WOODED WITH NUMEROUS SMALL TREES

2.3m HIGH PALISADE FENCE

River Dearne

BELOW-GROUND OIL SEPARATOR OVERFLOW SYSTEM TO BE REMOVED AND VOIDS BACKFILLED IN ACCORDANCE WITH THE SPECIFICATION

2.3m HIGH PALISADE FENCE

GRAVEL

CONCRETE

0.4m HIGH ARMCO BARRIER

CONC UPSTAND

CONCRETE BLOCK TO BE REMOVED

LIGHTING COLUMN TO BE REMOVED

ARMCO BARRIER TO BE REMOVED

TREE CANOPY

2.3m HIGH PALISADE FENCE

LIGHTING COLUMN TO BE REMOVED

GRASS

KERB

CONCRETE

GRASS

NOTE:
ALL EXISTING PALISADE FENCING TO REMAIN

2.3m HIGH PALISADE FENCE

CONCRETE ROAD TO REMAIN

CONCRETE

ASPHALT

Depot

Reproduced from Ordnance Survey Digital Data by permission of Ordnance Survey ® on behalf of the Controller of Her Majesty's Stationery Office. © Crown Copyright. All rights reserved. Reference number 100017603.

NOTES

1. DO NOT SCALE
2. DRAWINGS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT CONTRACT DRAWINGS AND SPECIFICATION
3. ANY DISCREPANCIES ON THIS DRAWING NOTED BY THE CONTRACTOR SHALL BE BOUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO COMMENCEMENT OF WORKS ON-SITE
4. ANY SURVEY INFORMATION USED IN THE PREPARATION OF THE DRAWING IS NOT WARRANTED. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THIS SURVEY INFORMATION PROVIDED
5. THE CONTRACTOR IS REQUIRED TO ADMINISTER ALL ASPECTS OF THE SITES HEALTH AND SAFETY DURING HIS POSSESSION IN ACCORDANCE WITH ALL CURRENT CODES OF PRACTICE AND LEGISLATION GOVERNING HEALTH AND SAFETY AND TO COMPLY WITH ALL CDM REGULATIONS
6. NO DEMOLITION WORKS ARE TO TAKE PLACE UNTIL A WRITTEN METHOD STATEMENT / DEMOLITION PLAN HAS BEEN PREPARED AND COMMUNICATED TO ALL SITE PERSONNEL
7. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL SERVICES ON THE SITE PRIOR TO COMMENCING THE WORKS. THE CONTRACTOR IS TO LIAISE WITH THE RELEVANT STATUTORY UNDERTAKERS. CONTACT DETAILS ARE AVAILABLE IN THE PRE-TENDER HEALTH & SAFETY PLAN
8. THE CONTRACTOR IS TO REFER TO THE RELEVANT DEMOLITION / REFURBISHMENT ASBESTOS SURVEY REPORT FOR THE IDENTIFICATION AND LOCATION OF ALL ASBESTOS CONTAINING MATERIALS IN THE BUILDINGS TO BE DEMOLISHED, AND IS TO CARRY OUT THE REMOVAL OF ALL ASBESTOS CONTAINING MATERIALS IN ACCORDANCE WITH THE SPECIFICATION AND CURRENT LEGISLATION PRIOR TO THE DEMOLITION WORKS COMMENCING
9. THE CONTRACTOR IS TO REFER TO THE RELEVANT HAZARDOUS MATERIALS INFORMATION IN THE SPECIFICATION AND IS TO REMOVE AND PROPERLY DISPOSE OF ALL HAZARDOUS MATERIALS IN ACCORDANCE WITH THE SPECIFICATION AND CURRENT LEGISLATION PRIOR TO THE DEMOLITION WORKS COMMENCING

KEY

- NATIONAL GRID PROPERTY SITE OWNERSHIP BOUNDARY
- BUILDINGS / STRUCTURES TO BE REMOVED
- H — APPROXIMATE EXTENT OF HERAS FENCE AS DEMARKATION AROUND INVASIVE SPECIES AREAS

0 2.5 5 7.5 10 12.5 m

SCALE 1:250

REV	DESCRIPTION	BY	CHK	APP	DATE
A	GENERAL AMMENDEMNTS	RLC	MB	MB	09.04.14

Client

NATIONAL GRID PROPERTY HOLDINGS LTD

GENEVA BUILDING,
LAKE VIEW DRIVE,
SHERWOOD BUSINESS PARK,
ANNESLEY, NOTTINGHAMSHIRE
NG15 0ED

TEL: +44 (0)1623 684 550
e-mail: nottingham@wyg.com

Project:

GASHOLDER DEMOLITION
BARNSLEY

Drawing Title:

GASHOLDER
DEMOLITION REQUIREMENTS

Scale @Custom	Drawn	Date	Checked	Date	Approved	Date
1:250	RLC	20.03.14	MB	27.03.14		

Project No.	Office	Type	Drawing No.	Revision
A074754-149	51	CS	B004	A

© WYG Group Ltd.