



Hampton Rural Blend

Hampton Rural Blend

Manufactured to BS EN 771-1

Brick type

Category II, HD, Clay Masonry Unit

Standard work size

215 x 102.5 x 65mm

Dimensional tolerances

Tolerance category: T2

Range category: R1

Compressive strength

$\geq 20\text{N/mm}^2$

Water absorption

$\leq 13\%$

Durability

F2

Active soluble salts content

S2

Configuration

Frogged 5-10% voids

Dry weight per brick

2.35kg

Pack size

495

This panel is printed on paper made using ecf from fibres obtained from a sustainable timber source.

DISCLAIMER:

The reproduction of colours and textures is only as accurate as the printing process will allow. Photographic samples should be used when shortlisting products but we advise that an actual sample should be seen before ordering.



Hanson Building Products
222 Peterborough Road
Whittlesey
Cambridgeshire
PE7 1PD

Tel: 08705 258258
Fax: 01234 762040

www.hanson.com/uk