

Tree Number	Common Name	Botanical Name	Height (m)	Effective Diameter (mm)	Branch spread (m)				Crown Clearance (m)	Age class	Physiological condition	Structural condition	Observations	Recommendations	Visual Amenity Value	Remaining contribution (years)	Category grading	RPA radius (m)
					North	East	South	West										
1	Cut leaf beech	<i>Fagus sylvatica</i>	10	370	4.5	7.4	6.5	3.0	2	Semi mature	Fair	Fair	A multi-stem tree. The main stems have crossed and grafted multiple times creating an interesting feature which is hidden from view by epicormic growth. Tree grafted near ground level.	Crown lift to 5m	Medium	20+	B1	4.4
2	Chestnut	<i>Aesculus sp.</i>	10	340	1.5	4.5	5.7	5.0	2	Semi mature	Fair	Fair	A twin stem tree with no major apparent defects. Tree grafted near ground level.	Crown lift to 5m	Medium	20+	B1	4.1
3	Copper beech	<i>Fagus sylvatica</i> <i>'Purpurea'</i>	11	770	6.5	7.0	7.0	6.5	3	Mature	Fair	Fair	A single stem tree with no major apparent defects.	Crown lift to 5m	Medium	20+	B1	9.2
4	Deodar cedar	<i>Cedrus deodara</i>	17	700	5.5	7.5	6.5	1.0	1	Semi mature	Fair	Fair	A single stem tree with no major apparent defects.	Crown lift to 5m	Medium	20+	B1	8.4
5	Copper beech	<i>Fagus sylvatica</i>	15	560	8.5	4.5	6.0	4.5	2	Semi mature	Fair	Fair	A single stem tree with no major apparent defects. Grafted near ground level. Meripilus fruiting bodies were found near this tree, but the patterns of distribution suggest that it is not this tree which is infected. Additionally, the crown of the tree appears to be healthy, with no signs of die-back or thinning as a result of root infection.	Crown lift to 5m	Medium	20+	B1	6.7