CATCHMENT 1
7.25 Ha Gross
3.98 Ha Impermeable

CARLOW Pre Cast
TANK
50m x 25m x 2m
Volume = 2500m³

HYDROBRAKE
30.75 l/s

Foul
Pumping
Station

Nominal bund to retain water
between 30 yr and 100yr event

1.5mØ Storage Pipe, 65m long

CATCHMENT 2
0.90 Ha Gross
0.50 Ha Impermeable

Health and Safety Notes/CDM Regulations 2007

In line with the above regulations we are obliged to inform the Contractor of the abnormal risks that may be encountered in the construction of these works. As part of the design process all the salient health & safety aspects are given full consideration and these are observed within the designs viewed on this document. Although considerable effort is undertaken to eliminate risks, the very nature of the project gives rise to some hazards and risks.

Significant risks that cannot be eliminated by design and could not be foreseen by a competent contractor are noted in the risk assessment boxes on the drawings.

Rev	Description	By	Date

Client:

Persimmon Homes West Yorkshire

Project Title:

Wilthorpe Road, Barnsley

Drawing Title:

Drainage Strategy

Scale	Date
1:1000 @ A1	March 2014

Drawing No	Revision	Status
4015-FRA05	0	Comment

Geo
Structures
Civils
iD Civils Design
Consulting Engineers

North East & Yorkshire:
Aske Stables, Aske, Richmond,
North Yorkshire, DL10 5HG
t: 01748 889015
f: 01565 740263

North West & Midlands:
Caledonian House,
Tatton Street, Knutsford,
Cheshire, WA16 6AG
t: 01565 755557
f: 01565 740263