© Buro Happold Limited or its group companies.
All Rights reserved. Buro Happold and its group companies assert (unless otherwise agreed in writing) their rights under s.77 to 89 of the Copyright, Designs and Patents Act 1988.

DO NOT SCALE THIS DRAWING.

HEALTH AND SAFETY INFORMATION

IN ADDITION TO THE HAZARDS/RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING:

CONSTRUCTION.

MAINTENANCE/CLEANING/OPERATION.

DECOMMISSIONING/DEMOLITION.

Notes

KEY:

- FOUL WATER DRAINAGE
- SURFACE WATER DRAINAGE
- RAIN WATER DRAINAGE

REQUIREMENTS FOR FOOTPATH DRAINAGE T.B.C.

LAND DRAINAGE BY PITCH SPECIALIST. TO OUTFALL TO SURFACE WATER SYSTEM

POSSIBLE DIVERSION REQUIRED

MAKE AN ALLOWANCE FOR UNDERSLAB DRAINAGE. LAYOUT T.B.C.

LAND DRAINAGE BY PITCH SPECIALIST. TO OUTFALL TO SURFACE WATER SYSTEM

LAND DRAINAGE BY PITCH SPECIALIST. TO OUTFALL TO SURFACE WATER SYSTEM

PROPOSED FOUL WATER PUMP LIMITED TO 8l/s

RAIN WATER HARVESTING TANK

ATTENUATION TANK. ATTENUATION REQUIREMENTS 1000m³

NEW OUTFALL REQUIRED. OUTFALL ARRANGEMENTS T.B.C.

FLOW CONTROL HYDROBRAKE MANHOLE

PROPOSED POLLUTION CONTROL DEVICE – BYPASS SEPARATOR

FLOW CONTROL HYDROBRAKE MANHOLE

REQUIREMENT TO REPLACE EXISTING OUTFALL T.B.C. FOLLOWING AN ASSESSMENT OF THE CONDITION & CAPACITY OF THE EXISTING OUTFALL

ROAD DRAINAGE TO OUTFALL TO RIVER DOVE

CAR PARK IN ABEYANCE

ATTENUATION TANK. ATTENUATION REQUIREMENTS 400m³

MAKE AN ALLOWANCE FOR ROAD GULLIES EVERY 18 LINEAR METRES

EXISTING YORKSHIRE WATER SEWER

SURFACE WATER ROAD DRAINAGE TO OUTFALL TO BULLING DIKE

ATTENUATION TANK. ATTENUATION REQUIREMENTS 400m³

FOUL WATER DRAINAGE TO OUTFALL TO EXISTING FOUL SEWER SECTION 106 REQUIRED

FLOW CONTROL HYDROBRAKE MANHOLE

EXISTING YORKSHIRE WATER SEWER

NEW OUTFALL TO BULLING DIKE REQUIRED. OUTFALL ARRANGEMENTS T.B.C.

SECTION 278 DESIGN IN ABEYANCE

Rev	Description	Date	Drn	Chkd

PRELIMINARY

Status of drawing

Barnsley Partnership For Learning
LAING O'ROURKE
2 Brewery Place
Brewery Wharf
Leeds LS10 1NE
UK
Tel: +44 (0)113 204 2000
Fax: +44 (0)870 787 4144
Email: 022413@burohappold.com
Web: www.burohappold.com
Buro Happold
Consulting Engineers

Architect	AEDAS
Project	Barnsley BSF - Foulstone and Wombwell
Drg Title	Civil Infrastructure Drainage Strategy
Scales@A0	1:1000
Drawn by	MB
Checked by	VC
Date	Apr-09
Job No.	026077
Drawing No.	CSK04
Rev	-

BP4L_WOM_BUR_DR_