

Facility Issue	Activity/Mitigation	Additional Comments
<p>Development of the site</p>	<p>Works are to comply with the Control of Noise at Work Regulations (2005)</p>	<p>Contractor to submit Construction Phase Plan to confirm management of noise arising from works.</p>
<p>Hours of operation:</p> <p><u>Building</u> Monday-Sunday – 9am -11pm</p> <p><u>Sports Pitch &amp; Archery Range</u> Monday-Friday – 9am -10pm Saturday &amp; Sunday – 9am – 6pm</p>	<p>Internal activities will range from fitness classes to community meetings as well as use of the changing facilities by both internal and external facility users.</p> <p>The pitch will be used for football.</p> <p>The archery range is unlit and will therefore only be used during daylight hours.</p> <p>Closure of the site by staff will ensure that all participants or spectators are off site by 11:30pm.</p> <p>Ventilation plan mean windows should not require opening which will mitigate use of music.</p> <p>Event organisers to be made aware of, and agree, to the specific space and conditions of use.</p>	
<p>Social/Activity Area within the Pavilion.</p>	<p>Appropriate operating times for activities and the movement of users off site.</p> <p>Activities and their noise during operating times will be contained within the indoor footprint of the pavilion.</p>	

	<p>Activities will be limited to indoor low level multi sports activities including fitness sessions and social activity groups.</p> <p>Windows and door closed except in extenuating circumstances i.e., extreme warm weather.</p> <p>Ventilation plan mean windows should not require opening which will mitigate use of music.</p>	
--	---	--

<p>Immediately Outside Pavilion</p>	<p>Event organisers to be made aware of the specific space and conditions of use.</p> <p>Dedicated smoking area that locates potential smokers away from residential areas.</p> <p>Relevant signage to be installed guiding users to be considerate of surrounding residents.</p> <p>Terms and conditions of bookings will specifically ask event organisers to agree to.</p>	
<p>Car Park Noise</p>	<p>Carpark entrance &amp; exit via old Sheffield Road entrance, Slow speed notices to be displayed for site Health &amp; Safety along with noise reduction.</p>	<p>Aim for Carpark to be empty within 30 mins of the centre closing on any given night and for special functions.</p>

<p>Playing area – Football Noise</p>	<p>Pitch is orientated lower than surrounding levels to reduce noise pollution.</p> <p>Fencing/rebound noise – dividing curtains have no sound issues. The surrounding fence is set back from the playing area to mitigate potential noise.</p> <p>Booking terms and conditions will have reference to noise especially the use of bad language and the relevant consequence.</p> <p>Relevant noise mitigations will be confirmed and put in place to ensure that the noise levels comply with World Health Organisation and Sport England Guidance on the recommended 50db limit.</p> <p>A 4m. high acoustic fence is proposed along the north side of the pitch to protect the residential properties on Parkside Road.</p>	<p>Spectator areas to the lower side of the site furthest from neighbouring properties</p>
<p>Playing area – Archery noise</p>	<p>Range is at least 100meters away from any neighbouring property and a quiet participant sport.</p> <p>Archery activities would have limited noise output.</p>	

<p>Maintenance Garage Noise</p>	<p>Sited away from neighbouring residences on a lower plateau with close board screening for visual &amp; acoustic benefit.</p> <p>Where reasonably practicable, ensuring the use of quiet working methods.</p>	<p>No work from the Garage area after 8:00pm</p>
---------------------------------	---	--