

Project name

Lidl Hoyland - Be Lean**As designed****Date:** Fri Dec 17 13:42:46 2021

Administrative information

Building Details

Address: ,

Certification tool

Calculation engine: TAS**Calculation engine version:** "v9.5.0"**Interface to calculation engine:** TAS**Interface to calculation engine version:** v9.5.0**BRUKL compliance check version:** v5.6.a.1

Owner Details

Name: Lidl Great Britain Ltd**Telephone number:** 0800 977 7766**Address:** 19 Worpole Road, Wimbledon, London, SW19 4JS

Certifier details

Name: Stephen Ogden**Telephone number:** 01924 265757**Address:** RCM Business Centres, Dewsbury Road, Ossett, Wakefield, WF5 9ND**Criterion 1: The calculated CO₂ emission rate for the building must not exceed the target**

CO ₂ emission rate from the notional building, kgCO ₂ /m ² .annum	26.4
Target CO ₂ emission rate (TER), kgCO ₂ /m ² .annum	26.4
Building CO ₂ emission rate (BER), kgCO ₂ /m ² .annum	20.5
Are emissions from the building less than or equal to the target?	BER ≤ TER
Are as built details the same as used in the BER calculations?	Separate submission

Criterion 2: The performance of the building fabric and fixed building services should achieve reasonable overall standards of energy efficiency

Values which do not achieve the standards in the Non-Domestic Building Services Compliance Guide and Part L are displayed in red.

Building fabric

Element	U _a -Limit	U _a -Calc	U _i -Calc	Surface where the maximum value occurs*
Wall**	0.35	0.25	0.25	External Wall
Floor	0.25	0.25	0.25	Ground Floor
Roof	0.25	0.19	0.19	Roof
Windows***, roof windows, and rooflights	2.2	1.7	1.7	Staff_Office Window
Personnel doors	2.2	2.05	2.2	1226 Door
Vehicle access & similar large doors	1.5	1.5	1.5	Delivery Door
High usage entrance doors	3.5	1.7	1.7	ME Door
U _a -Limit = Limiting area-weighted average U-values [W/(m ² K)] U _a -Calc = Calculated area-weighted average U-values [W/(m ² K)] U _i -Calc = Calculated maximum individual element U-values [W/(m ² K)] * There might be more than one surface where the maximum U-value occurs. ** Automatic U-value check by the tool does not apply to curtain walls whose limiting standard is similar to that for windows. *** Display windows and similar glazing are excluded from the U-value check. N.B.: Neither roof ventilators (inc. smoke vents) nor swimming pool basins are modelled or checked against the limiting standards by the tool.				

Air Permeability	Worst acceptable standard	This building
m ³ /(h.m ²) at 50 Pa	10	4

Building services

The standard values listed below are minimum values for efficiencies and maximum values for SFPs. Refer to the [Non-Domestic Building Services Compliance Guide](#) for details.

Whole building lighting automatic monitoring & targeting with alarms for out-of-range values	NO
Whole building electric power factor achieved by power factor correction	<0.9

1- Central Vent System (2 Zones)

	Heating efficiency	Cooling efficiency	Radiant efficiency	SFP [W/(l/s)]	HR efficiency
This system	0.91	6.36	-	1.92	0.83
Standard value	0.91*	2.6	N/A	1.6^	0.65
Automatic monitoring & targeting with alarms for out-of-range values for this HVAC system					YES
* Standard shown is for gas single boiler systems <=2 MW output. For single boiler systems >2 MW or multi-boiler systems, (overall) limiting efficiency is 0.86. For any individual boiler in a multi-boiler system, limiting efficiency is 0.82.					
^ Limiting SFP may be extended by the amounts specified in the Non-Domestic Building Services Compliance Guide if the system includes additional components as listed in the Guide.					

2- MVHR Only (3 Zones)

	Heating efficiency	Cooling efficiency	Radiant efficiency	SFP [W/(l/s)]	HR efficiency
This system	1	-	-	1.19	0.81
Standard value	N/A	N/A	N/A	1.5^	0.5
Automatic monitoring & targeting with alarms for out-of-range values for this HVAC system					YES
^ Limiting SFP may be extended by the amounts specified in the Non-Domestic Building Services Compliance Guide if the system includes additional components as listed in the Guide.					

3- LTHW + AC Only (3 Zones)

	Heating efficiency	Cooling efficiency	Radiant efficiency	SFP [W/(l/s)]	HR efficiency
This system	0.91	6.36	-	-	-
Standard value	0.91*	2.6	N/A	N/A	N/A
Automatic monitoring & targeting with alarms for out-of-range values for this HVAC system					YES
* Standard shown is for gas single boiler systems <=2 MW output. For single boiler systems >2 MW or multi-boiler systems, (overall) limiting efficiency is 0.86. For any individual boiler in a multi-boiler system, limiting efficiency is 0.82.					

4- Extract Only (2 Zones)

	Heating efficiency	Cooling efficiency	Radiant efficiency	SFP [W/(l/s)]	HR efficiency
This system	1	-	-	0.5	-
Standard value	N/A	N/A	N/A	N/A	N/A
Automatic monitoring & targeting with alarms for out-of-range values for this HVAC system					YES

5- MVHR + LTHW + AC (3 Zones)

	Heating efficiency	Cooling efficiency	Radiant efficiency	SFP [W/(l/s)]	HR efficiency
This system	0.91	6.36	-	1.19	0.81
Standard value	0.91*	2.6	N/A	1.5^	0.5
Automatic monitoring & targeting with alarms for out-of-range values for this HVAC system					YES
* Standard shown is for gas single boiler systems <=2 MW output. For single boiler systems >2 MW or multi-boiler systems, (overall) limiting efficiency is 0.86. For any individual boiler in a multi-boiler system, limiting efficiency is 0.82.					
^ Limiting SFP may be extended by the amounts specified in the Non-Domestic Building Services Compliance Guide if the system includes additional components as listed in the Guide.					

6- MVHR + LTHW + AC (DRS Room)

	Heating efficiency	Cooling efficiency	Radiant efficiency	SFP [W/(l/s)]	HR efficiency
This system	0.91	6.36	-	1.15	0.81
Standard value	0.91*	2.6	N/A	1.5^	0.5
Automatic monitoring & targeting with alarms for out-of-range values for this HVAC system					YES
* Standard shown is for gas single boiler systems <=2 MW output. For single boiler systems >2 MW or multi-boiler systems, (overall) limiting efficiency is 0.86. For any individual boiler in a multi-boiler system, limiting efficiency is 0.82.					
^ Limiting SFP may be extended by the amounts specified in the Non-Domestic Building Services Compliance Guide if the system includes additional components as listed in the Guide.					

1- DHW System

	Water heating efficiency	Storage loss factor [kWh/litre per day]
This building	1	0
Standard value	1	N/A

Local mechanical ventilation, exhaust, and terminal units

ID	System type in Non-domestic Building Services Compliance Guide
A	Local supply or extract ventilation units serving a single area
B	Zonal supply system where the fan is remote from the zone
C	Zonal extract system where the fan is remote from the zone
D	Zonal supply and extract ventilation units serving a single room or zone with heating and heat recovery
E	Local supply and extract ventilation system serving a single area with heating and heat recovery
F	Other local ventilation units
G	Fan-assisted terminal VAV unit
H	Fan coil units
I	Zonal extract system where the fan is remote from the zone with grease filter

Zone name	SFP [W/(l/s)]										HR efficiency	
ID of system type	A	B	C	D	E	F	G	H	I		Zone	Standard
Standard value	0.3	1.1	0.5	1.9	1.6	0.5	1.1	0.5	1			
Bakery	-	-	-	-	-	0.5	-	-	-	-	-	N/A
Customer WC	-	-	-	-	-	0.5	-	-	-	-	-	N/A

General lighting and display lighting

Zone name	Luminous efficacy [lm/W]			General lighting [W]
	Luminaire	Lamp	Display lamp	
Standard value	60	60	22	
Main Entrance	-	108	22	302
Z1 Sales Area	-	160	100	3492
Z2 Sales Area	-	160	100	3431
DRS Room	160	-	-	38
Bakery	-	125	-	311
Manager's Office	140	-	-	50
Cash Room	140	-	-	51
Clockroom	-	105	-	16
Staff WC 1	-	85	-	25
Staff WC 2	-	85	-	25
Staff Room	-	100	22	105
IT Room	140	-	-	15
Utility Room	140	-	-	10
Storage Warehouse	140	-	-	94
Delivery Warehouse	140	-	-	134
Customer WC	-	85	-	51

Criterion 3: The spaces in the building should have appropriate passive control measures to limit solar gains

Zone	Solar gain limit exceeded? (%)	Internal blinds used?
Main Entrance	NO (-23%)	NO
Z1 Sales Area	NO (-85%)	NO

Zone	Solar gain limit exceeded? (%)	Internal blinds used?
Z2 Sales Area	NO (-98%)	NO
DRS Room	N/A	N/A
Manager's Office	NO (-81%)	NO
Cash Room	N/A	N/A
Staff Room	NO (-88%)	NO
IT Room	N/A	N/A
Storage Warehouse	N/A	N/A
Delivery Warehouse	N/A	N/A

Criterion 4: The performance of the building, as built, should be consistent with the calculated BER

Separate submission

Criterion 5: The necessary provisions for enabling energy-efficient operation of the building should be in place

Separate submission

EPBD (Recast): Consideration of alternative energy systems

Were alternative energy systems considered and analysed as part of the design process?	YES
Is evidence of such assessment available as a separate submission?	YES
Are any such measures included in the proposed design?	YES

Technical Data Sheet (Actual vs. Notional Building)

Building Global Parameters

	Actual	Notional
Area [m ²]	1854	1854
External area [m ²]	5003	5003
Weather	LEE	LEE
Infiltration [m ³ /hm ² @ 50Pa]	4	6
Average conductance [W/K]	1325	1518
Average U-value [W/m ² K]	0.26	0.3
Alpha value* [%]	7.37	7.37

* Percentage of the building's average heat transfer coefficient which is due to thermal bridging

Building Use

% Area	Building Type
99	A1/A2 Retail/Financial and Professional services A3/A4/A5 Restaurants and Cafes/Drinking Est./Takeaways B1 Offices and Workshop businesses B2 to B7 General Industrial and Special Industrial Groups B8 Storage or Distribution C1 Hotels C2 Residential Institutions: Hospitals and Care Homes C2 Residential Institutions: Residential schools C2 Residential Institutions: Universities and colleges C2A Secure Residential Institutions Residential spaces D1 Non-residential Institutions: Community/Day Centre D1 Non-residential Institutions: Libraries, Museums, and Galleries D1 Non-residential Institutions: Education D1 Non-residential Institutions: Primary Health Care Building D1 Non-residential Institutions: Crown and County Courts D2 General Assembly and Leisure, Night Clubs, and Theatres Others: Passenger terminals Others: Emergency services
1	Others: Miscellaneous 24hr activities Others: Car Parks 24 hrs Others: Stand alone utility block

Energy Consumption by End Use [kWh/m²]

	Actual	Notional
Heating	24.03	19.31
Cooling	1.14	6.41
Auxiliary	6.65	3.52
Lighting	17.38	31.09
Hot water	4.13	4.54
Equipment*	20.71	20.71
TOTAL **	53.34	64.87

* Energy used by equipment does not count towards the total for consumption or calculating emissions.

** Total is net of any electrical energy displaced by CHP generators, if applicable.

Energy Production by Technology [kWh/m²]

	Actual	Notional
Photovoltaic systems	0	0
Wind turbines	0	0
CHP generators	0	0
Solar thermal systems	0	0

Energy & CO₂ Emissions Summary

	Actual	Notional
Heating + cooling demand [MJ/m ²]	106.38	147.35
Primary energy* [kWh/m ²]	119.93	151.27
Total emissions [kg/m ²]	20.5	26.4

* Primary energy is net of any electrical energy displaced by CHP generators, if applicable.

HVAC Systems Performance										
System Type	Heat dem MJ/m2	Cool dem MJ/m2	Heat con kWh/m2	Cool con kWh/m2	Aux con kWh/m2	Heat SSEFF	Cool SSEER	Heat gen SEFF	Cool gen SEER	
[ST] Central heating using air distribution, [HS] LTHW boiler, [HFT] Natural Gas, [CFT] Electricity										
	Actual	24.4	31.7	7.8	1.4	9	0.86	6.36	0.91	6.36
	Notional	27.7	115.3	9.4	8.9	4.4	0.82	3.6	----	----
[ST] No Heating or Cooling										
	Actual	32.1	0	8.9	0	5.9	1	0	1	0
	Notional	33.8	0	11.5	0	7.1	0.82	0	----	----
[ST] Central heating using water: radiators, [HS] LTHW boiler, [HFT] Natural Gas, [CFT] Electricity										
	Actual	276.8	27.8	88.9	1.2	2.7	0.86	6.36	0.91	6.36
	Notional	122.1	34.6	41.4	2.7	1.4	0.82	3.6	----	----
[ST] No Heating or Cooling										
	Actual	32.1	0	8.9	0	15.2	1	0	1	0
	Notional	33	0	11.2	0	12.1	0.82	0	----	----
[ST] Central heating using water: radiators, [HS] LTHW boiler, [HFT] Natural Gas, [CFT] Electricity										
	Actual	99.6	8.1	32	0.4	8.5	0.86	6.36	0.91	6.36
	Notional	65.9	42	22.4	3.2	6.1	0.82	3.6	----	----

Key to terms

Heat dem [MJ/m2]	= Heating energy demand
Cool dem [MJ/m2]	= Cooling energy demand
Heat con [kWh/m2]	= Heating energy consumption
Cool con [kWh/m2]	= Cooling energy consumption
Aux con [kWh/m2]	= Auxiliary energy consumption
Heat SSEFF	= Heating system seasonal efficiency (for notional building, value depends on activity glazing class)
Cool SSEER	= Cooling system seasonal energy efficiency ratio
Heat gen SSEFF	= Heating generator seasonal efficiency
Cool gen SSEER	= Cooling generator seasonal energy efficiency ratio
ST	= System type
HS	= Heat source
HFT	= Heating fuel type
CFT	= Cooling fuel type

Key Features

The Building Control Body is advised to give particular attention to items whose specifications are better than typically expected.

Building fabric

Element	U _{i-Typ}	U _{i-Min}	Surface where the minimum value occurs*
Wall	0.23	0.25	External Wall
Floor	0.2	0.25	Ground Floor
Roof	0.15	0.19	Roof
Windows, roof windows, and rooflights	1.5	1.7	Main Window
Personnel doors	1.5	1.75	1900 Door
Vehicle access & similar large doors	1.5	1.5	Delivery Door
High usage entrance doors	1.5	1.7	ME Door
U _{i-Typ} = Typical individual element U-values [W/(m²K)]			U _{i-Min} = Minimum individual element U-values [W/(m²K)]
* There might be more than one surface where the minimum U-value occurs.			

Air Permeability	Typical value	This building
m³/(h.m²) at 50 Pa	5	4