



Signature Catering Ltd

***Commercial Stainless Steel Catering Equipment Manufacturers
Specialist in Designing & Fitting out Restaurants, Bars, Fast Food Outlets
Bespoke Counter Design Service***

Economy Baffle Filter Model GFBE Stainless Steel



Technical information provided by

- Signature Catering Ltd
- JASUN ENVIROCARE PLC

GENERAL DESCRIPTION

These filters are designed for use in commercial kitchens and ventilation from food preparation areas where their primary function is to reduce flame from travelling from the cooking area up into the extract duct.

Construction

Filters are manufactured by rolling stainless steel to create a series of baffle plates which are welded onto a sub frame. The sub frame is then wrapped with the outer frame.

Features

- Strong Double frame construction • Scratch Free outer surface • Bright Polished Surface • Fold down handles • Drain Holes • Rolled Safety Edges • Ex-Stock Delivery

Frame Material

- Stainless Steel to Specification BS1449(2)
- Bright Polished Surface




Signature Catering Ltd

Commercial Stainless Steel Catering Equipment Manufacturers
Specialist in Designing & Fitting out Restaurants, Bars, Fast Food Outlets
Bespoke Counter Design Service

SIZE

Height (H) x Width (W) This is particularly important with baffle filters because the handles will always go on the H edge, the blades will always run along the H edge, and the drain holes will always be in the W edge.



Part No	Size (mm) Height x Width x Depth	Rated Airflow (m ³ /hr)
GFBE-2020	495x495x45	1323

Pressure Drop	
Velocity 1.5m/second	175Pa