



UNIT 4
 81,000 ft² WAREHOUSE
 8,000 ft² OFFICE (OVER 2 FLOORS)
TOTAL 89,000 ft² GIA

UNIT 3
 36,000 ft² WAREHOUSE
 5,500 ft² OFFICE (OVER 2 FLOORS*)
TOTAL 41,500 ft² G.I.A.
 (*APPROVAL SHOWS TOTAL OF 8,235 ft² OFFICE OVER 3 FLOORS)

UNIT 2
 61,000 ft² WAREHOUSE
 7,000 ft² OFFICE (OVER 2 FLOORS)
TOTAL 68,000 ft² G.I.A.

UNIT 1
 83,000 ft² WAREHOUSE
 6,500 ft² OFFICE (OVER 2 FLOORS*)
TOTAL 89,500 ft² G.I.A.
 (*APPROVAL SHOWS TOTAL OF 9,688 ft² OFFICE OVER 3 FLOORS)



Label	Color/Type	Units	Avg	Max	Min	Min/Avg	Min/Max
Access Road	Illuminance	Lux	16.33	46	5	0.33	0.11
ObservationLight_1_OA_Seq1	Observative Light - OA	N.A.	3097	4286	710	0.24	0.17
ObservationLight_1_OA_Seq2	Observative Light - OA	N.A.	3207	3662	2525	0.79	0.69
ObservationLight_1_OA_Seq3	Observative Light - OA	N.A.	3206	3296	2310	0.53	0.61
ObservationLight_1_OA_Seq4	Observative Light - OA	N.A.	3124	3382	2884	0.52	0.85
ObservationLight_1_OA_Seq5	Observative Light - OA	N.A.	3062	3306	2783	0.91	0.84
ObservationLight_1_OA_Seq6	Observative Light - OA	N.A.	2775	3024	2463	0.89	0.81
ObservationLight_1_I11_Seq1	Observative Light - I11	Lux	0.46	2	0	N.A.	N.A.
ObservationLight_1_I11_Seq2	Observative Light - I11	Lux	1.06	2	1	0.74	0.50
ObservationLight_1_I11_Seq3	Observative Light - I11	Lux	0.00	0	0	N.A.	N.A.
ObservationLight_1_I11_Seq4	Observative Light - I11	Lux	0.01	1	0	N.A.	N.A.
ObservationLight_1_I11_Seq5	Observative Light - I11	Lux	0.42	1	0	N.A.	N.A.
ObservationLight_1_I11_Seq6	Observative Light - I11	Lux	0.00	0	0	N.A.	N.A.
Unit 1 Car Park	Illuminance	Lux	21.78	59	6	0.28	0.10
Unit 1 Perimeter	Illuminance	Lux	21.95	58	6	0.27	0.10
Unit 1 Service Yard	Illuminance	Lux	34.50	71	14	0.41	0.20
Unit 2 Car Park	Illuminance	Lux	21.13	58	7	0.33	0.12
Unit 2 Perimeter	Illuminance	Lux	22.17	51	6	0.27	0.12
Unit 2 Service Yard	Illuminance	Lux	33.75	76	14	0.41	0.18
Unit 3 Car Park	Illuminance	Lux	24.41	56	9	0.37	0.16
Unit 3 Perimeter	Illuminance	Lux	25.61	58	7	0.27	0.12
Unit 3 Service Yard	Illuminance	Lux	32.88	78	14	0.43	0.18
Unit 4 Car Park	Illuminance	Lux	21.75	56	6	0.28	0.11
Unit 4 Perimeter	Illuminance	Lux	20.22	56	5	0.25	0.09
Unit 4 Service Yard	Illuminance	Lux	30.34	77	12	0.40	0.16

Symbol	Qty	Label	Arrangement	Description
1	3	A	SINGLE	150W CDD-TT Race 1 Road lantern (10 lamp position) column mounted at 8m
2	24	A Spill	SINGLE	150W CDD-TT Race 1 Road lantern with spill shield (10 lamp position) column mounted at 8m
3	12	B	SINGLE	100W CDD-TT Race 1 Road lantern (10 lamp position) column mounted at 6m
4	9	B Spill	SINGLE	100W CDD-TT Race 1 Road lantern with spill shield (10 lamp position) column mounted at 6m
5	3	B2	WAX-WAX	2 x 70W CDD-TT Race 1 Road lantern (10 lamp position) column mounted at 6m
6	37	CM	SINGLE	250W CDD-TT Alutera Floodlight column mounted at 8m
7	9	ES	TW20 20 DEGREE	2 x 150W CDD-TT Alutera Floodlight column mounted at 8m
8	9	EM	SINGLE	70W CDD-TT Alutera Floodlight wall mounted at 6m
9	4	P2	TW20 20 DEGREE	2 x 250W CDD-TT Alutera Floodlight column mounted at 10m
10	63	Q	SINGLE	40W PL Quarto bulkhead wall mounted at 3.5m
11	27	QB	SINGLE	40W PL Quarto emergency bulkhead wall mounted at 3.5m