
MATERIALS SCHEDULE



Window Schedule


TO FRONT ELEVATIONS & PROMINENT GABLES ONLY (Scale 1:50)



White gutters, downpipes, waste pipes and meter boxes to be used when constructing dwelling from artificial stone.
Black gutters, downpipes, waste pipes and meter boxes to be used when constructing dwelling from brickwork.

Front Entrance / Garage Doors:

Note:
All front / rear entrance doors to be painted black



All rear doors will have clear glazing.
Side & garage doors will have Cotswold Niagra Obscure glazing.

Style 2
Clear glazing to styles 2 & 3

Style 3

Style 4
Glazing to style 4 door to be Regal Screenprint Red diamonds

Rear / Side / Garage Personnel doors

KEY

Masonary

- Autumn Antique with Minster Rainworth Detail Brick
- Tudor Stone (Darlton) Rural Buff Brown with Autunm Antique detail brick


Detail Walls

- Minster Rainworth
- Tudor Stone

Roof Tiles

All roof tiles are supplied by Russell Roof Tiles Limited


- Russel Grampian Anthracite
- Russell Double Roman Cottage Red
- Ridge colour as per roof tile
- Half Render



- Roof tile specification
- Ridge tile
- Brick/stone specification

LEGEND

- 1635mm High Screen Wall
- 1800mm High Timber Screen Fence
- 1200mm High Metal Railings/Timber Picket Fence
- 900mm High Timber Boundary Fence
- Existing Tree to be Removed
- Existing Tree to Remain
- Existing Hedge to be Removed
- Existing Hedge to Remain



Materials Schedule

Plot	Elevation	Windows	Doors	Comments
1	B	1	2	
2	B	1	3	Render at first floor
3	B	1	3	Render at first floor
4	B	1	3	Render at first floor
5	B	1	3	Render at first floor
6	B	1	2	
7	B	1	2	
8	B	1	3	Render at first floor
9	B	1	3	Render at first floor
10	B	1	2	Prominent gable
11	B	2	2	Prominent gable
12	B	2	4	
13	B	2	4	
14	B	2	4	
15	B	2	4	Prominent gable
16	B	2	2	
17	B	2	4	
18	B	2	4	
19	B	2	4	
20	B	2	4	
21	B	2	2	
22	B	1	3	Prominent gable
23	B	1	2	
24	B	1	3	
25	B	2	2	
26	B	2	4	
27	B	2	4	
28	B	2	2	
29	B	2	3	Prominent gable
30	B	2	3	Prominent gable
31	B	2	2	
32	B	2	4	
33	B	2	4	
34	B	2	2	
35	B	1	3	Prominent gable
36	B	1	2	
37	B	1	3	Prominent gable
38	B	1	2	
39	B	1	3	
40	B	1	3	
41	B	1	2	Prominent gable
42	B	2	3	Prominent gable
43	B	2	3	Prominent gable
44	B	1	3	Render at first floor around full block

Barnsley Metropolitan Borough Council
19 MAR 2008
Corporate Mail Room

Rev	Details	Date	Drwn.	Chk.
B	Plots 12-15,22,24,35,37,38&41 made stone/render removed	17-03-08	SAC	
A	Handings to plots 14 & 15 amended.	Feb 2008	W.P.	

Haslam Homes Limited | Yorkshire

Cypress Road,
Kendray.

Materials Schedule

Dwg No. : HH07/007/20 B Drawn : K.Ryan
Date : November 2007 Checked : S.A.C.
Scale : 1:500 @ A2

Copyright © Haslam Homes Limited

MPSL Planning & Design Ltd Commercial House 14 West Point Enterprise Park, Clarence Avenue, Trafford Park, Manchester. M17 1QS
Tel: 0161 772 1999
Fax: 0161 772 1980
Email: admin@mpsldesign.co.uk
www.mpsigroup.com

Haslam Homes Ltd. Ten Pound Walk. Doncaster. DN4 5HX.
Tel 01302 347600. Fax 01302 347605. www.haslam-homes.co.uk
HaslamHomes