



Sports & Play Fencing Systems:

## Duo® Sports

Duo... whatever the sport

NEW - Available as 3m high single panel



Fixings every 200mm and synthetic rubber inserts at each fixing virtually eliminate rattle during play. A clamp bar covering panel ends ensures a safe playing surface with no sharp edges.



Evolved from the Duo6 and Duo8 products, Duo Sports is ideal for both light usage courts and for heavy use with Multi Use Games Areas in urban settings.

One of the major stumbling blocks during the planning of sports courts is the noise that occurs during play. Like Duo, Duo Sports is available using either 6mm or 8mm twin horizontal wires, however Duo Sports has been developed to overcome the rattle that so many residents object to. Duo Sports uses twice as many fixings to mount the panels to the posts, ensuring that there is minimum movement between the two. Furthermore, each fixing uses a synthetic rubber EPDM insert to insulate the panel from the post. Panels can be cranked inwards to increase ball retention and the addition of Zaun goal units (see page 38-39) will increase user participation.

Duo Sports conforms to BS EN 15312:2007

Duo® Sports **page 26**

For additional fixtures, fittings and options **see pages 62-63**



### Specifications

| Height Available | Mesh Pattern | Horizontal Wires      | Vertical Wires        | Post Centres | Panel               |
|------------------|--------------|-----------------------|-----------------------|--------------|---------------------|
| 0.43 - 6.13m     | 200 x 50mm   | Duo6 (6mm) Duo8 (8mm) | Duo6 (6mm) Duo8 (8mm) | 2.525m       | Fixings every 200mm |

### Detail Specifications

| Fence Height | Post Section | Panel Weight                           | Finish                                                                   |
|--------------|--------------|----------------------------------------|--------------------------------------------------------------------------|
| 0.43 - 2.25m | 60 x 40mm    |                                        |                                                                          |
| 2.43 - 3.69m | 80 x 40mm    | Duo8 Panel = 2.5 x 2m<br>Weight = 38kg | Galvanised and polyester powder coated, (See page 67 for colour options) |
| 3.89 - 4.48m | 100 x 50mm   |                                        |                                                                          |
| 4.69 - 6.13m | 120 x 60mm   |                                        |                                                                          |

### Zaun Ratings

| Appearance | Economy | Security | Vandal Proof | Strength |
|------------|---------|----------|--------------|----------|
| 6          |         |          |              |          |
| 5          |         |          |              |          |
| 4          |         |          |              |          |
| 3          |         |          |              |          |
| 2          |         |          |              |          |
| 1          |         |          |              |          |

### Applications

- ✓ Schools
- ✓ Public Multi Use Games Area
- ✓ Backspace sports courts

Ordering is easy with Zaun Fencing Systems  
Call **01902 796699** or visit [www.zaun.co.uk](http://www.zaun.co.uk)