H-3-263-757




ROAD1

| Row | Values |
|---|---|
| CHAINAGE | 0.000, 9.037, 10.000, 15.000, 20.000, 25.000, 29.037, 30.000, 40.000, 42.476, 50.000, 55.708, 57.117, 60.000, 65.988 |
| EXISTING GROUND LEVEL | 72.028, 70.921, 70.878, 70.841, 70.844, 70.793, 70.707, 70.720 |
| ALIGNMENT LEVEL | 71.982, 72.095, 72.106, 72.137, 72.120, 72.056, 71.970, 71.946, 71.696, 71.446, 71.306, 71.342, 71.272, 71.191 |
| VERTICAL ALIGNMENT | G= 1.250% 1: 80.0; L= 20.000 KF= -5.33333; G= -2.500% 1: -40.0; G=-2.500% 1: -40.0 |
| HORIZONTAL ALIGNMENT | |
| SURFACE WATER – SW DETAILS / CL | 71.500; Dia 225 Circular UPVC 1 in 14.4; 71.110 |
| SURFACE WATER – SW LENGTH / IL | 70.075; 16.419 Pipe 6.000; 68.783 |
| FOUL WATER – FW DETAILS / CL | 71.197; 71.197 |
| FOUL WATER – FW LENGTH / IL | 69.292; 69.292 |




ROAD2

| Row | Values |
|---|---|
| CHAINAGE | 0.000, 2.000, 10.000, 10.202, 15.000, 15.888, 20.000, 20.202, 25.000, 26.501, 30.000, 30.202, 30.459, 34.684, 35.000, 40.000, 44.684, 45.000, 50.000, 54.684, 60.000, 60.793, 64.008, 67.483, 68.887, 70.000, 77.617, 80.000, 90.000, 100.000, 101.201, 102.478, 110.000, 120.000, 130.000, 140.000, 150.000, 152.952 |
| EXISTING GROUND LEVEL | 71.400, 71.387, 71.327, 71.254, 71.217, 71.126, 70.954, 70.817, 70.689, 70.595, 70.736, 70.890, 70.961, 71.014, 71.044, 71.051, 71.054 |
| ALIGNMENT LEVEL | 71.383, 71.281, 71.278, 71.233, 71.216, 71.216, 71.230, 71.276, 71.278, 71.334, 71.338, 71.383, 71.397, 71.397, 71.379, 71.334, 71.268, 71.177, 71.229, 71.218, 71.093, 70.968, 70.843, 70.825, 70.740, 70.842, 70.984, 71.126, 71.268, 71.410, 71.413 |
| VERTICAL ALIGNMENT | G= -1.250% 1: -80.0; KF= 8.0 L= 20.000; G=1.250% 1:80.0; L= 20.000 KF= -8.0; G= -1.250% 1: -80.0; G= -1.250% 1: -80.0; G= 1.419% 1: 70.5 |
| HORIZONTAL ALIGNMENT | R= 84.750; R= 152.750 |
| SURFACE WATER – SW DETAILS / CL | 71.208; Dia 375 Circular UPVC 1 in 133.4; 71.110; 70.831; Dia 300 Circular UPVC 1 in 126.3; 71.433 |
| SURFACE WATER – SW LENGTH / IL | 69.158; 50.034 Pipe 7.001; 68.783; 69.000; 39.399 Pipe 2.000; 68.688 |
| FOUL WATER – FW DETAILS / CL | 71.279; Dia 150 Circular UPVC 1 in 80; 71.197; Dia 150 Circular UPVC 1 in 80; 70.870; 71.503 |
| FOUL WATER – FW LENGTH / IL | 69.823; 42.520 Pipe 4.001; 69.292; 25.529 Pipe 4.002; 68.973 |




ROAD4

| Row | Values |
|---|---|
| CHAINAGE | 0.000, 2.750, 8.810, 10.000, 10.700, 20.000, 23.152, 30.000, 32.326, 40.000, 50.000, 51.530 |
| EXISTING GROUND LEVEL | 71.486, 71.585, 71.736, 71.861, 71.900, 71.831, 71.813 |
| ALIGNMENT LEVEL | 71.593, 71.672, 71.743, 71.789, 71.904, 72.029, 72.154, 72.279, 72.298 |
| VERTICAL ALIGNMENT | G= 1.250% 1: 80.0; G= 1.250% 1: 80.0 |
| HORIZONTAL ALIGNMENT | R= 77.750 |
| SURFACE WATER – SW DETAILS / CL | 71.479; Dia 300 Circular UPVC 1 in 72; 71.680 |
| SURFACE WATER – SW LENGTH / IL | 68.956; 60.498 Pipe 8.001; 68.102 |
| FOUL WATER – FW DETAILS / CL | 71.536; Dia 150 Circular UPVC 1 in 80; 72.209 |
| FOUL WATER – FW LENGTH / IL | 69.500; 45.713 Pipe 5.001; 68.930 |




ROAD5A

| Row | Values |
|---|---|
| CHAINAGE | 0.000, 2.751, 10.000, 11.649 |
| EXISTING GROUND LEVEL | 71.020, 71.109, 71.109 |
| ALIGNMENT LEVEL | 71.877, 71.968, 72.013 |
| VERTICAL ALIGNMENT | G= 1.250% 1: 80.0 |
| HORIZONTAL ALIGNMENT | |




ROAD6

| Row | Values |
|---|---|
| CHAINAGE | 0.000, 2.750, 10.000, 18.476, 20.000, 20.974, 25.000, 25.503, 30.000, 35.000, 38.476, 40.000, 50.000, 53.744 |
| EXISTING GROUND LEVEL | 70.521, 70.466, 70.488, 70.626, 70.771, 71.039, 71.113 |
| ALIGNMENT LEVEL | 71.259, 71.169, 71.063, 71.046, 71.019, 71.019, 71.037, 71.099, 71.168, 71.204, 71.434, 71.500 |
| VERTICAL ALIGNMENT | G= -1.250% 1: -80.0; KF= 5.62208 L= 20.000; G= 2.307% 1: 43.3 |
| HORIZONTAL ALIGNMENT | R= 78.500 |
| SURFACE WATER – SW DETAILS / CL | 71.316; Dia 450 Circular CONC 1 in 185.7; 70.988; Dia 450 Circular CONC 1 in 185.9; 71.270 |
| SURFACE WATER – SW LENGTH / IL | 68.273; 24.704 Pipe 1.003; 68.140; 20.080 Pipe 1.004; 68.032 |
| FOUL WATER – FW DETAILS / CL | 71.332; Dia 150 Circular UPVC 1 in 80; 71.056; Dia 150 Circular UPVC 1 in 80; 71.600; 71.600; Dia 150 Circular UPVC 1 in 80 |
| FOUL WATER – FW LENGTH / IL | 68.230; 31.758 Pipe 1.003; 67.830; 25.217 Pipe 1.004; 67.510; 67.470; 2.607 Pipe 1.005 |

# N O T E S

Yorkshire Water General Notes

1. All adoptable sewer works and material to be in accordance with "Sewers for Adoption" 6th Edition, the relevant British/European and Yorkshire Water's Standards/Requirements/Addendum to the Mechanical and Electrical Specification and Kitemarked.
2. Manhole covers shall/must have a clear opening of 600mm and shall be Class D400 to BS EN 124 with 150mm deep frames in highways.
3. Filled ground must be filled and consolidated under the supervision, and to the satisfaction, of Yorkshire Water before any sewer works are carried out.
4. Cover slabs must carry the BSI Kitemark or will be rejected by the Yorkshire Water inspector. Where the clear opening of the Kitemarked product is different to that of the cover and frame, a loading bearing slab should be fitted above the cover slab to bring the size down to 600x600mm for the Yorkshire Water specified cover size. Please refer to the Concrete Pipe Systems Association (CPSA), 'Technical Bulletin' issued autumn 2004 for kitemarked cover slab opening sizes.
5. The adoptable sewers should be a minimum of 1m and manholes 0.5m from kerb faces and service margins.
6. Sewers must have 5 metres clearance from trees and hedges, (please also refer to Figure 2.3 on page 33 in "Sewers for Adoption" 6th Edition for restrictions on tree planting adjacent to Sewers).
7. Sewers to be laid in Class "S" bedding (150mm granular bed and surround). Where depth of cover to top of the sewer is less than 1.2m in highways and verges (or less than 900mm in none vehicular access areas) then a concrete slab should be provided above the granular bed and surround.
8. Adoptable plastic sewer pipes to be BSI Kitemarked (Certified to WIS 4-35-01 and BS/EN13476). Adoptable sewer pipes to be laid in maximum 3 metre lengths unless there is a specific operational need to lay longer.
9. Plastic channel sections in manholes are not acceptable and clayware is preferable. Plastic channels are difficult to set in concrete and a satisfactory finish cannot be obtained on the benching.
10. The chamber size of manholes with more than one connection in them may need to be increased an increment to accommodate the connections and bends.
11. Yorkshire Water policy is not to accept Type "C" brick manhole and 1050mm dia manhole rings. Instead it is preferred that you use a type "B" manhole with 1200mm dia or 1500mm dia. rings, with the opening sited over the channel where depth of cover to pipe soffit is 1-1.5m.
12. Surface water and foul rising mains to be provided with marker tape above the rising mains.
13. If plastic pipes are to be used then the following should apply:-
    a. All adoptable sewers to be BSI Kitemark (certified to WIS 4-35-01).
    b. Bedding and backfill material to conform to the requirements of Water industry Specification 4-08-02 (Table A2)
14. Where plastic pipes are proposed for adoptable sewers, structural calculations for the plastic pipes and a site investigation report to prove that the ground condition is suitable for the plastic pipes to be produced.
15. Where plastic pipes are installed into the ground prior to getting full technical approval, the developer must provide a CCTV survey of the prospectively adoptable sewers and a deformation test (Light-Line test) of the plastic pipes.
16. Demarcation chambers to be a min. 450mmø chamber for 100mmø foul & 150mmø surface water pipes up to 1.2m deep. For depths greater than 1.2m, restricted access opening to 350mm is required for safety reasons.
17. Maximum depth of demarcation chamber to be 2m, where depth exceeds 2m, manhole to be constructed as type B manhole.
18. Yorkshire Water is not obliged to accept filter drain/land drainage runoff into the public sewer network or adoptable drainage system (directly or in-directly). An alternative method of disposal of the land drainage runoff will therefore be required and you will have to liaise with the Land Drainage Authority/Land Drainage Section with regard to the disposal of the filter drain/land drainage runoff is required.
19. Sulphate resisting cement (C20-DC2) and precast concrete products must be used or a laboratory report provided proving that such precautions are not necessary.
20. Strength of vitrified clay pipes (if used) to be 40KN/m for 100ø, 40KN/m for 150ø, 45KN/m for 225ø and 72KN/m for 300ø. All concrete pipes to be Class 120 concrete to EN 1916/BS 5911-1:2002.
21. All levels of existing drainage to be confirmed prior to work commencing on site.
22. The contractor must allow for any fee's required for road and sewer opening permits, sewer connections and make the appropriate applications.

SUBJECT TO THE APPROVAL OF ALL RELEVANT AUTHORITIES

| Rev | By | Date | Revision | Chk |
|---|---|---|---|---|
| D | JMG | 29.11.17 | Additional Information added | ANB |
| C | JMG | 28.11.17 | Updated to suit YW comments | ANB |
| B | ANB | 31.08.17 | Gradients Amended | |
| A | ANB | 18.08.17 | Sections updated following new layout Rev D | |
| / | JMG | 16.03.17 | Issued for approval | MI |


ARP ASSOCIATES
CHARTERED CONSULTING ENGINEERS
Northwest House • 5/6 Northwest Business Park • Servia Hill • Leeds LS6 2QH
Telephone: 0113 2458498 • Fax: 0113 2443864 • E-Mail: leeds@arpassociates.co.uk
ARP Associates is a trading division of ARP Geotechnical Ltd, a company registered in England and Wales with company number 3771811, whose registered office is at 5/6 Northwest Business Park, Servia Hill, Leeds LS6 2QH


TITLE
LONGITUDINAL SECTIONS
SHEET 1 OF 4

PROJECT
LEE LANE, ROYSTON

CLIENT
BDW YORKSHIRE WEST

| Scale | Date | Drawn | Chk. |
|---|---|---|---|
| 1:500H 1:100V @ A1 | MAR 17 | JMG | MI |

Drg. No. 1048/88/06.01 Rev D