



NANNY MARR ROAD

A1



KEY

Proposed Level.

Flag on edge retaining.

Masonry Retaining Wall. To be Highway Authority approved when within 3.6m of adoptable Highway.

5

Facing Brickwork courses below DPC

1/106
gradient

Root protection zone

Fall protection required where levels differ by more than 600mm

RISK ASSESSMENT	SUGGESTED ACTION
DEEP EXCAVATIONS ASSOCIATED WITH DEEP DRAINAGE WORKS	ENSURE ALL EXCAVATIONS HAVE ADEQUATE TRENDON SUPPORTS AND ARE PROTECTED BY A PROTECTIVE FENCE.
WORKING UNDER OVERHEAD POWER LINES AND ADJACENT TO HIGH VOLTAGE CABLES	USE CORRECT LIFTING EQUIPMENT AND ENSURE OPERATOR'S WEIGHT IS NOT PLACED ON THE CABLES.
CONTACT WITH SERVICES/WORKING IN CONFINED SPACES	USE GAS DETECTORS/VENTILATING EQUIPMENT AND ENSURE OPERATOR'S WEIGHT IS NOT PLACED ON THE CABLES.
NOISE FROM MACHINERY	OPERATOR'S TO WEAR THE CORRECT EAR PROTECTION.
EXCAVATIONS NEAR TO UTILITIES	UTILITY LINES TO BE IDENTIFIED AND PROTECTED. COATED CABLES AND ARE FENCED OFF TO PROTECT FROM FALLS.
EXCAVATIONS IN PUBLIC HIGHWAY	ENSURE THE CORRECT ROADWORK TO BE COMPLETED.

Preliminary

Partner Construction

Foulstone School Phase 2
Darfield, Barnsley

External Works
Sheet 1

Dwg No. : STE/19/03/03/01 G
Date : 25-1-19
Scale : 1:200

SHAUN TONGE
ENGINEERING

11 Bromfield Road, Wombwell, Barnsley, S73 3SA.
Tel: 01282 755929, Mobile 077528 278070, Email Shaun@shauntonge.co.uk