



NEW ALUMINIUM ENTRANCE FRAME WITH
AUTOMATIC BI-PARTING DOORS TO ICELAND SPEC.

WAREHOUSE NOTES

ALL SERVICE PENETRATIONS IN EXTERNAL WALLS TO BE MASTIC SEALED TO LIMIT AIR INFILTRATION.

VENTILATION RATES
 Staff Areas - 6 Air changes per hour
 Toilets/Cloaks - 10 Air changes per hour
 Cash/Admin - 6 Air changes per hour
 Goods Area - 1 Air change per hour

DRAINAGE FROM SINK IN STAFFROOM, SINK IN CLEANERS ROOM, HANDBASINS IN TOILETS, TO BE CONNECTED INTO 50mm WASTE PIPES WITH 76mm DEEP SEAL ANTI-SYPHONAGE TRAPS, 100mm WASTE FROM WC's. ALL CONNECTED INTO DRAINAGE SYSTEM.

NEW DOORS TO HAVE A OPENING STRENGTH OF 20N MAX.

SHARED REFRESHMENT FACILITY TO STAFFROOM & KITCHENETTE TO COMPLY TO PART M (DIAGRAM 16).

ALL SIGNAGE TO FIRE-EXIT DOORS TO B.S.5499 PART 1.

A FULLY AUTOMATIC FIRE DETECTION SYSTEM TO BE INSTALLED THROUGHOUT THE UNIT TO B.S.5839 PART 1, 2004 TYPE L1.

COLDROOM DOOR IS CAPABLE OF BEING OPEN FROM THE INSIDE BY MEANS OF A PUSH LEVER MECHANISM AND TO BE MARKED BOTH SIDES WITH A DIRECTIONAL ARROW AND WORDS 'SLIDE DOOR TO OPEN'.

IN THE EVENT OF THE FIRE ALARM BEING ACTIVATED OR/AND A POWER FAILURE THE AIR
CONDITIONING SYSTEM WILL SHUT DOWN AND THE BI-PARTING ENTRANCE DOORS WILL
AUTOMATICALLY OPEN.

PROPOSED WALL AND CEILING LININGS ARE TO CLASS 1 AND CLASS 0 RESPECTIVELY.

FIRE EXTINGUISHERS TO BE INSTALLED TO B.S.EN3:1996, B.S.7863:1996 & B.S.5306 PART 4 1986.

EMERGENCY LIGHTING TO B.S.5266-1:2005 & B.S.5266-8:2004.

NEW CUSTOMER ENTRANCE/EXIT DOORS TO BE INSTALLED TO BS 7036.
CONFIGURATION OF DOORS TO BE INSTALLED ENSURING THAT POCKET SCREENS WILL NOT BE
REQUIRED.

ANY DEVIATIONS FROM LAYOUT AFTER SITE SURVEY TO BE APPROVED WITH PROJECT MANAGER PRIOR TO MANUFACTURE.


ANY INSTALLATIONS WHERE POCKET SCREENS ARE A NECESSITY ALSO TO BE DISCUSSED WITH P.M. PRIOR TO MANUFACTURE.

ESCAPE LIGHTING TO BE PROVIDED THROUGHOUT STORE INCLUDING WINDOWLESS ACCOMMODATION TO B.S.5266-1:1999

PARTITION WALLS TO BE CONSTRUCTED FROM 75mm GYPROC METAL STUDDING
COMPLETE WITH 1-LAYER OF 12.5mm WALLBOARD SKIMMED TO BOTH SIDES(half hour)

DOORS

1/2 HOUR SELF CLOSING INTERNAL FIRE DOORS 840mm WIDE
FITTED WITH SMOKE SEALS & INTUMESCENT STRIPS.
VISION PANELS NOTED AS = V.P.
FIRE SAFETY SIGNS TO BS499 Part 9



FOOD WAREHOUSE

