This drawing is the copyright and property of NatWest Group plc.
It must not be copied or published without written consent.
Only scale from this drawing for planning consent purposes.

Architecture

Lewis & Hickey Ltd
1 St. Bernard's Row
Edinburgh, EH4 1HW
0131 343 6222
edinburgh@lewishickey.com

Edinburgh | Guildford | London | Manchester | Nottingham

EXTERNAL	
PROPOSED SCOPE	Deep clean shop front and make good (gutter clearing and graffiti removal etc. as required). Repair all aspects as required. Remove window posters. Remove all weeds. Remove all slip bins and make good. Maintain lighting and repair and re-lamp with LED / Energy Saving.
SPECIALIST SIGNAGE CONTRACTOR	Specialist signage contractor to check all heights and sizes on site and all statutory consents are in place prior to manufacturer of proposed signage shown.
FASCIA PANEL	REPLACE FASCIA SIGN WITH NEW BUTTON LOGO SIGN
PROJECTING SIGN	REPLACE PROJECTING SIGN WITH NEW
ATM SURROUND	BESPOKE: REPLACE ATM SURROUND WITH NEW BUTTON LOGO
ATM ADVERT PANEL	REPLACE TO NEW STANDARDS
MANIFESTATIONS	INSTALL NEW "ENTRANCE HEADER VINYL" AS SHOWN INSTALL NEW "HALF TONE" GRAPHIC AS SHOWN

SIGNAGE CONTRACTOR TO CONFIRM
MAXIMUM HEIGHT OF NEW FASCIA SIGNAGE.

SIGNAGE CONTRACTOR TO CONFIRM
BESPOKE SIZE OF NEW ATM SURROUNDS.

0 0.5 1 1.5 2 2.5m 5m

rev	date	description	drawn	checked
A	04/08/22	UPDATED TO CONTRACTORS PROPOSAL	MD	04/08/22

NatWest Group

address
NATWEST BARNSLEY
26 MARKET HILL, BARNSLEY
SOUTH YORKSHIRE,
S70 2QE

ref no. -
sortcode 516135

description
ELEVATION 1
AS PROPOSED
SPOKE REFRESH

status
CONTRACTOR'S PROPOSAL

IPMS1 - sqm -
IPMS2 - sqm -
IPMS3 - sqm -

scale 1:100
paper size A3
brand
drn KL date 11/07/22
chk -- date --/--/--

nw drawing number E7153-GA-E1
rev. A