

Laurel Hedge Length 52m; Planted at 0.4m centres					
Name	Height cm	Root Zone	Specification	Mix %	Number
Prunus Iusitanica	60-80	В	1+2; Transplant - seed raised; branched; 3 brks	100	130
Lengthm:No.ofrows:Offsetm	1		Sub-totals	100%	130

Abbrev.	Name	Height cm	Root Zone	Specification	No.	
Bp Betula pendula		300-350	35-45L	Selected Standard; clear stem 175-	2	
	Dotata portuata		00.02	200cm; 4 breaks	_	
Mg 'G'	Magnolia grandiflora 'Gallisoniensis'	250-300	45-85L	Selected Standard; clear stem 150-	1	
ivig G			43-83L	175cm; 4 breaks		
Qi	Quercus ilex	300-350	35-45L	Selected Standard; clear stem 175-	1	
		300-330	33-43L	200cm; 4 breaks	I	

Mix A	Area: 25m²			
Name	Height cm	Root Zone	Specification	Mix %
Achemilla mollis		2L	Full pot	10
Berberis thunbergii 'Rose Glow'	30-40	2L	Branched; 3 brks	15
Choisya ternata 'Sundance'	20-30	2L	Bushy; 3 brks	15
Cornus stolonifera 'Flaviramea'	40-60	2L	Branched; 3 brks	15
Euphorbia amygdaloides robbiae		2L	Full pot	15
Hypericum 'Hidcote'	20-30	2L	Bushy; 3 brks	15
Symphoricarpos x chenaultii 'Hancock'	40-60	2L	Branched; 3 brks	15
	•	•	Sub-totals	100%

Mix B Area: 21m²

Name	Height cm	Root Zone	Specification	Mix %	No./m²	Number
Achemilla mollis		2L	Full pot	10	3	6
Berberis wilsoniae	30-40	3L	Bushy; 4 brks	15	3	9
Choisya ternata 'Sundance'	20-30	2L	Bushy; 3 brks	15	4	13
Cornus sanguinea 'Midwinter Fire'	40-60	2L	Branched; 3 brks	15	4	13
Euphorbia amygdaloides robbiae		2L	Full pot	15	5	16
Hypericum 'Hidcote'	20-30	2L	Bushy; 3 brks	15	3	9
Prunus laurocerasus 'Otto Luyken'	20-30	2L	Bushy; 3 brks	15	3	9
	•		Sub-totals	100%		


Scale 1:500 0 5 10 15 20 25 [m]

Tarmac road. Non-permeable with suitable drainage to engineers details. Ensuring no

Permeable Resin Bound Gravel, 6mm.

Marshalls Priora Permeable 200 x 100 x 80 Buff Block Paving or similar approved





OUTLINE SPECIFICATION:

GENERAL All works to be in accordance all relevant British Standards and the Landscape Consultant's planting plans and specification (to be issued) and in compliance with the National Landscape Specification (NBS) 1998, latest revision.

SETTING OUT

All dimensions and levels should be checked and adjusted on site. Contractor responsible for care around all services. Do not scale from this drawing.

SITE PREPARATION

SITE PREPARATION Building rubble in excess of 50mm dimension to be removed, compaction ripped 150mm deep or broken out by JCB back-actor leaving surface rough. Ensure free drainage.

TOPSOIL

Multipurpose topsoil BS:3882 medium loam, not more than slightly stoney, pH 5.7-7.5.

Depth 450mm all planting areas. 150mm to all other areas. Provide Declaration of Analysis of topsoil to Employer's Agent.

TREE PIT

75 mm deeper than root system and wide enough to accommodate roots when fully spread OR

Transplants 300mmØ x 300mm denth

Select Standard 1200mmØ x 750mm depth

PREPARATORY HERBICIDE Weed allowed to grow and treated with up to three applications of weed killer prior to cultivation or planting during the fallow period.

GRASSING Grassing between April-October. Cultivate to prepare seed bed. Finished seed bed levels 25mm above pavings and kerb edges. Stones pick to 25mm. Pre-seeding fettiliser 50g/m2. Grass mix chosen for low maintenance

requirements:-GRASS SEED MIX from DLF Trifolium Tel: 01386 791102: LOW MAINTENANCE: 'Pro85 DOT Road verge mix Eng&WIs'

PLANTS

General Plant material in accordance with the HTA's National Plant Specification 1997. All plants container grown, well formed and free from disease. Plant handling to CPSE Plant Handling Code.

Quality as supplied by: Johnsons of Whixley Ltd, York YO26 8AQ. Tel: 01423 330234. Or other nursery listed in the Horticultural Trades Association Nursery Certification Scheme.

Planting Plant November to March. Planting areas cultivated 150 mm deep and stone picked of material greater than 50mm. Plant material pit planted 300 x 300 x 200 minimum. Approved planting compost incorporated into the soil during planting.

Backfill mix	Enmag	P4	Compost
Shrubs	35g	5g	10 litres
Transplants	35g	5g	10 litres
Select Standard	75g	50g	75 litres

Backfill mix (30%) incorpo	rated into top	psoil (70	%) during planti	ng.

TREE STAKING Select Standard -Short Double Staking Preserved softwood 100mm min diameter. Driven vertically 450mm into base of pit on either side. Cross bar - timber, as stake.Secured with rubber J Tom's 37.5mm wide standard nylon reinforced rubberbelt ref L2 ties including rubber spacer pads ref L1.

MULCH

Total cover coarse bark mulch to shrub areas, Melcourt Bark Nuggets 75mm deep.

AFTERCARE

AP I EXCARC 24 months aftercare by planting contractor. Including grass and meadow cutting, weed, pest and disease control, pruning and watering. Weed control by residual herbicide or hand weeding as necessary to achieve a weed free contilion. Watering in periods of drough to ensure establishment and continued thriving of planting.

DEFECTS LIABILITY Twenty-four months on plant material and grass. Replacements in November in year of loss.

ONGOING MAINTENANCE Continue to maintain for five years from completion of planting by hand weeding and spot treatment of weed killer to any weed in planted areas until plants close canopies. Replace failures for 5 years.

Based on Eight_OneTwo Architects drawing 21_810 102, dated Dec 2022

REVISION:

A. Updates to plan, key, and schedule. NS 27-01-2023 B. Revised to client comments. CB 07-02-2023 C. Amended side access path. CB 08-02-2023

D. Amended tarmac spec and side access. CB 10-02-2023

Weddle Landscape Design					
LANDSCAPE ARU ENVIRONMENTAL Mews Studio, Charnwood House, 8 Kenwood Bank, Sheffield S7 1NU www.wedles.co.uk	CHITECTURE PLANNING Tel (0114) 250 1181 Fax (0114) 250 1188 mail@weddles.co.uk				
Job BARNSLEY ROAD, BRIERLEY					
Title LANDSCAPE MAST	ERPLAN				

ob number 1016

D D

BRB 04

scale@A3 drawn date 1:500 EH JAN 23