BHT Landscapes
17 Manor Road
Harlington
Doncaster
DN5 7JD
Tel 01709 898572
Mob 07884391904

Site location
Fontenay Barracks
Wakefield Road
Barnsley
S71 1NU

The Row of 40 Manchester Poplars (Poulus Nigra var betulifolia) is covered by a tree preservation order TPO No GRP1/36/1974

The works proposed will improve the long term health and appearance of the trees will remove nuisance branches from the trees reduce overhanging branches from adjacent buildings and footpaths and increase safety

The removal of two small poorly formed trees will not affect the overall visual amenity of the avenue of trees It is normal practice when removing trees covered by a TPO to provide replacement planting to mitigate for the loss In this instance I am proposing that no replacement trees are required in the avenue their removal will not be noticed

All works to be carried out to comply with BS 3998 Tree work Recommendations 2010

T1	Removal of two large horizontal limbs to NW and SW side of tree The limbs are at 2 metres and 3 5 metres high Removal of dead wood from crown
T2	Removal of one limb to the SW side of the tree @ 2 metres height The horizontal limb is resting on the fence line Reduce length of branch to the SE aspect that overhangs the building by 50% in length Removal of dead wood from crown
T3	Light crown lift of minor branches to trunk and removal of one limb to NE aspect at a height of 1metre Removal of dead wood from crown
T4	Light crown lift of minor branches to the trunk and reduction by 50% in length to limb to NE aspect of the tree that overhangs the adjacent building
T5	Light crown lift of minor branches to the main trunk and removal of horizontal limb to SW aspect at a height of 2 metres
T6	Light crown lift of minor branches to main trunk and removal of one limb to the SW aspect of the tree at 2 metres
T7	Light crown lift of minor branches to main trunk to a height of 3 metres and removal of dead wood
T8	Light crown lift of minor branches to main trunk and removal of limb at 2 metres height to NE aspect that overhangs car park
T9	Light crown lift to main trunk and removal of dead wood

T10	This is a very small misshaped tree that has been severely stunted by the adjacent trees There is a large amount of dead wood The tree has a very low amenity value It is recommended that this tree is removed
T11	Remove of 1 horizontal limb to NW aspect at a height of 3 metres Removal of dead wood
T12	Removal of one horizontal limb to the SW aspect of the tree at a height of 3 metres And removal of minor branches to main trunk to a height of 3 metres
T13	Light crown lift of minor branches to main trunk and removal of dead wood
T14	Light crown lift of minor branches to main trunk and removal of dead wood Reduce by 50% in length two limbs that overhang the car park to NE and SE aspect
T15	Light crown lift of minor branches to main trunk and removal of dead wood
T16	Light crown lift of minor branches to main trunk and removal of dead wood Removal of lowest limb to NE aspect that overhangs the car park
T17	Removal of dead wood
T18	Light crown lift of minor branches to main trunk and removal of dead wood
T19	Light crown lift of minor branches to main trunk and removal of dead wood Removal of lowest limb to NE aspect that overhangs the car park
T20	Light crown lift of minor branches to main trunk and removal of dead wood
T21	Light crown lift of minor branches to main trunk and removal of dead wood The tree forks at a height of 6 metres Removal of limb to Eastern aspect of tree at 6 metres
T22	Light crown lift of minor branches to main trunk and removal of dead wood
T23	Reduce by 50% limb to SE aspect of tree at a height of 7 metres that overhangs the car park Light crown lift of minor branches to main trunk and removal of dead wood
T24	This small tree has been overshadowed by adjacent trees and is 75% dead Removal of tree recommended
T25	This small tree has been overshadowed by adjacent trees and is 50% dead The tree has fallen and leans to the east over the car park
T26	Light crown lift and removal of branch previously poorly pruned to base of tree
T27	Removal of two horizontal limbs to NW and SW aspect of tree at 2 metres Light crown lift of minor branches to main trunk and removal of dead wood
T28	Removal of one limb to Western aspect of tree at 6 metres height
T29	Removal of horizontal limb to NW aspect of tree at 5 metres Removal of dead wood and light crown lift of minor branches to trunk
T30	No works required
T31	Light crown lift of minor branches to main trunk and removal of dead wood
T32	Light crown lift of minor branches to main trunk and removal of dead wood
T33	Light crown lift of minor branches to main trunk and removal of dead wood
T34	Light crown lift of minor branches to main trunk and removal of dead wood
T35	Reduce by 50% length of two limbs to Southern aspect of tree at 6 metres and 8 metres where they overhang the adjacent public footpath Light crown lift of minor branches to main trunk and removal of dead wood
T36	Reduce two limbs to Southern aspect by 50% one at 5 metres and one at 6 metres height where they overhang the public footpath and adjacent houses
T37	Remove one limb to the Southern aspect at 3 metres height and reduce by 50% limbs overhanging the footpath and adjacent properties Light crown lift of minor branches to main trunk and removal of dead wood
T38	Remove one limb to Southern aspect of tree at 3 5 metres height where it overhangs footpath and adjacent properties

T39	Remove two horizontal limbs to the Southern aspect of the tree and reduce by 50% one limb that overhangs the car park to the northern aspect of the tree
T40	Reduce by 50% horizontal limb to Southern aspect of tree where it overhangs footpath and adjacent properties

