

## APPENDIX 1 - TREE SCHEDULE

Key: Greens - Locational and ID Data Pinks - QTRA Decision Factors and Survey Notes

Navy - Recommendations - for: Surveyor Contractor

Ref.	What 3 Words	Species	Description	Measurements	Physio' Condition	Structural Condition	Amenity Value	Highest Residual Risk	Target Range	Size	PoF	RoH	Recommendations
G021	/// shopping.conjured.lion	Mixed species (Mixed species)	Broad woodland group, assigned for broad risk assessment. Targets - seating area and neighbouring gardens(s), garages (e), and power lines (ne), neighbouring gardens (w)  Highest point of occupancy - seating	Life Stage: Mature			Good	Falling deadwood	Occupation(2) 2.4 hours/day - 15 min/day	Size(3) 250mm - 110mm dia.	PoF(3) 1/100 - 1/1K	1/50K	
T152	/// glitter.guru.ballpoint	English elm (Ulmus procera)	Outside of pub seating area. DED symptoms.	Height (m): 18 Crown Radius (m): 4 DBH (cm): 25 Stems: 4 Life Stage: Semi Mature Life Exp.: <10 years	Poor	Fair		Stem/limb decay.	Occupation(3) 14 min/day - 2 min/day	Size(3) 250mm - 110mm dia.	PoF(2) 1/10 - 1/100	1/50K	
T154	/// stability.directs.watchdogs	English elm (Ulmus procera)	Outside of pub seating area. Standing dead. Slight lean away from targets.	Height (m): 18 Crown Radius (m): 4 DBH (cm): 25 Stems: 4 Life Stage: Dead	Poor	Fair		Stem/limb decay.	Occupation(2) 2.4 hours/day - 15 min/day	Size(3) 250mm - 110mm dia.	PoF(2) 1/10 - 1/100	1/5K	Fell tree. Timescale: 28-Apr-2027 (1 Year)
T155	/// begin.grunt.crabmeat	Common ash (Fraxinus excelsior)	Ivy clad. Slight wound at base revealed by spilt in bark. Lean towards targets to SE. No lower canopy. Slightly sparse crown. Two recent lower limb failures leaving tear out stubs.	Height (m): 23 Crown Radius (m): 2.5 DBH (cm): 45 Life Stage: Mature Life Exp.: 10+ Years	Fair	Fair		Stem failure.	Property(2) £200,000 - £20,000	Property	PoF(3) 1/100 - 1/1K	1/3K	Fell tree. Timescale: 28-Apr-2027 (1 Year)
T156	/// bandage.d.heartened.recording	Common ash (Fraxinus excelsior)	To side of mowed path in wild garlic woodland floor. Holly growing under. Trained with Elm. Light ivy on main stem. Thin woodland form with slight lean SE. Weakening canopy with light epicormic reactionary growth.	Height (m): 23 Crown Radius (m): 2 DBH (cm): 25 Life Stage: Early Mature Life Exp.: <10 years	Fair	Fair		Fragile branches	Occupation(3) 14 min/day - 2 min/day	Size(3) 250mm - 110mm dia.	PoF(2) 1/10 - 1/100	1/50K	
T157	/// tailing.himself.telise	Common ash (Fraxinus excelsior)	To rear of garages. Waste piled at base. Broad form. No lower canopy. Slight weakening of crown. Lower branch over garage has historic tear-out wound at midway point subject to decay.	Height (m): 25 Crown Radius (m): 6 DBH (cm): 60 Life Stage: Mature Life Exp.: 10+ Years	Fair	Fair		Lower branch failure at wound	Property(3) £20,000 - £2,000	Property	PoF(3) 1/100 - 1/1K	1/30K	

## APPENDIX 2 - MAPS

### A 2.1 - MAP 1 - TREE LOCATION PLAN



