


















KEY

-  Existing tree to be removed
-  Existing vegetation to be retained. Refer to arboricultural report by Brooks Ecological
-  Proposed semi-mature (20-25cm girth) trees
-  Proposed contemporary ornamental shrub and herbaceous planting
-  Proposed Marshalls Perfecta paving, laid stretcher bond, 450 x 450mm in colour: Natural
-  Proposed Marshalls Perfecta paving, laid stretcher bond, 450 x 450mm in colour: Buff
-  Proposed Marshalls Tegula concrete sett paving, laid stretcher bond to 'pathway' through square, in colour: Pennant Grey
-  Proposed Marshalls Tegula concrete sett paving, 240 x 160mm in colour: Charcoal
-  Proposed Marshalls Tegula kerb edge to planting beds, 130 x 160mm in colour: Pennant grey
-  Proposed mosaic panel set into paving to link to site heritage and demolished pub
-  Proposed 450mm height raised planting bed formed from concrete blocks and rendered with areas for informal seating along edge
-  Proposed area for 3 x 3m covered temporary market stall.
-  Proposed electricity points for temporary market stalls.
-  Proposed uplighting positioned within soft landscape areas
-  Proposed bench seating
-  Proposed litter bins. 2nr MLB112 steel bin in black with no artwork, beading or banding from www.wybone.co.uk
-  Proposed engineered tree pit consisting of soil cells, irrigation pipe and underground rootball guying system from www.greenblue.com and Sunburst square tree grille, 1200 x 1200mm from www.broxap.com (Refer to standard detail)

NOTES

CONCEPT

This proposed Public Square is on the site of the old Horse and Groom pub site in the Heart of Goldthorpe and has been drawn up following initial Community Consultation regarding the development. The design has been developed to create a multifunctional space that would be attractive all year round and provide a central hub and meeting place for a range of activities.

The new paving scheme incorporates a series of concentric circles radiating out from a point which represents the location of the old pub. At the centre of the circle, a mosaic artwork will be incorporated within the paving as a celebration of the heritage of the site and to create a feature that feels relevant to the new space. This area will also contain a number of solar powered 'Smart benches' with capacity for phone charging and there are areas indicated for pieces of incidental play equipment.

A large open area provides room to accommodate 24 temporary covered market stalls for both regular and festive trading capacity. Vehicular access will be provided to this section of the site as well as covered anchor and electricity points. This large open area will also allow for a range of other community events during times when the market is not in operation.

The soft landscape scheme within the new square utilises curved forms to really soften the space and encourage pockets of more intimate seating zones. A low raised planting bed to the front of the space provides informal seating and the curved 'walkway' across the site provides both visual paving interest and links a number of benches surrounded by planting.

PROTECTION OF EXISTING VEGETATION

Existing vegetation to be retained on site shall be protected where necessary during works by 2300mm high mesh panel fencing secured to a scaffold tubing framework with fluorescent tape to the top rail. Protective fencing shall be erected on the canopy drip line wherever possible. Laminated, waterproof A4 signs shall be fixed to the fence posts at 10m intervals bearing the words 'PROTECTED TREE ZONE - NO STORAGE OR OPERATIONS WITHIN FENCED AREA'.

Tracking of machinery, storage of chemicals and building materials shall not be permitted within the protected area. Leaks or spills should be removed immediately and the contaminated soil replaced. No bonfires shall be lit within 5m of the canopy spread. Any excavation work beneath the canopy spread shall be carried out by hand. All works affecting trees within the development shall be subject to BS 5837:2012.

TREE PLANTING

Planting of semi-mature trees at key points within the new square will create a structure to the site and add focal, vertical elements within the predominantly hard landscape. As the trees mature, they will also allow for shade to some of the designated seating areas.

Species to be chosen from but not limited to:

- Acer platanoides 'Laciniatum' (Ap)
- Prunus avium 'Plena' (PaP)
- Amelanchier lamarckii (Al)
- Quercus robur 'Fastigiata Koster' (QrFK)
- Betula pendula (Bp)
- Sorbus aria 'Majestica' (SaM)
- Carpinus betulus (Cb)
- Tilia cordata 'Green Spire' (TGs)

SHRUB PLANTING

A contemporary planting scheme utilising a mix of evergreen, deciduous shrubs and swmps of herbaceous planting and grasses will be planted throughout the site to provide year round interest through form, foliage and colour.

Species to be selected from but not limited to: () density/m2

- Berberis frikartii 'Amstelveen' (5), Berberis thunbergii 'Atropurpurea Nana' (5), Berberis cordifolia 'Silberlicht' (6), Ceanothus thrysiliflorus repens (4), Cornus alba 'Sibirica' (2), Cornus stolonifera 'Flaviramea' (2), Cytisus 'Allgold' (4), Elaeagnus pungens 'Maculata' (3), Escallonia 'Apple Blossom' (4), Euonymus fortunei 'Emerald Gaiety' (6), Euphorbia griffithii 'Fireglow' (5), Festuca spp (6), Geranium 'Johnson's Blue' (4), Hebe albicans 'Red Edge' (4), Hebe 'Autumn Glory' (4), Juniperus sabina 'Tamariscifolia' (3), Lavandula 'Hidcote' (6), Lonicera 'Maygreen' (4), Miscanthus spp. (4), Nepeta faassenii (4), Perovskia 'Blue Spire' (6), Phormium var. 'Potentilla 'Red Ace' (5), Prunus laurocerasus 'Zabeliana' (3), Pyracantha 'Orange Charmer' (3), Rubus x 'Betty Ashburner' (4), Spiraea 'Gold Flame' (4), Viburnum tinus 'Eve Price' (3)

Rev E:	Tree grilles and litter bins and kerbs added (CS)	Oct 22
Rev D:	Tree codes and shrub bed numbers added (CS)	Oct 22
Rev C:	Market stall position amended. Electricity points added and planting adjusted around trees T1 and T2 (CS)	Oct 22
Rev B:	Layout amends to client requirements (CS)	Aug 22
Rev A:	Play equipment added, timber uprights removed (CS)	Jul 22

<p>Sue Farmer BA MAID MLI Landscape Architect</p> <p>fdalandscape</p> <p>Westleigh Hall Wakefield Road Denby Dale Huddersfield HD8 8QJ telephone 01484 861611 fax 01484 861616 isdn 01484 866900 email info@fdalandscape.co.uk www.fdalandscape.co.uk</p>	client	
	Barsley Metropolitan Borough Council	
	project	
	Heart of Goldthorpe Town Square Redevelopment GOLDTHORPE	
drawing title		
LANDSCAPE LAYOUT		
scale	date	drwn by
1:200/A1	Jun 22	CS
		drawing no
		R/2608/1E