

N O T E S

K E Y

- Proposed Storm Water Manhole
- Proposed Storm Water Sewer
- Foul Water Manhole
- Proposed Foul Water Sewer

Notes

- Drainage runs shown are approximate and are subject to change at detailed design stage.

- No trees to be planted within 5m of drainage.

- All levels and pipe sizes are approximate and may vary at detailed design stage.

Drainage Design Criteria Design parameters are based on the latest information available and may be subject to change at detailed design and planning approval stage	
Climate Change Allowance (%)	30%
Urban Creep (%)	0%
CV Values (Summer/Winter)	0.75/0.84

Rev	By	Date	Revision	Apvd
G	MI	21.04.26	Updated to suit revised layout received 14.04.2026	MI
F	MI	17.02.26	Updated to layout received 12.02.26	MI
E	MI	26.01.26	New laterals added out of ExS5 & ExF5	MI
D	MI	11.12.25	MH's added to bend, off site sewer route changed	MI
C	MI	03.12.25	Updated to suit revised layout SI-02C	MI
B	CR	20.06.25	Updated to suit revised layout	MI
A	MI	28.05.25	Updated to suit revised layout and outfalls	MI
/	MI	20.05.25	Issued for approval	MI

ARP ASSOCIATES
Chartered Consulting Engineers
Northwest House ● 5 & 6 Northwest Business Park ● Servia Hill, Leeds ● LS6 2QH
☎ 0113 245 8498 🖷 0113 244 3864 ✉ leeds@arpassociates.co.uk 🌐 www.arpassociates.co.uk
ARP Associates is a trading division of ARP Geotechnical Ltd, a company registered in England and Wales with company number 3771811, whose registered office is at 5/6 Northwest Business Park, Servia Hill, Leeds LS6 2QH

TITLE
DRAINAGE FEASIBILITY

PROJECT
WHITE HART ROAD,
PENISTONE

CLIENT
BELLWAY HOMES YORKSHIRE

DRAWING STATUS
PRELIMINARY

Scale	Date	Drawn	Chk.
1:500 @ A1	MAY 25	MI	MI

Drg. No. 0172/85/SK01 Rev G