

Control of Noise & Dust

- The Project will be registered with the Considerate Constructors Scheme
- All work of a potentially noisy nature to be carried out Mon – Fri between 0730 – 1730 hrs
- Water to be sprayed over materials that are likely to generate dust during any construction process
- A wheel wash & road sweeper to be constantly engaged during the removal of materials from site
- All deliveries to be timed to avoid peak traffic flows in the immediate area where practical
- Ambient noise levels to be recorded prior to any construction phase commencing
- Noise to be monitored and recorded at regular intervals from fixed points over the whole area of the Project whilst any construction work is taking place
- Immediate neighbours to be contacted and given contact numbers of site management
- Contact numbers of site management team to be clearly displayed on hoardings to enable the swift resolution of any complaint in respect of noise or dust
- The store to be able to contact construction management team to resolve any complaints arising from construction phases
- Tool box talks to advise on the suppression of noise & dust during construction process's