

NOTE:
ALL DIMENSIONS MUST BE CHECKED ON SITE AND NOT SCALED FROM THIS DRAWING.

COPYRIGHT:
THIS DRAWING IS THE PROPERTY OF THE COMPANY AND MAY NOT BE COPIED, USED OR DISCLOSED FOR ANY PURPOSE EXCEPT AS AUTHORISED IN WRITING BY THE COMPANY.

MAIN WORDING ON SIGNS IN GREEN
WAVE UNDER IN RED.
SIGN BACKING IN WHITE, POWDER COATED ALUMINIUM.
MAIN BUILDING IN CREAM COLOURED RENDER.

Main Sign construction.
15830mm x 1200mm - 2mm Powder coated white satin Aluminium sign with 50mm returns. Vinyl Costcutter logos applied in Pantone 343 (Green) and 032 (Red) as per attached sheet. Troughlights for full length Bright LED's Consumption rate of 4.8W / 305mm run. With a brightness of 1950 Lumens. Rearward shining onto Fascia with a 120 degree beam angle.


Mock Windows.
2080mm wide x 8080mm High . In 4mm Polycarbonate with Digital Graphics applied. Framework is 30mm Silver anodised aluminium.



Front entrance doors and windows to have Pilkingtons
Soft coated low E glass with a U value of 1.8 or better.

MAIN ELEVATION
1:50.

RECEIVED
23 Dec 2005
COSTCUTTER
BARNSELEY

REV.	DATE	AMENDMENT
CLIENT MR R. FORD TA. COSTCUTTER DODWORTH.		
TITLE APPLICATION FOR SIGNAGE TO COSTCUTTER SUPERMARKET. BARNSELEY ROAD DODWORTH BARNSELEY. S15 3JR		
 P. Dimelow B.A. honrs Dip Arch. M.A. Architectural Design and Planning Consultant		
Ash Barn Finkle Street Wortley Sheffield S35 7DH 0114 2894937		
SCALE 1/50/1/200/1:20	DATE DECEMBER 05	DRAWN P.D
DRAWING No. RFD - 1200 - 2.		REV.