



FalcoQuarter

The FalcoQuarter shelter has specifically been developed for our English counterpart Falco UK. The decision was also recently taken to introduce this product into the Dutch market. A great plus is the enormous volume inside that can be used with measurements of 2.10 metre deep and 2.10 metre high. Combined with the advantage of a number of standard production lengths of 2, 3, 4 and 5 metres this shelter is bound to become popular.

The name FalcoQuarter evolved from the shape of the sidewalls of the shelter which form a quarter of a circle. The shelter is manufactured from robust 60x60mm box section tube with a roof construction of 60x40mm box section and supporting posts also out of 60x60mm tube mounted on base plates in 120x100mm sheet. The construction is designed to be bolted onto a concrete pad or onto Falco prefab concrete blocks. The outside covering of the shelter is completed in 4mm thick clear polycarbonate which is fixed to the frame with special clamps. The construction can be powder coated in any standard RAL colour. This shelter can be used as a smoking shelter, bus shelter or cycle shelter. The FalcoQuarter is a flexible, modular shelter with all the practical advantages you would expect from a Falco product.

