



Proposed Site Plan
1:250

Soft Landscape Areas			
Plan view	Description	Comments	
	AG	Proposed amenity grass. Outside planning boundary	
	Mix01	Proposed native shrub mix. Ref. to Planting table	
	Mix02	Proposed ornamental shrub mix. Ref. to Planting table	
	Mix03	Slope stabilising shrub mix. Ref. to Planting table	
	Mix04	Proposed biodiversity-rich planting mix. Ref. to Planting table	
	Mix05	Proposed herbaceous SUDS-friendly planting. Ref. to Planting table	
	WFM	Proposed wildflower mix. Ref. to Planting table	

Planting table									
Proposed Hedgerow	Size Height, cm	Cr m	No. / sq.m	Root/Pot Size	Notes	Mix %	Area sq.m	Total Quantity	
Conocarpus plectata	60-90	0.45	5	2L	Full-pot - min 5 breaks	100%	33	33	165
TOTALS						100%	33	33	165
Mix 01 Proposed native shrub mix	Size Height, cm	Cr m	No. / sq.m	Root/Pot Size	Notes	Mix %	Area sq.m	Total Quantity	
Rosa canina	40-60	0.9	3	bare-root	2 years transplants	40%	272	816	
Rosa europaeus	60-90	0.58	3	bare-root	2 years transplants	20%	153	465	
Liquidum vulgare	40-60	0.58	3	bare-root	2 years transplants	15%	115	340	
Viburnum opulus	60-90	1.41	0.5	bare-root	2 years transplants	15%	115	87	
Alnus galli	40-60	0.58	3	bare-root	2 years transplants	10%	77	230	
TOTALS						100%	680	1150	
Mix02 Proposed ornamental mix	Size Height, cm	Cr m	No. / sq.m	Root/Pot Size	Notes	Mix %	Area sq.m	Total Quantity	
Potentilla fruticosa 'Sunset'	20-25	0.7	2	2L	Full-pot - min 5 breaks	20%	162	325	
Salix purpurea	20-25	0.8	3	2L	Full-pot - min 5 breaks	15%	122	365	
Bergenia 'Abendsglut'	20-30	0.5	4	1L	Full-pot	15%	122	487	
Bedfordia spicata	20-30	0.8	3	2L	Full-pot - min 5 breaks	10%	81	244	
Geranium macranthum 'Bevan's Variety'	15-30	0.4	5	1	2 years transplants	10%	81	406	
Sarcococca confusa	60-90	0.5	4	2L	Full-pot - min 5 breaks	5%	41	162	
Naucleria 'Lime Marmalade'	20-30	0.5	4	1L	Full-pot	5%	41	162	
Lonicera maackii	20-30	0.4	5	1	2 years transplants	5%	41	233	
Polystichum scolopendrium	40-60	0.5	4	1	3 years transplants	5%	41	162	
Skimmia japonica 'Nymans'	60-90	0.5	4	2	2 years transplants	5%	41	162	
Vincetoxicum	60-90	0.4	5	Full pot 8x8 cm	Full-pot	5%	41	233	
TOTALS						100%	812	1674	
Mix03 Proposed slope stabilising mix	Size Height, cm	Cr m	No. / sq.m	Root/Pot Size	Notes	Mix %	Area sq.m	Total Quantity	
Potentilla fruticosa 'Sunset'	40-60	0.7	2	2L	Full-pot - min 5 breaks	25%	69	137	
Comus sanguinea 'Amp's Winter Orange'	40-60	0.8	3	2L	2 years transplants	20%	59	165	
Skimmia japonica 'Nymans'	40-60	0.5	4	1L	2 years transplants	15%	41	165	
Vincetoxicum	20-30	0.5	4	9 cm pot	1 year transplants	15%	41	165	
Bergenia 'Abendsglut'	20-30	0.5	4	1L	2 years transplants	10%	27	110	
Cytisus scoparius	40-60	0.5	4	1L	2 years transplants	10%	27	110	
Hedera helix	20-30	0.4	6	9 cm pot	1 year transplants	5%	14	82	
TOTALS						100%	275	931	
Mix04 Proposed biodiversity-rich mix	Size Height, cm	Cr m	No. / sq.m	Root/Pot Size	Notes	Mix %	Area sq.m	Total Quantity	
Rosa canina	40-60	1	1	bare-root	2 years transplants	20%	153	153	
Comus sanguinea	40-60	1	1	bare-root	2 years transplants	20%	153	153	
Alnus galli	40-60	0.71	2	bare-root	2 years transplants	20%	153	306	
Crataegus monogyna	40-60	1.41	0.5	bare-root	2 years transplants	10%	77	38	
Viburnum opulus	40-60	1.41	0.5	bare-root	2 years transplants	10%	77	38	
Conocarpus plectata	40-60	0.71	2	bare-root	2 years transplants	10%	77	153	
Prunus spinosa	40-60	1.41	0.5	bare-root	2 years transplants	5%	38	19	
Corylus avellana	40-60	1.41	0.5	bare-root	2 years transplants	5%	38	19	
TOTALS						100%	766	1078	
Mix05 Herbaceous SUDS-friendly mix	Size Height, cm	Cr m	No. / sq.m	Root/Pot Size	Notes	Mix %	Area, sq.m	Total Quantity	
Salix officinalis 'Purpurea' / Purple sage	10-15	0.41	6	pot 9x9 cm	Full pot	20%	31	180	
Alum 'Purple Sensation' Ornamental onion	10-15	0.41	6	pot 9x9 cm	Full pot	15%	23	140	
Leucanthemum vulgare 'Oxeye daisy'	10-15	0.41	6	pot 9x9 cm	Full pot	15%	23	140	
Reseda autumnalis/Autumn moor grass	10-15	0.41	6	pot 9x9 cm	Full pot	16%	16	93	
Alum 'Sensation' Mount 'Sensation' Ornamental	10-15	0.41	6	pot 9x9 cm	Full pot	10%	16	93	
Hedera kosterensis/Argentea variegata	10-15	0.41	6	pot 9x9 cm	Full pot	10%	16	93	
Alnus repens/Bugle	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47	
Chionodoxa purpurea/Purple cornflower	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47	
Foeniculum vulgare/Fennel	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47	
Rosmarinus officinalis/Rosemary	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47	
TOTALS						100%	155	467	
WFM Wildflower meadow mix	Rate g/ sq.m					Mix	Total area, sq.m	Total Quant., kg	
Emergent seeds EMF Basic General Purpose Meadow Mixture (to TGA quality standards)					4	100%	4032	16	
TOTALS						100%	4032	16	
AG Amenity grass	Rate g/ sq.m					Mix	Total area, sq.m	Total Quant., kg	
Geminal A18 Road Verge and Embankments					40	100%	101	4	
TOTALS						100%	101	4	

This document is © Bond Bryan Architects Ltd. If in doubt ASK. Drawing measurements shall not be obtained by scaling. Verify all dimensions prior to construction. Immediately report any discrepancies on this document to the Originator. This document shall be used in conjunction with associated models, specifications and related consultant documents.

Key plan

North

0 10 20 30m

1:500

Legend

- Total curtilage including adopted highway
- Developable area
- North-Eastern Highways Area*
- Electrical cable easement areas
- Proposed hard surfaces
- Proposed trees. Ref: to BALU-BBA-YAP-XX-DR-L-2001 - Soft Landscape Strategy (1 of 2)
- Existing vegetation. Ref: to Arboricultural Impact Assessment & Preliminary Arboricultural Method Statement by Thompson Consultancy
- Existing vegetation to remain
- Existing vegetation. Root Protection Area

P02 Stage 4 Issue AF SR 10/02/2025

P01 Issued for Planning, Stage 3 TT SR 16/07/2024

Rev	Description	Drawn	Checked	Date

B

BOND BRYAN

e: info@bondbryan.co.uk
w: www.bondbryan.co.uk

Barnsley Metropolitan Borough Council

BARNESLEY

Metropolitan Borough Council

Currie & Brown

Barnsley Levelling Up Fund

Youth Zone Activity Park

Soft Landscaping Strategy, Planting Plan and Schedule

Originator project ref: 2304B
Scale(s): 1:250
Paper size: A0

Purpose of Issue: For information
Revision description: Preliminary

project originator	volume level	type	role	number	revision
BALU-BBA-YAP-XX-DR-L-2002					P02

www.bondbryan.co.uk