

[illegible]

- Note:**
For all proposed trees centred in a location within 3.0m of the prospectively adoptable highway, root barrier membranes are to be installed on the tree side along the back edge of the highway boundary and are to extend a minimum of 3.0m in each direction from a point at its intersection with a perpendicular line drawn from the highway boundary to the tree trunk. Where a root barrier on the highway boundary strikes a driveway, footpath or other area of handstanding within a plot/POS then the remaining length of root barrier should extend back along the edge of the handstanding into the plot/POS. Root barriers are to extend to a depth of 1000mm

Indicates an embankment. Max gradient 1 in 2 but typically 1 in 3.

Indicates a masonry retaining wall. Retained height as indicated

REV	DESCRIPTION	SIG	CHK	DATE
A	First Issue.			
B	Revised to suit latest site layout and latest proposed highway levels. External works amended to suit.	RJ	CH	07.03.16
C	Basin layout and levels amended to suit latest drainage proposals. External works amended to suit.	RJ	CH	16.02.17
D	Revised to suit latest site layout. External works amended to suit.	DK	CH	15.08.17
E	External works to Phase 1 build plots reviewed and amended as required.	RJ	CH	04.09.17
F	External works reviewed and amended as required.	RJ	CH	20.11.17
G	External works amended to suit clients comments. FFL's to Plots 257-260 and associated garages amended.	RJ	CH	06.02.18
H	basin access track levels updated. Highway barrier replaced by Marshall's Bollards along Road 4.	GH	CH	19.07.18

SHEET 09 OF 09

EOP

APPROVAL

DRAWN	CHECKED	DATE	DRAWING NUMBER	REV
RJ	CH	11.12.15	39094/014	N