Peter Thompson M.B.I.A.T.
Architectural Design Consultant Ltd.
Tel & Fax: 01226 201391
Mobile: 07973 251730
e-mail: peter-thompson@hotmail.co.uk

PROPOSED ELECTRICAL CONTRACTORS
DEPOT & OFFICE
OAKWELL LANE
LANDSCAPE SPECIFICATION

Linwood
Barnsley Road
Dodworth
Barnsley S75 3JR

General Notes and Specification

TOPSOIL

Topsoil to be to B.S. 3882 pH to be 6.0 to 7.0 with low stone and clay content good crumb structure and organic content. Minimum depths to be 150mm to turfed areas and 450mm to shrub beds and 600mm to tree pits.

Before top soil is spread ensure that the subsoil / sub grade is well broken up by mechanical means to form effective drainage and aid development of the the soil structure.

Compacted hard-core, clay etc. is to be dug out and replaced with on-site subsoil as available or imported subsoil to suit. Topsoil is to be cultivated to a depth of 300mm and all stone, debris etc. brought to the surface and removed from site.

plant quantities given as indication only - main contractor is entirely responsible for accurate quantities

PLANTS

Plants are generally to be as indicated on this plan all planting is to be into cultivated topsoil, incorporating T.P.M.C. or fertiliser as specified. After planting all beds are to be cleared, tidied and levelled and an ornamental grade bark mulch, nominal 25-50mm grade 50mm thickness, spread over all shrub beds.

All labels are to be removed, all damaged growth removed and all leggy growth carefully pruned back. Mulch is to be carefully applied around shrubs. All shrubs are to be pit planted into prepared topsoil as specified.

All shrubbed areas and grassed banked areas are to be under planted with a selection of bulbs including Daffodil, Crocus, Snowdrop and Tulip.

SHRUBS SCHEDULE

A. Sarcococca humilis
B. Berberis x media 'Parkjuweel
C. Pyracantha 'Mohave'
D. Pyracantha 'Golden Sun
E. Skimmia japonica 'Rubella
F. Chaenomeles x superba 'Rowllane
H. Euonymous 'Emerald n' Gold
I. Spiraea 'Snowmound'
J. Mahonia aquilfolium 'Apollo'