

DRY STONE WALL

WORK BANK LANE

DRY STONE WALL

RELATIVE TO ADJOINING LANE & GROUND. HEIGHT VARIES BETWEEN 1400-1500MM

3600

BET. GATE POSTS 5000 CLEAR OPENING

2850 EXISTING

2150 PROPOSED

STONE EDGING TO THE TARMAC

REMOVE SECTION OF DRY STONE WALL, SHOWN DOTTED. MAKE GOOD. INSTALL TIMBER GATE POST AND 5-BAR TIMBER GATE - SAME HEIGHT AND DESIGN AS EXISTING.

T1

CHAPEL

NOTE: EXISTING WATER SUPPLY PIPE TO TOILETS ROUTED UNDER THE AREA TO BE TARMACED.

REMOVAL OF 3 TREES T2, T3 AND T4 ONLY.

OT2

TARMAC FINISH
225 TYPE 1 SUB-BASE
50 BINDER COURSE
20 MM GRANITE-GRAVEL FILLED EDGE STRIP AGAINST WALLING.

EXTG. STONE PAVINGS

TARMAC UP TO THE EXISTING PATH

DRY STONE WALL

SPACE FOR PARKING 2 CARS FOR DISABLED PERSONS.

OT3

T4

STONE PAVINGS INCREASED TO 1200MM WIDTH. AND SLIGHT RAMP TO ELIMINATE STEP AT POSITION (X)

GRAVEL FILLED TRENCH AS SOAKAWAY FOR CARPARK SURFACE WATER.

STONE EDGING TO THE TARMAC

TIM ABBOTT
07918 656326
timothyabbott1@icloud.com

PROVIDENCE BAPTIST CHAPEL
ING BIRCHWORTH RD. THURLESTONE
S36 9QN SCALE 1:100 17/10/2023

WIDENING OF EXISTING VEHICLE ACCESS ETC FOR DISABLED PERSONS

4

REV A
January 2024