


## KEY

| | |
|---|---|
| 66.200 * | Proposed Level. |
| FOE | Flag on edge retaining. |
| RW | Masonry Retaining Wall. To be Highway Authority approved when within 3.6m of adoptable Highway. |
| DDPC | Double damp proof course |
| (5) | Facing Brickwork courses below DPC |
| 1/106 ⇨ | Approx drive/path/garden gradient |

| RISK ASSESSMENT: SIGNIFICANT RISKS THAT CANNOT BE DESIGNED OUT | | SUGGESTED ACTION |
|---|---|---|
| RISK | LEVEL OF RISK (H/M) | |
| DEEP EXCAVATIONS ASSOCIATED WITH DEEP DRAINAGE WORKS | HIGH | ENSURE ALL EXCAVATIONS HAVE ADEQUATE TRENCH SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS. |
| HANDLING LARGE DIAMETER MANHOLE AND SOAKAWAY RINGS | HIGH | USE CORRECT LIFTING EQUIPMENT AND ENSURE OPERATIVES WEAR THE CORRECT PERSONAL PROTECTIVE EQUIPMENT. |
| CONTACT WITH SEWEAGE/WORKING IN CONFINED SPACES | MEDIUM | USE GAS DETECTORS/BREATHING EQUIPMENT AND ENSURE OPERATIVES WEAR THE CORRECT PERSONAL PROTECTIVE EQUIPMENT. |
| NOISE FROM MACHINERY | MEDIUM | OPERATIVES TO WEAR THE CORRECT EAR PROTECTION. |
| EXCAVATIONS NEAR TO UTILITIES | HIGH | UTILITY MAPS TO BE INSPECTED AND APPARATUS LOCATED USING APPROPRIATE EQUIPMENT PRIOR TO EXCAVATION. |
| EXCAVATIONS IN PUBLIC HIGHWAY | HIGH | ENSURE ALL EXCAVATIONS HAVE ADEQUATE TRENCH SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS. ENSURE THE CORRECT SIGNAGE/TRAFFIC CONTROL IS USED. |
| IT IS ASSUMED THAT WORKS ASSOCIATED WITH THIS DESIGN WILL BE UNDERTAKEN BY A PERSON(S) WHO ARE COMPETENT AND HAVE THE REQUIRED LEVEL OF EXPERIENCE AND EXPERTISE. | | |

Preliminary

| Rev | Details | Date | Drwn | Chk. |
|---|---|---|---|---|
| C | Plots 8-14 amended | 28-3-19 | AST | |
| B | Plot 40 amended | 22-3-19 | AST | |
| A | Amended following comments from PC | 14-3-19 | AST | |

Partner Construction

Foulstone School Phase 2
Darfield, Barnsley

External Works
Sheet 1

Dwg No. : STE/19/03/03/01 C

Date : 25-1-19

Scale : 1:200

Copyright © Shaun Tonge Engineering

SHAUN TONGE ENGINEERING
11 Broomhead Road. Wombwell. Barnsley. S73 0SA.
Tel 01226 755929. Mobile 07528 278070 . Email Shauntongeengineering@yahoo.co.uk

A1