


DOUBLE GATE

SINGLE GATE

SINGLE & DOUBLE GATE

- NOTES SPECIFIC TO 1800MM HIGH WALLS/GATES/PILLARS
1. PILLARS TO BE REINFORCED AS PER DETAIL ON DRAWING NO. 06 & 07. COMPLETELY INFILLED WITH CONCRETE AS WORK PROCEEDS ENSURING NO VOIDS.
  2. GATE POSTS TO BE 75x75MM FOR SINGLE GATE ONLY, AND 100x100MM FOR DOUBLE & SINGLE GATES OR DOUBLE GATES.
  3. SEE DRAWING NO. 06 & 07 FOR GENERAL SPECIFICATIONS FOR WALLS, PIERS, FENCING AND GATES.

REV A 1/5/09  
PIERS TO EITHER SIDE OF VEHICULAR GATES OMITTED

 <p><b>BARN斯LEY</b> Metropolitan Borough Council Property &amp; Procurement Alan White Assistant Executive Director Springfield House, Springfield St Barnsley S70 6HH Tel. 01226 774300 Fax. 01226 774399</p>		<p><b>PROJECT</b> GREEN CORRIDOR IMPROVEMENTS ROYSTON</p>		<p><b>DRAWING</b> WALL &amp; GATE OPTIONS CORONATION AVE</p>	
Drawn	ab	Date	March 09	Scale	1:50
Project Code	HSG 4097	Drawing No.	08	Revision	A