



EXISTING DRAINED AREA HATCHED IN BLUE  
 ADDITIONAL DRAINED AREA HATCHED ORANGE

Linwood

EXISTING FOUL WATER  
 OUTFALL FROM SITE  
 TO BE RETAINED

EXISTING SURFACE WATER  
 OUTFALL FROM SITE  
 TO BE RETAINED

ALL EXISTING AND PROPOSED SURFACE WATER  
 DRAINAGE TO BE TAKEN INTO ATTENUATION TANK.  
 TANK CAPACITY TO BE 56CU M OF CELLULAR BLOCKS  
 (BASED ON 95% VOID RATIO.  
 HYDROBREAK DEVICE ON TANK OUTLET TO LIMIT DISCHARGE TO  
 13.3LIT/SEC

NEW FOUL DRAINAGE

NEW S.W. DRAINAGE



ARCHITECTURAL SERVICES

Project:  
 PROPOSED RETAIL DEVELOPMENT  
 CASTLE VIEW, DODWORTH,  
 BARNSELY S75 3LF

Drawing  
 Title:  
 DRAINAGE

OFFICE ONE,  
 34 VICTORIA ROAD,  
 BARNSELY,  
 S70 2BU

Phone: 01226 208482

Email: [info@whiteaguspartnership.co.uk](mailto:info@whiteaguspartnership.co.uk)  
 Web: [www.whiteaguspartnership.co.uk](http://www.whiteaguspartnership.co.uk)

Client:  
 FORD PROPERTIES LTD

Date:  
 OCT 2020

Scale:  
 1:200@ A3

Ref.  
 17-183

Dwg. No.  
 07

Rev.

Date	Suffix	Description	Date	Suffix	Description