

Penistone Cricket Club New Pavilion (2024/0583) - Landscaping Plan



KEY:

-  Area around new pavilion to be rolled and seeded to return to grass to match playing area.
-  Soil to be removed from banking (17.4 M cubed) and area to be rolled and seeded with grass to match playing area.
-  Hedgerow and trees to be planted 35m x 2m along boundary wall

HEDGEROW:

Hedgerow to consist of Beech, Blackthorn and Hawthorn at 45cm intervals (offset)  
Small trees to consist of Silver Birch and Grey Willow. Plant height to vary from 40cm to 1m.

NOTE1 : All existing trees and hedgerows on site will remain untouched (or removed) as documented in the Arboricultural Report and Impact Assessment (Aug 2023) and Arboricultural Method Statement (Aug 2023) submitted as part of the planning application 2024/0583

NOTE2 : There is no proposed Hard Landscaping as part of this development as driveway to car park and car park all ready exist. Area around new pavilion to be return to grass as per existing pavilion.