

APPENDIX 1 - SCHEDULE OF PROPOSED TREE WORK

INFORMATION PROVIDED IN SUPPORT OF APPLICATION FOR CONSENT TO FELL 7NO.SYCAMORE TREES, CROWN RAISE & CROWN CLEAN BOUNDARY TREES AT 2 HEMINGFIELD ROAD WOMBWELL BARNSLEY

T8: Sycamore (*Acer pseudoplatanus*)
DBH: 0.25
Height: 13.0
Crown spread: 10
Age: Semi mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments: Poorly positioned resulting in pronounced crown bias to north. Location compromises adjacent tree T9

Recommendation: Remove for arboricultural management reasons and replant in area highlighted at appendix 3.

T35: Beech (*Fagus sylvatica*)
DBH: 0.3
Height: 16.0
Crown spread: 10
Age: Early mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments: Poorly positioned resulting in pronounced crown bias to north. Location compromises adjacent tree T34.

T50: Sycamore (*Acer pseudoplatanus*)
DBH: 0.4
Height: 20.0
Crown spread: 9
Age: Early mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments: Reasonable condition, though presently competing with better tree T49. Removal would aid development of T49.

Recommendation: Remove for arboricultural management reasons and replant in area highlighted at appendix 3.

T61: Sycamore (*Acer pseudoplatanus*)
DBH: 0.25
Height: 19.0
Crown spread: 7
Age: Early mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments:

Reasonable form, though noticeably thin crown due in part to earlier suppression. Removal specified to aid realignment of existing drive.

Recommendation: Remove for arboricultural/property management reasons and replant in area highlighted at appendix 3

T63: Sycamore (*Acer pseudoplatanus*)
DBH: 0.35
Height: 17.0
Crown spread: 9
Age: Early mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments: Poorly positioned resulting in pronounced bole & crown bias to north over adjacent highway. Removal would aid development of T65.

Recommendation: Remove for arboricultural management reasons and replant in area highlighted at appendix 3

T68: Sycamore (*Acer pseudoplatanus*)
DBH: 0.35
Height: 18.0
Crown spread: 11
Age: Early mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments:

Reasonable condition, though presently competing with equally good trees. Removal would aid development of T65 & T67.

Recommendation: Remove for arboricultural management reasons and replant in area highlighted at appendix 3

T73: Sycamore (*Acer pseudoplatanus*)
DBH: 0.25
Height: 18.0
Crown spread: 4
Age: Early mature
Vigour: Normal
Visual amenity value: Poor

Condition/comments: Drawn pole type tree, competing with T74.
Removal would aid development of T74.

Recommendation: Remove for arboricultural management reasons and replant in area highlighted at appendix 3

T83: Sycamore (*Acer pseudoplatanus*)
DBH: 0.6
Height: 19.0
Crown spread: 11
Age: Mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments:
Very poor condition having suffered longstanding fire damage on main stem at a height of 0.5-2m. Decay also evident at root collar.

Recommendation: Remove for arboricultural management reasons and replant in area highlighted at appendix 3

T90: Sycamore (*Acer pseudoplatanus*)
DBH: 0.3
Height: 19.0
Crown spread: 8
Age: Early mature
Vigour: Normal
Visual amenity value: Moderate

Condition/comments:
Reasonable form, though removal specified to aid necessary level changes associated with construction of garage & neighbouring footpath.

Recommendation: Remove for arboricultural/property management reasons and replant in area highlighted at appendix 3