



SURFACE FINISHES

- DBM CARRIAGEWAY
30mm AC10 DENSE SURF 100/150
- BLOCK PAVED SHARED SURFACE
60mm PCC BLOCKS
- BLOCK PAVED RAMP
60mm PCC BLOCKS
- DBM FOOTWAY / DRIVE CROSSING
25mm AC6 DENSE SURF 160/220
- PERMEABLE PRIVATE DRIVE
60mm PCC BLOCKS
- PCC TACTILE PAVING FLAGS
400 x 400 x 65mm (BUFF)

KERB TYPE DETAILS

- 100 125 x 255mm PRECAST CONCRETE
HALF BATTERED KERB WITH 100mm FACE
- 25 125 x 150mm PRECAST CONCRETE BULLNOSED
KERB WITH 25mm FACE
- 100C 125 x 255mm PRECAST CONCRETE HALF BATTERED
KERB WITH 100mm FACE AND CHANNEL BLOCK
- 25C 125 x 150mm PRECAST CONCRETE BULLNOSED
KERB WITH 25mm FACE AND CHANNEL BLOCK
- 0-6C 125 x 150mm PRECAST CONCRETE BULLNOSED
KERB WITH 0-6mm FACE

TRANSITION KERB TO BE POSITIONED AS SHOWN,
BETWEEN DIFFERING KERB FACE HEIGHTS AT
DRIVEWAY CROSSINGS, PEDESTRIAN CROSSINGS
AND SHARED SURFACES.

6/25mm TR 100mm

NOTE:
1. MINIMUM 4 DROP KERBS PER SINGLE DRIVE
2. MINIMUM 6 DROP KERBS PER DOUBLE DRIVE

P1	24.11.23	Preliminary Issue	GW	PB	PB						
Issue	Date	Description	By	Chkd	Appd						
<div>COAST CONSULTING ENGINEERS</div> <p>7 Silvertown Court, Northumberland Business Park, NE23 7RY 0191 5977879</p> <p>Client</p> <p>CAMSTEAD HOMES</p> <p>Job Title</p> <p>HOYLAND BARNSELEY</p> <p>Drawing Title</p> <p>SURFACE FINISHES & KERB LAYOUT</p> <p>Scale at A1</p> <p>1:500</p> <p>Drawing Status</p> <p>PRELIMINARY</p> <table><tr><td>Job No</td><td>23085</td><td>Drawing No</td><td>51</td><td>Issue</td><td>P1</td></tr></table>						Job No	23085	Drawing No	51	Issue	P1
Job No	23085	Drawing No	51	Issue	P1						