



Street Lighting Arrangement

N 'x' Proposed new 6M galvanised steel column with AriaLed 40 lantern complete with electronic PEC and 14 metres cable (N denotes new column 'x' denotes number)

NOTES:-

- The symbols used on this drawing to show Street Lighting Column Positions have been enlarged for clarity and are not to scale.
- All setting out and exact positions to be agreed on site by Barnsley Council Street Lighting Section prior to start. Allow at least 2 clear working days to attend site.
- Street Lighting Columns shall only be planted in the ground (1.0m deep) once Kerbs and Edgings (Pin Kerb) have been installed establishing both line and level (or walls to rear of footways have been built) and the ground construction is up to (and including) sub-base level.
- All disconnections and connections of new Street Lighting Columns to be co-ordinated by the principal contracgtor

B SA	drawing rev V	15/2/23	
A SA	columns added	16/5/22	
Rev	By	Revision Details	Date
 BARNSELEY Metropolitan Borough Council			
Project Bleachcroft Way Section 38 Works Harron Homes			
Title Street Lighting Proposals			
Scale 1:500	Drawn SGA	Checked	Date 15/2/23
A1	Drawing No. SL20-78_1300_1_Rev B	Rev B	