



Crown copyright and database rights. (2015) Ordnance Survey 0100031673

Provide a new foul drain, from the sewer in Shortwood Court to the front car park of Capital Compactors existing unit. The sewer and road are unadopted. Excavate up to the existing foul sewer approximately 3m. into the road and across the grass verge to the front boundary of the unit to install a 150mm. drain. The road will be backfilled with M.O.T type 1 stone and the tarmac reinstated as existing. The works will be carried out to N.R.S.W.A. standards. 450mm diameter I/C within Capital Compactors boundary. The drain will be 150mm diameter upvc at a depth of 750-900mm. subject to the location of any other underground services, with granular bed and surround and concrete slab protection as required in the road.

For further information please contact:

Andy McLean
Contracts Director
Jet Aire (DC) Ltd
Northways Court,
Great North Road,
Aberford,
Leeds LS25 3AU.

Tel: 0113 393 5500
Mob: 07831 388744
Email: andy@jetaire.co.uk
Web: www.jetaire.co.uk



MIDBROOK HOUSE, INTAKES LANE,
TURNDITCH, ASHBOURNE,
DERBYSHIRE, DE56 2LU
TEL: 01335 370128
WWW.MIDBROOKBUILDINGS.CO.UK
SALES@MIDBROOKBUILDINGS.CO.UK

CONSTRUCTIONLINE	HAS	LABC
REV	DATE	INT.
A	09/03/15	JV
UPDATED DETAIL		
DETAIL		

CLIENT	CAPITAL COMPACTORS
PROJECT	SHORTWOOD BUSINESS PARK BARNSELEY HOYLAND S74 9LH
TITLE	DRAINAGE DETAILS
SCALE: 1:500 @ A4	06/03/2015 Drg 04
	A