

Contaminant	Phytotoxicity			
	pH	pH	pH	pH
	5.0 to 5.5	5.5 to 6.0	6.0 to 6.5	>7.0
Arsenic	50			
Cadmium	3			
Chromium	400			
Lead	300			
Mercury	1			
Nickel	50	60	75	110
Copper	80	100	135	200
Zinc	200	200	200	300

The assessment concentration for lead is the Category 4 Screening Level produced by Contaminated Land: Applications in Real Environments (CL:AIRE) and outlined in Appendix H of their report SP1010. The others have been taken from Nathanail, C. P., McCaffrey, C., Gillett, A., Ogden, R., and Nathanail, J., 2015, *'The LQM/CIEH S4ULs for Human Health Risk Assessment'*, Land Quality Press, Nottingham. The metals/metalloids are based on a sandy loam soil and 6% soil organic matter. The assessment values are not intended to be applied to individual sample results where materials are similar, as the levels of contaminants will have a natural variability across the site. Instead, the modified mean value should be compared with the assessment concentration.

The assessment values for phytotoxicity are the levels at which plant growth is thought to be affected. They are taken from the maximum permissible and advisable concentrations in soil after application of soil sludge given in the *'The Code of Good Agricultural Practice for the Protection of Soil'*, MAFF, 1998.

The assessment of sulphate, water soluble sulphate, elemental sulphur and sulphide is to determine the aggressive nature of the ground with respect to concrete and consequently the results are compared with BRE Special Digest 1:2005 *'Concrete in Aggressive Ground'*.

Copyright Land Quality Management Limited reproduced with permission; Publication Number S4UL3153. All rights reserved.

Prepared	KDL	Checked	CAT	Date	03.11.15	Job No	38208
-----------------	-----	----------------	-----	-------------	----------	---------------	-------

 Eastwood & Partners <small>CONSULTING ENGINEERS</small> St Andrew's House 23 Kingfield Road Sheffield S11 9AS Tel: (0114) 255 4554 Fax: (0114) 255 4330	DUCHY HOMES NETHERMILL FARM, BARNSELEY ROAD, PENISTONE ASSESSMENT CRITERIA – RESIDENTIAL WITH HOMEGROWN PRODUCE
---	--

TPH Fraction	Intended Land Use Residential (mg/kg)		
	1% SOM	2.5% SOM	6% SOM
Aliphatic EC 5-6	42	78	160
Aliphatic EC >6-8	100	230	530
Aliphatic EC >8-10	27	65	150
Aliphatic EC >10-12	130 (48) ^{vap}	330 (118) ^{vap}	760 (283) ^{vap}
Aliphatic EC >12-16	1100 (24) ^{sol}	2400 (59) ^{sol}	4,300 (142) ^{sol}
Aliphatic EC >16-35	65,000 (8.48) ^{f, sol}	92,000 (21) ^{f, sol}	110,000 ^f
Aliphatic EC >35-44	65,000 (8.48) ^{f, sol}	92,000 (21) ^{f, sol}	110,000 ^f
Aromatic EC 5-7	70	140	300
Aromatic EC >7-8	130	290	660
Aromatic EC >8-10	34	83	190
Aromatic EC >10-12	74	180	380
Aromatic EC >12-16	140	330	660
Aromatic EC >16-21	260 ^f	540 ^f	930 ^f
Aromatic EC >21-35	1,100 ^f	1,500 ^f	1,700 ^f
Aromatic EC >35-44	1,100 ^f	1,500 ^f	1,700 ^f

^f oral, dermal, and inhalation exposure compared with oral HCV

^{sol} S4UL presented exceeds the solubility saturation limit, which is presented in brackets

^{vap} S4UL presented exceed the vapour saturation limit, which is presented in brackets

The assessment criteria for each of the petroleum hydrocarbon fractions have been taken from Nathanail, C. P., McCaffrey, C., Gillett, A., Ogden, R., and Nathanail, J., 2015, *'The LQM/CIEH S4ULs for Human Health Risk Assessment'*, Land Quality Press, Nottingham. These are also all based on a sandy loam soil.

Within the Environment Agency Science Report P5-080/TR3, Askari, K. & Pollard, S., 2005 *'The UK Approach for Evaluating Human Health Risks from Petroleum Hydrocarbons in Soils'* it is stated that the assessment values should not be considered individually; instead the potential additive effects should be calculated. This is achieved by calculating an individual Hazard Quotient (HQ) for each fraction. The HQ is the proportion of the assessment concentration represented by the recorded concentration. The HQs are then added together to form a Hazard Index (HI) and where this exceeds unity a potential significant risk to human health may exist.

Copyright Land Quality Management Limited reproduced with permission; Publication Number S4UL3153. All rights reserved.

Prepared	KDL	Checked	CAT	Date	03.11.15	Job No	38208
-----------------	-----	----------------	-----	-------------	----------	---------------	-------

<p>EOP Eastwood&Partners CONSULTING ENGINEERS St Andrew's House 23 Kingfield Road Sheffield S11 9AS Tel: (0114) 255 4554 Fax: (0114) 255 4330</p>	<p>DUCHY HOMES</p> <p>NETHERMILL FARM, BARNSELEY ROAD, PENISTONE</p> <p>ASSESSMENT CRITERIA – RESIDENTIAL WITH HOMEGROWN PRODUCE</p>
--	---