



Sahara Buff



Technical data

Production Plant	Denton
Production Method	extruded wirecut
Pack Quantity	400
Length x Width x Height	215 x 102.5 x 65 mm
Size Tolerance	T2
Range Tolerance	R1
Gross Dry Density	1460 kg/m ³
Compressive Strength	>=50 N/mm ² (EN 771-1)

Thermal Conductivity	0,690 W/(m·K) (EN 1745:2012: S1)
Durability Designation	F2 (EN 771-1)
Water Absorption	<=10 % (EN 771-1)
Reaction to Fire	A1 class
Active Soluable Salts	S2



Find a stockist

Have a question?

The content provided is correct as of date of printing. (Please see top-left corner) Due to the colour constraints of printing processes, the product colour may not be truly represented.