




REFERENCE	TYPE/ FINISH	LOCATION	SUPPLIER	PRODUCT REF	DESCRIPTION	PRODUCT/ SUPPLIER LINK	IMAGE
T01	Bitumen macadam	Access routes			To Enginner's specification		
HS01	Block paving	Paving areas 1 and 2	Tobermore or similar approved	Fusion	Setts 100x100x80 mm Fusion Silver 100%	<a href="https://www.tobermore.co.uk/professional/products/block-paving/fusion/">https://www.tobermore.co.uk/professional/products/block-paving/fusion/</a>	
HS02	Block paving	Paving areas 1 and 2	Tobermore or similar approved	Fusion constellations Libra	Slabs 300x200x80 mm Product 1: Fusion Silver Product 2: Fusion Mid Grey Product 3: Fusion Graphite	<a href="https://www.tobermore.co.uk/professional/constellations/fusion-constellations/?constellation=carina">https://www.tobermore.co.uk/professional/constellations/fusion-constellations/?constellation=carina</a>	
HS03	Impact attenuation surface	Surface of the parkour area and the banked edge between the skate park and the access road.	Tiger mulch or similar approved	Autumn	Surface to comply with BSEN117 and BS7188	<a href="https://www.tigermulch.co.uk/">https://www.tigermulch.co.uk/</a>	
HS04	Concrete slab				Omitted		
HS05	Hazard warning paving	Top and bottom of staircase at station side entrance	Marshalls or similar approved	Corduoy Paving Colour - Buff	It should be installed at 90 degrees and 400mm from any potential hazards & DDA compliant. 400mmx400mmx50mm+5mm	<a href="https://www.marshalls.co.uk/commercial/product/tacole-hazard-warning-paving">https://www.marshalls.co.uk/commercial/product/tacole-hazard-warning-paving</a>	
HS06	Concrete surface of the activity zone	Activity zone			To be determined buy the specialist designer		
SOE	Slab on edge wall	Stair areas	Tobermore or similar approved	Mayfair step slabs	Colour: Silver Size 400x400x40	<a href="https://www.tobermore.co.uk/professional/products/steps/mayfair-step-slabs/">https://www.tobermore.co.uk/professional/products/steps/mayfair-step-slabs/</a>	
PS	Proposed precast step units with contrasting nosing	Stairs	Tobermore or similar approved	Mayfair Edge Step Mayfair Riser	Colour: Silver Step size 400x400x40 mm Riser size 400x170x40 mm	<a href="https://www.tobermore.co.uk/professional/products/steps/mayfair-step-slabs-contrasting-nosing/">https://www.tobermore.co.uk/professional/products/steps/mayfair-step-slabs-contrasting-nosing/</a>	

SURFACE FINISHES

REFERENCE	TYPE/ FINISH	LOCATION	SUPPLIER	PRODUCT REF	DESCRIPTION	PRODUCT/ SUPPLIER LINK	IMAGE
Edging	PK1	Precast concrete edging			To Engineer's specification		
	K, DK	HB2 Kerb, half battered			To Engineer's specification		
Fencing and barriers	F01-1.2	1.2 m high flat top pedestrian guardrails/ barriers	Parkour area	IAE or similar approved	Pedestrian Guardrails Panels manufactured to BS 1722 Part 9. Panels with 16 mm diameter solid rod infills. Additional intermediate supports for panels to prevent sagging. For all elements - Hot Dip Galvanising to BS EN ISO 1461 Finishing - Polyester Powder Coated <b>Colour: RAL 6005, Moss green</b> Method of setting posts: Root or plate fixed foundations to comply with the design loading requirements.	<a href="https://iae.co.uk/product-fencing/pedestrian-guardrails/">https://iae.co.uk/product-fencing/pedestrian-guardrails/</a>	
	F01-1.8	1.8 m high flat top pedestrian guardrails/ barriers	North East access	IAE or similar approved	Pedestrian Guardrails Panels manufactured to BS 1722 Part 9. Panels with 16 mm diameter solid rod infills. Additional intermediate supports for panels to prevent sagging. For all elements - Hot Dip Galvanising to BS EN ISO 1461 Finishing - Polyester Powder Coated <b>Colour: RAL 6005, Moss green</b> Method of setting posts: Root or plate fixed foundations to comply with the design loading requirements.	<a href="https://iae.co.uk/product-fencing/pedestrian-guardrails/">https://iae.co.uk/product-fencing/pedestrian-guardrails/</a>	
	F02	1.8 m high flat top pedestrian guardrails/ barriers on cranked posts	Wildlife area, access points	IAE or similar approved	Pedestrian Guardrails Panels manufactured to BS 1722 Part 9. Panels with 16 mm diameter solid rod infills. Additional intermediate supports for panels to prevent sagging. For all elements - Hot Dip Galvanising to BS EN ISO 1461 Finishing - Polyester Powder Coated <b>Colour: RAL 6005, Moss green</b> Method of setting posts: Root or plate fixed foundations to comply with the design loading requirements. <b>Cranked posts</b>	<a href="https://iae.co.uk/product-fencing/pedestrian-guardrails/">https://iae.co.uk/product-fencing/pedestrian-guardrails/</a>	
	F03	Knee-high barrier 0.5 m high	Secondary access points	IAE or similar approved	Contractor's choice Steel SHS post and rail. For all elements - Hot Dip Galvanising to BS EN ISO 1461 Finishing - Polyester Powder Coated <b>Colour: RAL 6005, Moss green</b> Method of setting posts: Root or plate fixed foundations to comply with the design loading requirements	<a href="https://iae.co.uk">https://iae.co.uk</a>	
	F04	Knee-high barrier 0.5 m high	Area north from the activity area	Contractor's choice	Contractor's choice Posts: Treated to calss 4 softwood Rails: Treated to calss 3 softwood		
	G1	Kissing gate	Pedestrian and authorised service access Entrance to Mottram Way	GL Jones or similar approved	Hot Dip Galvanising - Standard Anti-Motorcycle Motorised Wheelchair / Pushchair Friendly Self Closing Side Panels Unlock to Allow Large Vehicle Access	<a href="https://www.gljones-playgrounds.co.uk/playground-equipment/kissing-gates/36m-wide-self-closing-kissing-gate-with-accessible-padlock-detail">https://www.gljones-playgrounds.co.uk/playground-equipment/kissing-gates/36m-wide-self-closing-kissing-gate-with-accessible-padlock-detail</a>	
	G2,3	Gate	Wildlife area, gates access to Harborough hill road	First Fence or similar approved	1.8m High x 2.5 m Wide EnviroRail® Flat Top Double Leaf Gate Kit	<a href="https://firstfence.co.uk/enviro-rail-1-8m-high-5-0m-wide-double-flat-top-railling-gate-kit?uk=true&amp;qad_source=1&amp;qclid=CjwKCAiA2JG9BhAuEiwAH_zf3sPwWfPF19l8imXQvWpo1-vV5VYPLWasuXfl_Z2oUUcbzPvLIBLv2gRoCxbwQAvD_BwE">https://firstfence.co.uk/enviro-rail-1-8m-high-5-0m-wide-double-flat-top-railling-gate-kit?uk=true&amp;qad_source=1&amp;qclid=CjwKCAiA2JG9BhAuEiwAH_zf3sPwWfPF19l8imXQvWpo1-vV5VYPLWasuXfl_Z2oUUcbzPvLIBLv2gRoCxbwQAvD_BwE</a>	
	G4	Gate	Wildlife area, gates access to Harborough hill road	First Fence or similar approved	1.2m High x 1.2 m Wide EnviroRail® Flat Top Single Leaf Gate Kit	<a href="https://firstfence.co.uk/plysecure-1-0m-x-1-2m-wide-single-gate-kit">https://firstfence.co.uk/plysecure-1-0m-x-1-2m-wide-single-gate-kit</a>	

REFERENCE	TYPE/ FINISH	LOCATION	SUPPLIER	PRODUCT REF	DESCRIPTION	PRODUCT/ SUPPLIER LINK	IMAGE
KB	K barrier	Pedestrian and accessible access Entrance points, limiting use of unauthorised motorcycles/ quads	K Barriers or similar approved	Dual adjustment K barrier	Barrier gates choice for managed / controlled entry <b>Colour: RAL 6005, Moss green</b>	<a href="https://www.kbarriers.co.uk/dual-adjustment/">https://www.kbarriers.co.uk/dual-adjustment/</a>	
HR	Handrail to external steps	Entrance steps handrails	Contractor's choice	Contractor's choice	Stainless or galvanised steel	Stainless or galvanised steel	

REFERENCE	TYPE/ FINISH	LOCATION	SUPPLIER	PRODUCT REF	DESCRIPTION	PRODUCT/ SUPPLIER LINK	IMAGE
S01	Round Bar Seat	Southern part of the park	Lightman or similar approved	LMRBS201	Dimensions: 1800mm length 870mm height 550mm depth For all elements - Hot Dip Galvanising to BS EN ISO 1461 Finishing - Polyester Powder Coated <b>Colour: RAL 1023, Traffic yellow</b> Method of setting posts: Root fixed	<a href="https://www.lightmain.co.uk/portfolio-items/round-bar-seat/">https://www.lightmain.co.uk/portfolio-items/round-bar-seat/</a>	
S02	Concrete curved bench	Canopy area	Bailey Street Scene or similar approved	Roosevelt Planter	L: 1168mm D: 300mm H: 450mm Dia : 3000mm Weight: 288kg Colour: Natural Fixings: Freestanding	<a href="https://www.baileystreetscene.co.uk/roosevelt-planter">https://www.baileystreetscene.co.uk/roosevelt-planter</a>	
PS	Picnic seat	Canopy and social area	Lightman or similar approved- with wheelchair accessibility	LMFPT100	Dimensions: 1500mm length 820mm height 1440mm depth For all elements - Hot Dip Galvanising to BS EN ISO 1461 Finishing - Polyester Powder Coated <b>Colour RAL 5010, Gentain blue</b> Method of setting posts: Root fixed	<a href="https://www.lightmain.co.uk/portfolio-items/flat-bar-picnic-table/">https://www.lightmain.co.uk/portfolio-items/flat-bar-picnic-table/</a>	
SC	Steel canopy	Seating area	Bailey Streetscene or similar approved	STADIUM CANOPY	Height varies of individual canopies <b>Colour: RAL 5010, Gentain blue</b>	<a href="https://www.baileystreetscene.co.uk/stadium-canopy">https://www.baileystreetscene.co.uk/stadium-canopy</a>	
IB	Freestanding interpretation display and signage	Spread over the park	Fitzpatrick Woolmer or similar approved	Cavalier™ interpretation display or similar approved	Height up to 2.2 m to accommodate a screen of up to A0 format Foundations per supplier's instructions <b>Colour: RAL 6005, Moss green</b>	<a href="https://www.FWDP.co.uk">https://www.FWDP.co.uk</a>	
RS	Road sign	Entrance points	Contractors's choice	Contractors's choice	Signage to be confirmed	Contractor's choice	
RB	Retractable bollards	NE site entrance	Autopa or similar approved	138 100 647Y	Square Removable Bollard 750 Above Ground 120mm x 120mm Galvanised & Yellow - Removable Equipped with BMBC district padlock	<a href="https://www.autopa.co.uk/products/vehicle-control-parking/removable-posts/square-removable-post/">https://www.autopa.co.uk/products/vehicle-control-parking/removable-posts/square-removable-post/</a>	
CS	Cycle stand	Cycle Stand	Broxap or similar approved	Broxap Sheffield Stand	Stainless Steel cycle stand, root fixed Tube profile: 48.3mm dia tube, width: 715mm, height: 800mm a/g, 400mm b/g- to include tapping bars.	<a href="https://www.broxap.com/sheffield-tapping-bar.html">https://www.broxap.com/sheffield-tapping-bar.html</a>	
LB	Litter Bin	Sitewide	MLB/224R Eco Metal Litter & Recycling Bin in black with gold lettering	Galvanized inner-bin	Dimensions: Overall Height- 955mm Width-485mm Depth- 910mm Weight- 83kg, (224 litres), gold letter plated, with smoking tray and dog waste integrated, ground fixed <b>Colour: RAL 9005, Jet black</b>	<a href="https://wybone.co.uk/product/mlb224r-eco-metal-litter-and-recycling-bin/">https://wybone.co.uk/product/mlb224r-eco-metal-litter-and-recycling-bin/</a>	 MLB/224R Eco Metal Litter & Recycling Bin

STREET FURNITURE